THROCKMORTON

SAM HOUSTON

DAVY CROCKETT

PETERS COLONY

BOURN STREET

SOUTH GOLIAD (S.H. 205)

EMMA JANE

DICKEY

LINE 'A' 6" WW

LINE 'B' 6" WW

N

0 20 40 60 80
SCALE IN FEET

CONTRACTOR TO VERIFY THE LOCATION & ELEVATION OF EXISTING WASTEWATER LINE PRIOR TO CONSTRUCTION OF ALL WASTEWATER LINES

CUT & PLUG EX. 6" WW MAIN UPON COMPLETION OF PROP. 6" WW MAIN

6+45 LINE 'B' CONSTRUCT 4" WW SERVICE

5+68.94 LINE 'B'= PAV. STA. 2+20, 9.5' RT. EMMA JANE CONSTRUCT 4' DIA. MANHOLE TOP = 572.19

5+50 LINE 'B' CONSTRUCT 4" WW SERVICE

PROP. 6" WATER (SEE SHT. U-1)

CONSTRUCT CLEANOUT ON EX. 6" WW MAIN

EX. 6" WW MAIN TO BE ABANDONED

3+98 LINE 'B' CONSTRUCT 4" WW SERVICE

4+74 LINE 'B' CONSTRUCT 4" WW SERVICE

4+90 LINE 'B' CONSTRUCT 4" WW SERVICE

3+38.31 LINE 'B'= PAV. STA. 4+51.16, 9.5' RT. EMMA JANE CONSTRUCT 4' DIA. MANHOLE TOP = 568.94 CONSTRUCT 4" WW SERVICE CONNECT TO EX. SERVICE

CUT & PLUG EX. 6" WW MAIN UPON COMPLETION OF PROP. 6" WW MAIN

ABANDON EX. MANHOLE UPON COMPLETION OF PROP. 6" WW MAIN

(SEE SHT. U-1) PROP. 6" WATER

3+04 LINE 'B' 4" WW SERVICE ADDED DURING CONSTRUCTION

2+74 LINE 'B' CONSTRUCT 4" WW SERVICE

1+97 LINE 'B' CONSTRUCT 4" WW SERVICE CONNECT TO EX. SERVICE

CUT & PLUG EX. 4" WW LATERAL UPON COMPLETION OF PROP. 6" WW MAIN

EX. 4" WW LATERAL TO BE ABANDONED

1+08 LINE 'B' CONSTRUCT 4" WW SERVICE

1+30 LINE 'B' CONSTRUCT 4" WW SERVICE

(SEE SHT. U-1) PROP. 6" WATER

6+01 LINE 'B' CONSTRUCT 4" WW SERVICE CONNECT TO EX. SERVICE

7+67.90 LINE 'B'= PAV. STA. 0+67.76, 39.0' LT. EMMA JANE CONSTRUCT 4' DIA. MANHOLE TOP = 573.70 CONNECT TO EX. 6"WW

7+19.40 LINE 'B'= PAV. STA. 0+67.76, 9.5' RT. EMMA JANE CONSTRUCT 4' DIA. MANHOLE TOP = 573.27 CONSTRUCT 10 LF 6" WW MAIN TO WEST & CAP F.L. 6" 565.69

℄ PIPE LINE 'B' CURVE DATA Δ= 13°55'58" R= 290.50' T= 35.50' L= 70.64'

PC 1+53.92 LINE 'B' PT = 6+53.24 LINE 'B' PT

PT 2+26.02 LINE 'B' PC = 5+62.60 LINE 'B' PC

℄ PIPE LINE 'A' CURVE DATA Δ= 3°20'15" R= 200.00' T= 5.83' L= 11.65'

0+00 LINE 'A'= 6+40.15 LINE 'A' BOURN ST. CONNECT TO EX. MANHOLE

INSTALL 50 LF OF 6" PVC WASTEWATER MAIN & 12" STEEL ENC. PIPE BY OTHER THAN OPEN CUT

CUT & PLUG EX. 4" WW LATERAL UPON COMPLETION OF PROP. 6" WW MAIN

PC 0+50.51 LINE 'A'= PAV. STA. 9+71.15, 19.84' RT. DAVY CROCKETT

PT 0+62.16 LINE 'A'= PAV. STA. 9+59.50, 19.50' RT. DAVY CROCKETT

0+82 LINE 'A' CONSTRUCT 4" WW SERVICE

1+54 LINE 'A' CONSTRUCT 4" WW SERVICE CONNECT TO EX. SERVICE

2+10 LINE 'A' CONSTRUCT 4" WW SERVICE CONNECT TO EX. SERVICE

3+31 LINE 'A'= 0+00 LINE 'B'= PAV. STA. 6+90.66, 19.5' RT. DAVY CROCKETT CONSTRUCT 4' DIA. MANHOLE TOP = 556.70

3+98 LINE 'A' CONSTRUCT 4" WW SERVICE CONNECT TO EX. SERVICE

4+03 LINE 'A'= PAV. STA. 6+18.66, 19.5' LT. DAVY CROCKETT END 6" WASTEWATER MAIN CONSTRUCT CLEANOUT

CUT & PLUG EX. 4" WW MAIN UPON COMPLETION OF PROP. 6" WW MAIN

CONSTRUCT CLEANOUT ON EX. 4" WW MAIN

NOTES:

1. VERIFY ELEVATION OF EXISTING WASTEWATER MAINS PRIOR TO CONSTRUCTION OF PROPOSED WASTEWATER MAIN.
2. VERIFY LOCATION & ELEVATION OF EXISTING WASTEWATER LATERALS PRIOR TO CONSTRUCTION OF PROPOSED WASTEWATER MAIN.

RECORD DRAWINGS FEBRUARY 5, 1999
THIS RECORD DOCUMENT HAS BEEN PREPARED BASED IN PART UPON INFORMATION FURNISHED BY OTHERS. THE DESIGN PROFESSIONAL CANNOT ASSURE THE ACCURACY OF OTHERS' INFORMATION AND THUS IS NOT RESPONSIBLE FOR THE ACCURACY OF THIS RECORD DOCUMENT OR FOR ANY ERROR OR OMISSION THAT MAY HAVE BEEN INCORPORATED INTO IT AS A RESULT. THOSE RELYING ON THIS RECORD DOCUMENT ARE ADVISED TO OBTAIN INDEPENDENT VERIFICATION OF ITS ACCURACY BEFORE APPLYING IT FOR ANY PURPOSE.

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY KENNETH A ROBERTS, P.E. 55446 ON MAY 7, 1998

STATE OF TEXAS
KENNETH A ROBERTS
55446
REGISTERED
PROFESSIONAL ENGINEER
5/7/98

2 RECORD DRAWING 2/5/99

1 ADDENDUM #2, 5/28/98

WASTEWATER PLAN

EMMA JANE STREET
DAVY CROCKETT
CITY OF ROCKWALL, TEXAS

Huitt-Zollars, Inc./Consulting Engineers
Dallas, Fort Worth, Houston, Phoenix, Austin, El Paso, Ontario, Albuquerque

DESIGN	DRAWN	APPR.	SCALE	DATE	PROJECT NO.	NO.
HZI	HZI	KAR	1"=40'	MAY 98	01226201	U-2

h:\proj\01226201\dgn\2262WT02.DGN

h:\proj\01226201\dgn\2262WT02.DGN
Plot Date: 8-10-2001 09:59
User Name: MILLER
Intersso
PRF 60141(ON)90.000000
F:\WTMILLER.TBL
Pl: 2262BASE.DGN, I-3,5,7,10-13,14-21,23,25-27,30,31,33-41,43-50,52,53
C: 2262CONT.DGN, I-19,24
I: 2262INTER.DGN, I-1,2,4-6,8,9,12,22,28,29,32,42,51,54-61
U: 2262UTIL.DGN, I-16,18-21,23-31,33-41,43-50,52-63
TI: CITYOP.DGN, I-11,51-52,64-83
P1: 2262BASE.DGN, 22
P3: 2262PAV.DGN, 24