



CONTROL COORDINATES

Node ID	Northing	Easting	Node ID	Northing	Easting	Node ID	Northing	Easting	Node ID	Northing	Easting
600	7012671.40	2587977.91	624	7012291.45	2587929.98	648	7012363.81	2588012.81	672	7012631.09	2587891.50
601	7012648.32	2587966.70	625	7012299.73	2587904.75	649	7012342.73	2588006.95	673	7014390.10	2590728.87
602	7012597.86	2587952.26	626	7012315.01	2587883.13	650	7012323.82	2587997.32	674	7012639.30	2587857.37
603	7012571.51	2587953.78	627	7012334.83	2587865.74	651	7012968.42	2587959.96	675	7012639.69	2587866.22
604	7012546.16	2587961.11	628	7012357.61	2587852.55	652	7012960.76	2587934.54	676	7012648.61	2587865.48
605	7012523.07	2587973.89	629	7012411.49	2587839.34	653	7012945.18	2587913.05	677	7012648.33	2587856.48
606	7012503.27	2587991.06	630	7012437.77	2587840.13	654	7012923.41	2587897.87			
607	7012482.98	2588006.79	631	7012463.58	2587845.13	655	7012897.85	2587890.69			
608	7012460.55	2588019.27	632	7012488.26	2587854.21	656	7012871.36	2587892.29			
609	7012436.49	2588028.22	633	7012511.16	2587867.13	657	7012846.84	2587902.52			
610	7012411.34	2588033.48	634	7012531.83	2587883.04	658	7012827.05	2587920.23			
611	7012385.73	2588034.99	635	7012553.48	2587896.82	659	7012811.77	2587941.16			
612	7012360.20	2588032.49	636	7012577.03	2587907.00	660	7012925.02	2587874.24			
613	7012335.56	2588025.62	637	7012601.92	2587913.37	661	7012900.85	2587862.74			
614	7012288.00	2588002.51	638	7012598.95	2587932.30	662	7012875.20	2587858.53			
615	7012277.74	2587977.31	639	7012568.14	2587934.06	663	7012849.04	2587861.59			
616	7012271.23	2587956.10	640	7012538.49	2587942.64	664	7012046.14	2587960.98			
617	7012257.30	2587933.57	641	7012511.49	2587957.59	665	7012043.86	2587943.29			
618	7012240.18	2587917.13	642	7012489.86	2587976.23	666	7012037.15	2587935.88			
619	7012212.95	2587902.57	643	7012471.96	2587990.10	667	7012044.56	2587929.16			
620	7012183.58	2587897.04	644	7012452.18	2588001.11	668	7012051.27	2587936.57			
621	7012126.79	2587912.95	645	7012430.96	2588009.00	669	7012065.02	2587941.03			
622	7012103.93	2587932.03	646	7012408.50	2588013.69	670	7012618.39	2587899.47			
623	7012089.57	2587957.98	647	7012386.08	2588015.00	671	7012628.90	2587901.38			

NOTE: SEE SERIES LM DRAWINGS FOR HARDSCAPE INCLUDED IN THIS CONTRACT

**BENCHMARK:**  
National Geodetic Survey Control, Designation: 0 1498, PID: CS2517, Monumented in 1986, NAD 83: 32 53 24 (N) / 096 29 22 (W).  
3.1 Miles SW from Rockwall, 1.7 Miles southerly along State Highway 205 from its junction with State Highway 66 in Rockwall, Thence 1.45 Miles southwesterly along Interstate Highway 30, set vertically in the north face of the most northerly 1 of 3 columns of the first pier east of the west abutment of the southwest bound highway overpass of Farm Road 740 (exit 67), and 20.7 feet west of the center of the Farm Road. The Mark is 1.4 meters above the Farm Road.  
ELEVATION = 445.31 feet (NAVD 88)

HORIZONTAL CONTROL PLAN						
ROCKWALL WATERFRONT PARK PACKAGE 2						
ROCKWALL, TEXAS						
<b>BROCKETTE • DAVIS • DRAKE, INC.</b> consulting engineers Civil & Structural Engineering - Surveying 4144 North Central Expressway, Suite 1100 • Dallas, Texas 75204 (214) 824-3647 • Fax: (214) 824-7064						
DESIGNED	DRAWN	DATE	SCALE	NOTES	FILE	NO.
TNA	BDD	10/2005	1"=30'	BDD	C03360	C1b