



- NOTES:
1. SOLAR CHARGE CONTROLLER SHALL BE MORNINGSTAR PS-15M 15 amp WITH METER.
 2. CONTROLLER SHALL BE ELTEC TC-18 SCALABLE TIME BASED CONTROLLER.
 3. BATTERY SHALL BE UPG UB-12350.
 4. CONTROLLER CABINET SHALL BE ELTEC NEMA 3R CABINET.
 5. FOUNDATION DIMENSIONS ARE SHOWN MINIMUM AND SHALL BE AS PER MANUFACTURER'S (PELCO) RECOMMENDATIONS.
- ADDITIONAL MANUFACTURER'S DATA SHEETS ARE ATTACHED AS APPENDIX IN PROJECT DOCUMENTS AND SPECIFICATION BOOK.

SIDE ELEVATION

FRONT ELEVATION

CONSTRUCTION NOTES

1. MOUNT DRIVER FEEDBACK SIGN USING $\frac{7}{16}$ " HOLES, 4 EA. TO MOUNT BRACKET TO POLE. WORK SHALL BE COMPLETED IN A WORKMANLIKE MANNER.
2. USE APPROVED DIRTWORK INSTALLATION/DISPOSAL METHODS
3. 2" CLEARANCE BETWEEN FINISH GRADE AND BOTTOM OF BASE PLATE REQUIRED FOR CARRIAGE BOLT INSTALLATION.
4. IF ADDITIONAL CONDUCTORS ARE REQUIRED, USE XHHW, 14 AWG WIRE OR APPROVED EQUIVALENT.
5. ALL TERMINATIONS MUST BE MADE AT TERMINAL BLOCKS. NO WIRE NUTS/SPLICES ALLOWED.
6. RUBBER GROMMETS TO BE INSTALLED AT ALL HOLES TO PREVENT CONTACT OF WIRING AND POLE.

SCHOOL ZONE FLASHER AND SIGN DETAILS

Drawing: P:\PROJECTS\RWL18219\CAD\Sheets\PHASE 1 - NORTH\60 SIGNAGE DETAILS 2 OF 2.dwg at Sep 27, 2019 - 10:45am by jpedalle
Layout: 60 SIGNAGE DETAILS 2 OF 2 - Arsite: wren-jordan.dwg

no.	revision	by	date

teague nall and perkins, inc
 825 Watters Creek Blvd., Suite M300
 Allen, Texas 75013
 214.461.9867 ph 214.461.9864 fx
 www.tnpsc.com
 TBPE: F-230; TBPLS: 10011600, 10011601, 10194381

City of Rockwall
The New Horizon

scale
when bar is
1 inch long
horiz
N/A
vert
N/A
SEP 2019

RECORD DOCUMENTS
 THESE PLANS ARE FOR THE OWNER'S USE AS RECORD SET OF THE CONSTRUCTED PROJECT, AND REFLECT REVISIONS AND CONSTRUCTION RELATED CHANGES AS RECORDED BY THE CONTRACTOR. CHANGES MADE FROM THE ORIGINAL CONSTRUCTION DOCUMENTS DO NOT DEPICT ENGINEERING AND ARE NOT THE RESPONSIBILITY OF TEAGUE NALL & PERKINS, INC. OR THE ENGINEER OF RECORD ON THE ORIGINAL DOCUMENTS. ORIGINAL PLANS RELEASED FOR CONSTRUCTION WERE SEALED BY GYANENDRA POKHREL, P.E. NO. 118159 ON 09/28/2018.

CITY OF ROCKWALL, TEXAS
HIGHLAND DRIVE RECONSTRUCTION, PHASE I
 (DRIFTWOOD STREET TO BEDFORD FALLS LANE)
SIGNAGE DETAILS 2 OF 2

tnp project
 RWL18219
 sheet
58