



VICINITY MAP  
NOT TO SCALE

GENERAL NOTES

1. CONTRACTOR to verify in the field the location of all existing utilities prior to construction. Information provided within these plans does not relieve the contractor of the full and total responsibility for the protection of existing utilities nor any damages caused by said contractor during construction.
2. CONTRACTOR to furnish trench safety plan to the City Engineer prior to construction. See Specification Trench Safety Requirements.
3. CONTRACTOR shall adjust all existing utilities to proposed pavement grade elevation.
4. ALL utility and paving construction shall meet City of Rockwall specifications.
5. ALL water mains to be installed 48-inches below proposed grade.
6. ALL proposed drive approaches shall be extended to right-of-way line except as noted on plans. Drives shall be constructed of 6-inch 3500 P.S.I. concrete reinforced with No. 3 rebars on 24-inch centers each way.
7. ALL existing drainage pipe to be removed and salvaged except as noted on the storm sewer design plans.
8. UTILITY CONTRACTOR shall be responsible for grade to drain inlet openings and culvert discharge sites.
9. PAVING CONTRACTOR to construct handicap curbs at all proposed intersections.

DRAWING INDEX

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	VICINITY MAP, GENERAL NOTES & DRAWING INDEX
3 - 7	PAVING IMPROVEMENTS
8 - 11	STORM SEWER IMPROVEMENTS
12	STORM SEWER PROFILES
13 - 14	WATER & SANITARY SEWER IMPROVEMENTS
15 - 19	TYPICAL DETAILS
1 - 13	CROSS SECTIONS

<b>GENERAL NOTES, VICINITY MAP &amp; DRAWING INDEX</b>	
<b>INDUSTRIAL BOULEVARD</b>	
FROM EXIST. END OF PVMT. TO U.P. R.R. R.O.W.	
<b>CITY OF ROCKWALL</b> "THE NEW HORIZON"	
DESIGNED: B.W.H. DRAWN: B.W.H. JOB NO:	SCALE: NONE APPROVED: <i>[Signature]</i> DATE: 10 / 89 SHEET NO. 2 OF 19

REVISION NO.	REMARKS	DATE