SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	PAVING SHEETS (2) P-1	P-2	P-3	P-4 ORIG. BID	P-5	P-6	P-7	P-8	P-9	UTILITIES ST-3	ST-4	ST-5	ST-6	ST-7	ST-8	ST-9	U-1	U-4	(2) CHANGE ORDER NO. 1	(2) TOTALS
1	BARRICADES & TRAFFIC CONTROL	LS	1																			1
2	REMOVE & DISPOSE OF EX. HMAC PVMT.	SY		950	1235	440	926	998	496	315	798										1419	7,577
3	UNCLASSIFIED STREET EXCAVATION	CY	25	68	612	28	60	67	50	20	51										49	1,029
4	FULL DEPTH SAW CUT	LF	257	467	570	224	500	506	337	152	393	552	58								361	4,377
5	REMOVE EX. CONCRETE PAVEMENT	SY	441	176	232	50	45	172	295		106	279	19								226	2,041 (1)
6	REMOVE EX. CONCRETE SIDEWALK	SF	21	392	335		208	205		35	138											1,334
7	REMOVE EX. SEP. CONC. CURB & GUTTER	LF		743	828	330	700	681	202	245	621										1168	5,518
8	6" LIME STABILIZED SUBGRADE	SY	467	1330	1550	580	1096	1273	826	378	982										1967	10,449
9	HYDRATED LIME (30 LBS./SY)	TON	7	20	24	9	17	19	13	6	15										30	160
10	8" 3600 PSI REINF. CONC. PAVEMENT	SY	441	1200	1450	315	1040	1185	556	352	916	239	19								1792	9,505 (1)
11	6" INTEGRAL CONCRETE CURB	LF	230	670	720	196	677	650	575	245	570	30	20								1176	5,759
12	REINF. CONC. STREET HEADER	LF	56		27	39		30	51	27	27										51	308
13	6" 3600 PSI REINF. CONC. DRIVEWAY	SY		58	165	29	45	111	42		108	20									237	815
14	SEPARATE 24" CONC. CURB & GUTTER	LF			20	120															30	170
15	3600 PSI REINF. CONC. ALLEY PAVEMENT	SY		42	100	21			230				20								42	455
16	4" 3000 PSI REINF. CONC. SIDEWALK	SF	21		350		148	165		35	138											857
17	4" 3000 PSI EXP. AGGR. CONC. SIDEWALK	SF					60	40														100
18	LONGITUDINAL BUTT JOINT	LF	83		24				55													162
19	4" THICK FLEX BASE FOR TEMP. ACCESS	SY		100	285	50	45	105	70		104										107	866
20	4" THICK TYPE B BASE COURSE	SY			27	160															40	227
21	2" THICK TYPE D SURFACE COURSE	SY			27	160															40	227
22	6" THICK TOPSOIL & SOLID SOD GRASS	SY	77	250	250	66	225	217	192	82	190	320	50								280	2,199
23	SPLIT RAIL FENCE	LF	50																			50
24	BLOCK RETAINING WALL	SF			300																	300
25	IRRIGATION MODIFICATIONS	LS	1																			1
26	18" CLASS III RCP	LF															75					75
27	21" CLASS III RCP	LF											31		53	164	11					260
28	24" CLASS III RCP	LF										4	2		359		24	119				508
29	30" CLASS III RCP	LF											264									264
30	36" CLASS III RCP	LF										121	136	400	44		351					1,052
31	42" CLASS III RCP	LF										398										398
32	10' STANDARD INLET	EA											1		2	2	3	1				9
33	15' STANDARD INLET	EA											1									1
34	6 GRATE INLET	EA															1					1
35	MANHOLE	EA										1										1
36	GABION MATTRESS	CY										21										21
37	JUNCTION BOX	CY											16									16
38	CONCRETE FLUME	SF																44				44
39	REMOVE INLET	LF											2					1				3
40	REMOVE PIPE	LF											90									90
41	TRENCH SAFETY - STORMWATER	LF										523	433	400	456	165	462	119				2,557
42	POLLUTION CONTROL	LS										1										1
43	8" PVC WATER	LF																		2384	553	2,937
44	6" GATE VALVE / BOX	EA																		10	1	11
45	8" GATE VALVE / BOX	EA																		14	2	16
46	1" PE WTR SERVICE LINE/TAP/VALVE/BOX	EA																		38	6	44
47	FIRE HYDRANT ASSEMBLY	EA																		6		6
48	REMOVE & DELIVER FIRE HYDRANT	EA																		2		2
49	CONNECT TO EXISTING WATER MAIN	EA																		7	1	8
50	CUT & PLUG EXISTING WATER MAIN	EA																		5	1	6
51	TRENCH SAFETY - WATER	LF																		2384	553	2,937
52	WATER TEST	LS																		1		1
53	8" PVC WASTEWATER	LF																	2280		488	2,768
54	4' DIA. MANHOLE	EA																	14		2	16
55	4" PVC WASTEWATER SERVICE W/CO	EA																	41		4	45
56	REMOVE MANHOLE	EA																	3		1	4
57	TRENCH SAFETY - WASTEWATER	LF																	2280		488	2,768
58	T.V. INSPECTION	LF																	2280		488	2,768
59	WASTEWATER TEST	LS																	1			1
60	TRAFFIC CALMING MEDIAN (ADD ALTERNATE)	LS		1																		1

RECORD DRAWINGS JULY 25, 2003 KAR
THIS RECORD DOCUMENT HAS BEEN PREPARED BASED ON INFORMATION PROVIDED BY OTHERS. THE CONSULTANT HAS NOT VERIFIED THE ACCURACY AND/OR COMPLETENESS OF THIS INFORMATION AND SHALL NOT BE RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY BE INCORPORATED AS A RESULT OF ERRONEOUS INFORMATION PROVIDED BY OTHERS.

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY KENNETH A ROBERTS, P.E. 55446 ON AUGUST 8, 2002

STATE OF TEXAS
KENNETH A. ROBERTS
55446
REGISTERED PROFESSIONAL ENGINEER
8-8-2002

NO.	DATE	REVISIONS	APPROVED
2	11/5/2002	CHANGE ORDER NO. 1	KAR
1	8/19/2002	ADDENDUM NUMBER 1	KAR

QUANTITY SHEET

RIDGE VIEW ADDITION REHAB

HUITT-ZOLLARS
Huitt-Zollars, Inc. Dallas
3131 McKinney Avenue, Suite 600
Dallas, Texas 75204-2489
Phone (214) 871-3311 Fax (214) 871-0757

CITY OF ROCKWALL, TEXAS

DESIGN	DRAWN	APPR.	SCALE	DATE	PROJECT NO.	NO.
HZI	HZI	KAR		AUGUST 2002	01-3018-01	Q-1

h:\proj\01301801\dgn\301801CQS01.DGN

BORDER, 301801QBDR1.DGN, 1,3,4,7,21,26,30,31,40,41,45,47,48,50,61,63 *no ref logical*, *no ref name*, *no ref levels*
h:\proj\01301801\dgn\301801CQS01.DGN
DATE: 07/29/02
TIME: 07:34:25
itheresa
SCALE: 1.0000999800
PRF: ROTATION=270.000000
F:\tbl\HZIFULL.TBL