



UTILITY EXCAVATION &  
EMBEDMENT DETAIL  
N.T.S.

- NOTES:
- PAYMENT TO THE CONTRACTOR FOR REPLACEMENT OF PAVEMENT AND/OR DRIVEWAYS WILL BE BASED ON ACTUAL MEASUREMENTS UP TO A MAXIMUM WIDTH EQUAL TO THE SPECIFIED MAXIMUM TRENCH WIDTH PLUS 2 FEET. ANY EXISTING PAVEMENT DAMAGED OR REMOVED IN EXCESS OF THE MAXIMUM LIMITS SHALL BE AT THE EXPENSE OF THE CONTRACTOR.
  - WHEN REMOVING CONCRETE PAVEMENT, THE CONTRACTOR SHALL ENDEAVOR TO LIMIT DAMAGE TO EXISTING REINFORCEMENT SO IT MAY BE EMPLOYED IN THE REPLACEMENT OPERATION. IF ORIGINAL REINFORCEMENT IS CUT OR BROKEN, REPLACEMENT BARS OF THE SAME SIZE SHALL BE INSTALLED BY DRILLING AND DOWELLING AS DIRECTED BY THE OWNER.

- NOTE:
- THE GENERAL CONTRACTOR AND ALL SUB-CONTRACTORS SHALL VERIFY THE SUITABILITY OF ALL EXISTING AND PROPOSED SITE CONDITIONS INCLUDING GRADES AND DIMENSIONS BEFORE COMMENCEMENT OF ANY CONSTRUCTION. IN THE EVENT OF ANY CONFLICT AND PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION IMMEDIATELY NOTIFY ENGINEER. MINOR ADJUSTMENTS OF FINISH GRADE TO ACCOMPLISH SPOT DRAINAGE ARE ACCEPTABLE, IF NECESSARY, UPON PRIOR APPROVAL OF ENGINEER.
  - THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL EXISTING STRUCTURES, UTILITIES, AND SERVICES PRIOR TO EXCAVATION AND CONSTRUCTION.
  - THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING WITH UTILITY COMPANIES FOR THE RELOCATION OF ANY EXISTING UTILITIES.
  - THE CONTRACTOR SHALL USE ALL NECESSARY PRECAUTIONS TO AVOID CONTACT WITH OVERHEAD AND UNDERGROUND POWER LINES.
  - CONTRACTOR SHALL REPLACE ALL SIGNAGE AND MAILBOXES THAT HAVE TO BE REMOVED DURING CONSTRUCTION.
  - CONTRACTOR IS RESPONSIBLE FOR RESTORING EXISTING CONDITIONS TO ALL DISTURBED AREAS (GRASS, PAVING, ROCK, ASPHALT, ETC)
  - LINE "B" (THROUGH THE PARK) THE CONTRACTOR SHALL DEVIATE FROM ORIGINAL ALIGNMENT ONE TO TWO FEET AS NEEDED TO MISS TREES, IF MORE DEVIATION IS NEEDED CONTACT ENGINEER FOR APPROVAL.
  - ALL WATERLINE TO BE C900 CLASS 200 PVC.
  - CONTRACTOR TO FURNISH TRAFFIC CONTROL PLAN.

LINE "B" STA. 20+00 TO 24+74.33	
12" WATER LINE	
ROCKWALL, TEXAS	
CITY OF ROCKWALL "THE NEW HORIZON"	
DESIGNED: A.J.W.	THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY CHARLES A. TODD TEXAS P.E. NO. 55647 ON
DRAWN: ACAD	DATE: 7/29/03 SHEET NO. 4 of 4
JOB NO.	

REVISION NO.	REMARKS	DATE
1.	MOVED WATER LINE	OCT. 31, 2003

