SHEET QUANTITIES

ITEM No.	DESCRIPTION	SHEET	QUANTITIES																	
		UNITS	SHEETS 6-26	6	7	8	9	10	11	12	13	14	15	16	17	18A	18B	19	25	26
1	Unclassified Excavation	CY	16,505	457	1,238	1,573	200	372	542	831	821	1,620	2,107	2,415	181	1,512	532	2,104		
2	Compacted Fill	CY	5,155	890	859	677	1,729	549	189	23	49	20	13	46	0	99	1	11		
3	Right-of-way Preparation	STA	62.6	4.7	5.0	5.0	5.0	5.0	5.0	4.0	3.9	5.0	5.0	5.0	0.3	4.0	1.5	4.2		
4	Remove Existing Concrete Pavement	SY	529		40	18				134				47				290		
5	Remove Existing Concrete Curb & Gutter	LF	230													230				
6	Remove Existing Street Barricade	LF	76		28															
7	Remove Existing Chain Link Fence	LF	356							24	24									
8	Remove Existing Traffic Buttons	LS	0										356							
9	Remove Existing "Y" Inlet	EA	1	1																
10	Remove Existing 15" to 18" Type "B" Headwall	EA	3													3				
11	Remove Existing 24" Type "B" Headwall	EA	1																	1
12	Remove Existing 42" Type "B" Headwall	EA	1																1	
13	Remove Existing Dbl. 42" Type "B" Headwall	EA	1																1	
14	Remove Existing 8" to 15" C.M.P.	LF	294													252		42		
15	Remove Existing 36" R.C.P.	LF	32																	32
16	Remove Existing Concrete Cap	SY	0																	
17	6" Lime Stabilized Subgrade (31 lbs/SY)	SY	6,602		151											2,587	830	3,034		
18	8" Lime Stabilized Subgrade (41 lbs/SY)	SY	20,669	1,536	1,848	1,875	1,469	1,337	1,447	1,328	1,339	1,609	3,336	3,311	234					
19	Hydrated Lime	TON	526.0	31.5	40.2	38.4	30.1	27.4	29.7	27.2	27.4	33.0	68.4	67.9	4.8	40.1	12.9	47.0		
20	6" Reinforced Concrete Street Pavement	SY	312		140											172				
21	8" Reinforced Concrete Street Pavement	SY	24,744	1,444	1,738	1,764	1,357	1,252	1,336	1,215	1,252	1,485	3,127	3,113	226	2,317	796	2,322		
22	6" Reinforced Concrete Drive Approach Pavement	SY	598										143			247		208		
23	6" Reinforced Concrete Curb & Gutter	LF	50											50						
24	6" Non-reinforced Concrete Riprap	SY	0																	
25	Temporary Asphalt Transition Pavement	SY	603															603		
26	Concrete Street Header	LF	116												60			56		
27	4' Wide 4" Thick Reinforced Concrete Sidewalk	SY	2,554	232	216	267	222	210	222	223	209	210	182	161	25	24	69	82		
28	4" Thick Reinforced Colored Concrete Handicap Ramps	SY	140	8	16			18			19		15	15	19	14		16		
29	Median Landscape Maintenance Ramp	EA	8		1	1		1		1	1		1	2						
30	Type 6 Retaining Wall with Integral Sidewalk	CY	23.5										3.6	19.9						
31	4' High Black Coated Chain Link Fence	LF	93										10	83						
32	Median & Parkway Sodding	SY	11,895	1,165	948	865	1,475	569	1,142	916	782	1,225	988	956	10	419	160	275		
33	4" Topsoil & Hydromulch Seed Slopes	SY	8,981	1,071	1,039	1,210	1,036	405	100	146	800	960	583	546	94	404	77	510		
34	Reflectorized Ceramic Pavement Markers (White)	EA	868	42	82	82	52	124	48	96	100	46	92	104						
35	Non-reflectorized Ceramic Pavement Markers (White)	EA	512	42	46	46	52	44	48	52	42	46	50	44						
36	Reflectorized Ceramic Pavement Markers (Yellow)	EA	0																	
37	Non-reflectorized Ceramic Pavement Markers (Yellow)	EA	0																	
38	Yellow Reflectorized 6"x6" Jiggle Tiles	EA	0																	
39	Yellow Reflectorized 8" Traffic Buttons	EA	93										42	51						
40	Stop Bar	EA	10		1						4			1	1	1		2		
41	Crosswalk	EA	11	1	1						4			1	1	1		2		
42	Left Turn Only Arrow	EA	7		1	1		2			2			1						
43	Right Turn Only Arrow	EA	0																	
44	Through Arrow	EA	0																	
45	2" Dove Grey Schedule 40 PVC Conduit for Street Lighting	LF	5,340	437	500	500	500	430	500	500	437	500	501	501	34					
46	3" Dove Grey Schedule 40 PVC Conduit for Traffic Signals	LF	455	64							40			235	116					
47	3" Schedule 40 PVC Conduit for Irrigation	LF	211		68	68								62	13					
48	4" Schedule 40 PVC Conduit for Irrigation	LF	168								56	56		56						
49	Traffic Signal Pullbox	EA	6											3	3					
50	Cyclone Metal Fence (6 Foot Tall)	LF	456										456							
51	Standard Street Barricade	LF	60												60					
52	Adjust Waterline Gate Valve Box to Finished Grade	EA	5											2		3				
53	Adjust Sanitary Sewer Manhole to Finished Grade	EA	3				2	1												
54	18" R.C.P. Storm Drain Pipe Class III	LF	33													33				
55	21" R.C.P. Storm Drain Pipe Class III	LF	0																	
56	24" R.C.P. Storm Drain Pipe Class III	LF	14																	
57	27" R.C.P. Storm Drain Pipe Class III	LF	0																14	
58	30" R.C.P. Storm Drain Pipe Class III	LF	0																	
59	39" R.C.P. Storm Drain Pipe Class III	LF	0																	
60	42" R.C.P. Storm Drain Pipe Class III	LF	359																359	
61	45" R.C.P. Storm Drain Pipe Class III	LF	0																	
62	48" R.C.P. Storm Drain Pipe Class III	LF	0																	
63	36" Rubber Gasket R.C.P. Storm Drain Pipe	LF	0																	
64	39" Rubber Gasket R.C.P. Storm Drain Pipe	LF	481																	0
65	10' Recessed Curb Inlet	EA	1	1																481
66	15' Recessed Curb Inlet	EA	2																	
67	20' Recessed Curb Inlet	EA	0																1	1
68	15' Standard Curb Inlet	EA	0																	
69	3'x3' "Y" Inlet	EA	0																	
70	4'x4' "Y" Inlet	EA	0																	
71	18" Type "B" Headwall	EA	1																	
72	48" Type "B" Headwall	EA	0													1				
73	Special Junction Box No. 1	EA	0																	
74	Convert Drop Inlet into Junction Box	EA	0																	
75	Asphalt Pavement Repair	LF	0																	
76	Make Dry Connection to Existing 6" Water Line	EA	0																	
77	Make Dry Connection to Existing 12" Water Line	EA	0																	
78	6" Water Main	LF	0																	
79	8" Water Main	LF	0																	
80	12" Water Main	LF	0																	
81	8" Gate Valve	EA	0																	
82	12" Gate Valve	EA	0																	
83	8"x8" Tapping Sleeve & 8" Valve	EA	0																	
84	Fire Hydrant Assembly	EA	0																	
85	Cast Iron Fittings	TON	0.0																	
86	Lower 6" Water Main	EA	0																	
87	Lower 12" Water Main	EA	0																	
88	Concrete Encase Water Main	LF	20																	
89	Relocate Existing Water Meter & Water Service	EA	1																	20
90	Trench Safety	LF	841														1			
91	Unreinforced Silt Fence	LF	0																373	468
92	Reinforced Silt Fence	LF	0																	
93	8" High Rock Berm	LF	0																	
94	12" High Rock Berm	LF	0																	
95	18" High Rock Berm	LF	0																	
96	Inlet Treatment	EA	0																	
97	Temporary Asphalt Widening	SY	0																	
98	Concrete Encase 6" Sanitary Sewer	LF	0																	

PREPARED BY:
WIER & ASSOCIATES, INC.
ENGINEERS SURVEYORS LAND PLANNERS
4300 BELTWAY PLACE SUITE 130 ARLINGTON, TEXAS 76018 METRO (817)467-7700
4100 AVON CORRER BLVD. SUITE 200 FORT WORTH, TEXAS 76155 METRO (817)355-9437

SHEET QUANTITIES

STATE OF TEXAS
ULYS LANE III
40864
REGISTERED PROFESSIONAL ENGINEER
12-1-99

COPYRIGHT © WIER & ASSOCIATES, INC.

LAST SHEET EDIT DATE 11-29-99
WA# 97057

SHEET NO. 5A

RECORD PLANS 1-15-02

TIME:14:04 FILE: SHEETQ1.dwg