



CONN. TO EXIST. CONC. PAVING & DOWEL INTO EXIST. PAVING w/ NO. 3 RE-BARS @ 24" CTRS.

CONST. CONC. STREET HEADER ON 3 SIDES OF PROP. CONC. RAMP

Remove & Dispose of 25 L.F. of Exist. 20" C.M.P.

PROPOSED TOP OF CURB ELEVATIONS FOR MEDIANS

T.C.#	ELEVATIONS	T.C.#	ELEVATIONS
1	441.80	20	438.28
2	441.69	21	438.0
3	441.48	22	438.52
4	441.70	23	440.06
5	441.90	24	440.68
6	442.10	25	442.20
7	441.50	26	441.80
8	442.23	27	441.30
9	440.10	28	442.59
10	439.25	29	442.11
11	439.50	30	442.86
12	440.0	31	443.0
13	440.80	32	442.70
14	440.40	33	439.40
15	441.50	34	439.19
16	442.63	35	439.21
17	443.12	36	439.53
18	442.91	37	438.60
19	438.40		

TREE LISTING

1	12" PECAN
2	10" PECAN
3	30" PECAN
4	6" PECAN
5	12" PECAN
6	38" COTTONWOOD
7	30" COTTONWOOD

LEGEND	
SYMBOLS	DESCRIPTIONS
	Proposed Top of Asph. Paving Spot Shots
	Proposed Top of Curb No. for Medians
	Existing Power Poles
	Existing Elevation Above Sea Level
	Proposed Trash Dumpster Pad
	Handicap Parking Spaces (2)
	Proposed 6" Thk. 3500 P.S.I. Reinf. Conc. Paving

NOTES:
 1. ALL UNCLASSIFIED EXCAVATION SHALL BE DISTRIBUTED AND COMPACTED ON SITE TO CONFORM TO THE PROPOSED GRADES.
 2. ALL BORROW MATERIAL REQUIRED SHALL BE DELIVERED ON SITE BY CITY FORCES AND COMPACTED BY THE CONTRACTOR.

B.M. NO.1:
 60d NAIL FND. IN P/P 400' WEST OF LAKESHORE DRIVE & 100' NORTH OF STATE HWY. NO. 66.
 ELEV.=459.17

B.M. NO.2:
 R.R. SPIKE SET IN P/P 50' NORTH OF CENTERLINE OLD HWY. 66 & 50' EAST OF ENTRANCE ROAD TO PARK.
 ELEV.=443.60

GRADING PLAN
ROCKWALL BOATRAMP
 ROCKWALL, TEXAS

CITY OF ROCKWALL
 "THE NEW HORIZON"

REVISION NO.	REMARKS	DATE

DESIGNED: B.W.H.	THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY WL DOUPHRATE II TEXAS P.E. No. 60102 ON MARCH 28, 1991
DRAWN: ACAD	
SCALE: 1" = 40'	
DATE: 3/91	SHEET NO. 3 / 5

