

ITEM NO.	DESCRIPTION	UNIT	UNIT	PV-1	PV-2	PV-3	PV-4	PV-5	PV-6	PV-7	PV-8	PV-9	PV-10	PV-11	PV-12	PV-13	PV-14	PV-15	PV-16	SD-1	SD-2	SD-3	SD-4	SD-5	SD-6	SD-7	SD-8	SD-9	TR-1	TR-2	TR-3	TR-4	TOTAL QUANTITY	
100	Mobilization	LS	Lump Sum																															1.00
101	Preparing Row including Removing Trees, Fences, Etc.	AC	Acres	0.75	0.86	0.86	0.86	1.20	0.86	0.86	0.86	0.86	0.86	1.22	1.26	1.26	1.26	0.15	0.50														14.49	
102	Swatf and Remove Curb & Gutter	LF	Linear Foot	110,000		280,000	55,000	110,000	143,000					48,000																			1,262,000	
103	Remove Exst Reinforced Concrete Pavement Including Curb and Gutter	EA	Each		1.00	1.00							1.00																				3.00	
104	Removal Of Reinforced Concrete Pavement Including Curb and Gutter	SY	Square Yard	222.22		330.00							40.00																				1,950.00	
105	Removal Of MBGF	LS	Lump Sum																														1.00	
106	Remove Pavement Markings	CY	Cubic Yard																														5,290.00	
107	Undersified Roadway Excavation	CY	Cubic Yard																														32,750.00	
108	Compacted Earth Fill	CY	Cubic Yard																														30,342.44	
109	8" Reinf. Concrete Pavement - Roadways	SY	Square Yard	194,958	1388,889	229,778	156,657	274,386	203,778	1388,889	147,778	2000,000	1768,67	2996,00	2777,78	2777,78	2978,00	195,00															15,730.00	
110	4" Reinf. Concrete Pavement - Sidewalk	SY	Square Yard											100,00	12,00					15,730.00													15,730.00	
111	2" Type "D" Asphalt	SY	Square Yard																														15,730.00	
112	4" Type "B" Asphalt	SY	Square Yard																														15,730.00	
113	6"-6x8 (27 Lbs/Sy Min) Lime Stabilized Subgrade (Including Lime)	SY	Square Yard	2144.54	1927.78	2527.56	1723.33	3018.25	2241.56	1927.78	1625.56	2250.00	1864.00	3339.00	3111.00	3111.00	3331.00	214.50	1685.00														35,241.84	
114	Hydrated Lime-68 (27 Lbs/Sy Min)	TN	Ton	28.95	20.53	34.12	23.27	40.75	30.26	20.63	21.95	30.38	23.16	43.08	42.00	42.00	44.97	2.90	22.75														473.76	
115	6" Integral Concrete Curb	LF	Linear Foot	1042.00	1000.00	1295.00	995.00	1065.00	1000.00	1110.00	1070.00	1270.00	1980.00	2000.00	2000.00	2000.00	2000.00	60.00															19,807.00	
116	Median Access Ramp	EA	Each		1.00	1.00		1.00	1.00			2.00	1.00	1.00																			8.00	
117	Brick Pavers	SY	Square Yard	130.00		139.00	69.00		69.00			69.00	35.00	35.00																			581.00	
118	2" Pvc Electrical Conduit	LF	Linear Foot	407.00	550.00	500.00	500.00	555.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00																7,062.00	
119	2" Pvc Electrical Conduit by Bore	LF	Linear Foot							50.00			55.00																				105.00	
120	4" Pvc Conduit	LF	Linear Foot			260.00	120.00		200.00			190.00	120.00	100.00																			1,025.00	
121	4" Pvc Conduit by Bore	LF	Linear Foot		46.00	46.00	46.00			46.00			46.00																				230.00	
122	Street Lights Foundation	EA	Each	2.00	2.00	3.00	2.00	2.00	3.00	2.00	2.00	3.00	2.00	2.00	2.00	2.00	3.00																32.00	
123	4" Reflective White Traffic Bulb	EA	Each																														290.00	
124	4" Non-Reflective White Traffic Bulb	EA	Each																														168.00	
125	4" Yellow Reflective Traffic Bulb	EA	Each																														26.00	
126	4" Wide White Thermoplastic Pavement Markings	LF	Linear Foot																														2,350.00	
127	4" Wide Yellow Thermoplastic Pavement Markings	LF	Linear Foot																														1,346.00	
128	8" Wide Yellow Thermoplastic Pavement Markings	LF	Linear Foot																														700.00	
129	8" Wide White Thermoplastic Pavement Markings	LF	Linear Foot																														150.00	
130	18" Wide White Thermoplastic Stop Bar	LF	Linear Foot																														64.00	
131	24" Wide Yellow Thermoplastic Crosshatch Marker	LF	Linear Foot																														275.00	
132	Arrow And Symbol Pavement Markings	EA	Each																														4.00	
133	Barbed Wire Fence With Corner Braces / Gates / Connections	LF	Linear Foot																														680.00	
134	Roll Anchorage Curb (RAC)	LF	Linear Foot					500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	80.00																6,580.00	
135	Traffic Rail (T101)	LF	Linear Foot																														245.00	
136	Metal Beam Guard Fence	LF	Linear Foot																														1,490.00	
137	Terminal Anchor Section	EA	Each																														4.00	
138	Single Guardrail Terminal (SOT (7) HB-Q3A)	EA	Each																														5.00	
139	Sodding including 4" Topsoil, Watering & Fertilizing (if/size topsoil approved by City)	SY	Square Yard	1827.00	3133.00	3332.00	2537.00	3223.00	2376.00	2777.00	2699.00	1994.00	2538.00	2638.00	3322.00	3333.00	3138.00	150.00	400														39,407.00	
140	Hydromulch (outside ROW)	SY	Square Yard	800	230	427	950	615	250	305	915	925	350	50	775	950	1555	200															209,271.00	
141	Erosion Control	LS	Lump Sum																														1.00	
142	Traffic Control	LS	Lump Sum																														1.00	
143	Project Sign	EA	Each																														2.00	
	Storm Sewer System																																	
200	Remove 4x2 Box Head Wall	EA	Each																														1.00	
201	Remove 5x4 Rep Headwall	EA	Each																														1.00	
202	Channel Excavation	CY	Cubic Yard																														8,750.00	
203	10" Standard Recessed Curb Inlet	EA	Each																														4.00	
204	15" Standard Recessed Curb Inlet	EA	Each																														6.00	
205	20" Standard Recessed Curb Inlet	EA	Each																														1.00	
206	3x3 "Y" Inlet	EA	Each																														1.00	
207	18" Rep Class III Storm Sewer	LF	Linear Foot																														173.00	
208	21" Rep Class III Storm Sewer	LF	Linear Foot																															