



(A) SAWED LONGITUDINAL CONTRACTION JOINT

- NOTES:
- CONSTRUCT PAVEMENT IN ACCORDANCE WITH CITY STANDARD CONSTRUCTION DETAILS EXCEPT AS NOTED HEREON.
  - PLACE BERMUDA GRASS SOD IN PARKWAY AND TO LIMITS SHOWN IN FUTURE MEDIANS AS PER SPECIFICATIONS.
  - IMPORT AND PLACE MINIMUM 4" TOPSOIL ON CUT AND FILL SLOPES. HYDROMULCH SEED WITH BERMUDA GRASS AS PER SPECIFICATIONS.
  - COMPACT ALL FILLS TO MINIMUM 95% OF STANDARD PROCTOR DENSITY. FILL COMPACTION SHALL BE PERFORMED WITH A SHEEPSFOOT ROLLER.
  - BACKFILL ALL CURBS WITH ON-SITE BROWN CLAY SOILS COMPACTED TO A MINIMUM 95% OF STANDARD PROCTOR DENSITY. TYPICAL ALL ROADWAY AND STREET CURBS THIS PROJECT.
  - 6'-0" CONCRETE SIDEWALK SHALL BE CONSTRUCTED WITH DEVELOPMENT OF ADJACENT PROPERTY.

RECORD PLANS  
 MARCH 28, 2008