MATCH LINE STA. 15+00
N 7009982.1151, E 2594686.5571

MATCH LINE STA. 20+00
N 7010328.2300, E 2594325.7253

JWS LAND LTD
VOL. 4476, PG. 271
34.212 AC.

HORIZON RD (F.M. 3097)

ROCKWALL LAKE ESTATES NO. 1

0 20 40 60
HORIZONTAL SCALE IN FEET

N 7009982.1151
E 2594686.5571
STA. 15+00
FURNISH & INSTALL:
1-4-INCH COMBINATION SEWAGE AIR & VACUUM RELIEF VALVE IN 6-FOOT DIAMETER MANHOLE

FURNISH & INSTALL
500 L.F. 30" FORCE MAIN

REMOVE 59 S.Y. GRAVEL DRIVEWAY
FURNISH & INSTALL
59 S.Y. REINFORCED CONCRETE DRIVEWAY

REMOVE 149 S.Y. GRAVEL DRIVEWAY
FURNISH & INSTALL
149 S.Y. REINFORCED CONCRETE DRIVEWAY

SAWCUT, REMOVE & REPLACE
10 S.Y. REINFORCED CONCRETE DRIVEWAY

SAWCUT, REMOVE & REPLACE
9 S.Y. REINFORCED CONCRETE DRIVEWAY

REMOVE 55 S.Y. ASPHALT DRIVEWAY
FURNISH & INSTALL
55 S.Y. REINFORCED CONCRETE DRIVEWAY

REMOVE 52 S.Y. ASPHALT DRIVEWAY
FURNISH & INSTALL
52 S.Y. REINFORCED CONCRETE DRIVEWAY

REMOVE 56 S.Y. ASPHALT DRIVEWAY
FURNISH & INSTALL
56 S.Y. REINFORCED CONCRETE DRIVEWAY

N 7010261.5109
E 2594394.0201
P.I. STA. 19+04.52
Δ = 00°38'51" RT.

REMOVE & REPLACE
43 L.F. 18" RCP CULVERT

BLOCK C, LOT 601 | BLOCK C, LOT 602 | BLOCK C, LOT 603 | BLOCK C, LOT 604 | BLOCK C, LOT 605 | BLOCK C, LOT 606 | BLOCK C, LOT 607 | BLOCK C, LOT 608 | BLOCK C, LOT 609 | BLOCK C, LOT 610

EXIST. CONC PVMT. | EXIST. CONC PVMT. | EXIST. HMAC PVMT. | EXIST. GROUND LINE | EXIST. HMAC PVMT. | EXIST. HMAC PVMT. | EXIST. GRAVEL PVMT. | EXIST. GRAVEL PVMT.

30" F.M. ON -1.40%

30" F.M. ON -4.04%

500 L.F. 30" F.M.
BY OPEN CUT
W/ CLASS B-4
EMBEDMENT

P.V.I. STA. 15+00
F.L. 30" F.M. 509.03

P.V.I. STA. 19+40
F.L. 30" F.M. 502.87

F.L. 30" F.M. 500.45

515 | 510 | 505 | 500 | 495 | 490 | 485 | 480

15+00 | 16+00 | 17+00 | 18+00 | 19+00 | 20+00

This record drawing is a compilation of the sealed engineering drawing for this project; modified by addenda, change orders and information furnished by the contractor. The information shown on the record drawings that was provided by the contractor or others not associated with the design engineer cannot be verified for accuracy or completeness. This original sealed drawings are on file at the offices of Birkhoff, Hendricks & Carter, L.L.P.

BY PAC DATE 06/13/2011

BIRKHOFF, HENDRICKS & CARTER, L.L.P.
PROFESSIONAL ENGINEERS
Texas Firm F526
11910 Greenville Ave., Suite 600
Dallas, Texas (214) 361-7900

STATE OF TEXAS
PAUL A. CARLINE
85400
LICENSED
PROFESSIONAL ENGINEER

4/12/10

CITY OF ROCKWALL, TEXAS
SQUABBLE CREEK FORCE MAIN

PLAN AND PROFILE
STA. 15+00 TO STA. 20+00

BHC PROJECT NO. 2007-110

April, 2010

SHEET NO. 5

These plans and related specifications were prepared for construction of this specific project only. Reuse of these documents is not permitted without written authorization of Birkhoff, Hendricks, & Carter, L.L.P.

REVISED: 6/13/11 - KBURKS

H:\Projects\Rockwall\2007110\Sheets\Complete Section III\07110-PP-III.dwg

PLOT SCALE: 1:1 PLOT STYLE: 11x17.ctb PLOTTED BY: KBURKS ON 6/13/2011