



NOTE:
A Water Pipeline Exists On
The North Side Of Heath Street.

Note:
Location Of Existing Sewer Pipeline Taken Principally From
Original Plans With Some Field Verification Of Data.
Locations Of Underground P.I. In Existing Sewer Will Be
Verified By City At Time Of Construction. The Contractor
Shall Verify All Elevations, Alignment, And Distances.
Contractors Shall Verify Location Of All Utilities And
Other Conflicts.

□ B.M. On Top Of Guard Post On
N.W. Corner Of Bridge On Hwy 66
East Of Heath Street Used As
Control Elevation 491.86

The Contractor Shall Connect Existing
Lateral Sewer To New 15" Pipeline.

R.I. Sta. 16+40.55
Δ 146°17'20"

P.I. Sta. 14+42.40
Δ 180°00'00"

R.I. Sta. 13+72.40
Δ 100°45'14" Lf.

☒ Connect All Lateral
Sewers At These Points

