



FURNISH & INSTALL
4'x6'x3' PULL BOX

FURNISH & INSTALL
330 L.F. 2-4" SCHEDULE 40
GRAY PVC CONDUITS BY
HORIZONTAL DIRECTIONAL
DRILLING

NOTE:
PULL BOX SHALL BE MANUFACTURED
BY QUAZITE, PART NO. 316044, LOCAL
SUPPLIER IS STUART IRBY COMPANY
817-284-0868.

This record drawing is a compilation of the sealed
engineering drawing for this project; modified by addenda,
change orders and information furnished by the contractor.
The information shown on the record drawings that was
provided by the contractor or others not associated with the
design engineer cannot be verified for accuracy or
completeness. This original sealed drawings are on file at the
offices of Birkhoff, Hendricks & Carter, L.L.P.
BY PAC DATE 03/06/12

TBM 6514
SQ. CUT IN CENTER OF NORTH
LAKESHORE DR. MEDIAN OPENING
AT SQUABBLE WWTP ENTRANCE &
SOUTH OF SUTTER DR.
N 7033789.3760
E 2592028.2244
ELEV. 483.52

These plans and related specifications were prepared for construction of this specific project only. Reuse of these documents is not permitted without written authorization of Birkhoff, Hendricks, & Carter, L.L.P.

CHANGE ORDER NO.1 9/3/10: UNDERGROUND ELECTRIC SERVICE

BIRKHOFF, HENDRICKS & CARTER, L.L.P.
PROFESSIONAL ENGINEERS
Texas Firm F526
11910 Greenville Ave., Suite 600
Dallas, Texas 75243 (214) 361-7900



[Signature]
5/23/10

CITY OF ROCKWALL, TEXAS
SQUABBLE CREEK LIFT STATION
LIFT STATION SITE PLAN

BHC PROJECT NO. 2007-110	SHEET NO.
MAY 2010	3