THE PARK AT STONE CREEK CONSTRUCTION PLANS CITY OF ROCKWALL, TEXAS


TPWD PROJECT #50-000454

ROCKWALL COUNTY FEBRUARY 2016

*** NOTICE TO CONTRACTORS ***

THE CONTRACTOR SHALL NOTIFY THE CONSULTANT IMMEDIATELY, IN WRITING, OF ANY DISCREPANCIES OR OMISSIONS TO THE TOPOGRAPHIC INFORMATION. THE CONTRACTOR(S) SHALL BE RESPONSIBLE FOR CONFIRMING THE LOCATION (HORIZONTAL/VERTICAL) OF ANY BURIED CABLES, CONDUITS, PIPES, AND STRUCTURES (STORM SEWER, SANITARY SEWER, WATER, GAS, TELEVISION, TELEPHONE, ETC.) WHICH IMPACT THE CONSTRUCTION SITE. THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND CONSULTANT IF ANY DISCREPANCIES ARE FOUND BETWEEN THE ACTUAL CONDITIONS VERSUS THE DATA CONTAINED IN THE CONSTRUCTION PLANS. ANY COSTS INCURRED AS THE RESULT OF NOT CONFIRMING THE ACTUAL LOCATION (HORIZONTAL/VERTICAL) OF SAID CABLES, CONDUITS, PIPES, AND STRUCTURES SHALL BE BORNE BY THE CONTRACTOR. ADDITIONALLY, THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND CONSULTANT IF ANY ERRORS OR DISCREPANCIES ARE FOUND ON THE CONSTRUCTION DOCUMENTS (PS&E), WHICH NEGATIVELY IMPACT THE PROJECT. CONSULTANT AND OWNER SHALL BE INDEMNIFIED OF PROBLEMS AND/OR COST WHICH MAY RESULT FROM CONTRACTOR'S FAILURE TO NOTIFY CONSULTANT AND OWNER.

LOCATION





*** STOP! CALL BEFORE YOU DIG! ***

AS REQUIRED BY "THE TEXAS UNDERGROUND FACILITY DAMAGE PREVENTION AND SAFETY ACT," TEXAS ONE CALL SYSTEM MUST BE CONTACTED (800-245-4545) AT LEAST 48 HOURS PRIOR TO ANY EXCAVATION OPERATIONS BEING PERFORMED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT TEXAS ONE CALL SYSTEM.

TITLE	SHEET NO.
COVER SHEET	1
SITE PLAN	
SURVEY AND DEMO PLAN $$	
EROSION CONTROL PLAN — — — — —	
SWPPP NOTES	
GRADING PLAN	200
UTILITY PLAN	
PAVING AND HORIZONTAL CONTROL PLAN	
PAVING DETAILS————————	
PLAYGROUND PLAN AND DETAILS— — —	
PAVILION DETAIL	
IRRIGATION PLAN- — — — — — — —	
GRASSING AND LANDSCAPE PLAN	(13
PICNIC STATION DETAILS	
TRAIL DETAILS ————————	
MISCELLANEOUS DETAILS	
ELECTRICAL — — — — — — — —	10

212 West Ninth Street Tyler, Texas 75701 903-597-6606 903-597-6517 Fax

MHS

TION PLANS
STONE CREEK

RAWN:

CONSTRUC

THE

CHECKED: MI

DATE: OCT 2015

OB NO.: 15-006

REFERENCE BENCHMARK:

THE BOUNDARY SURVEY, TOPOGRAPHIC SURVEY, BENCHMARKS AND LOCATION OF ALL EXISTING UTILITIES, STRUCTURES, TREES AND IMPROVEMENTS WERE PROVIDED BY

X Set in the southwest corner of concrete for a drop inlet located on the west side of State Highway No. 205 Bypass (John King Boulevard) and being located South 11°55'55' East a distance of 104.27 feet from a 2" iron pipe fence corner post near the northeast corner of the subject tract. Said bernchmark having a Texas State Plain Coordinate Value of (X= 2,596,352.27; Y=7,038,932.54)(TNC) and an Elevation of 529.11 feet.

X Set in the northwest corner of concrete for an drop inlet located on the north side of Feather Stone Drive and X Set in the northwest corner of concrete for an drop infel located on the north side of Feather Stone Drive an being located South 75°18'43" East a distance of 70.93 feet from the southeast corner of a wing wall near the south line of the subject tract. Said benchmark having a Texas State Plain Coordinate Value of (X= 2,595,913.75; Y= 7,038.591.29)(TNC) and an Elevation of 527.60 feet.

GENERAL NOTES


- ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO THE CITY OF ROCKWALL PLANS AND SPECIFICATIONS, EXCEPT AS NOTED HEREIN AND APPROVED BY THE CITY
- PLANS AND SPECIFICATIONS, EXCEPT AS NOTED HEREIN AND APPROVED BY THE CITY CONTRACTOR SHALL BE RESPONSBILE FOR MAINTAINING TERPICH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY STANDARDS, TEXAS STATE LAW, AND O.S.H.A. STANDARDS FOR ALL EXCAVATION IN EXCESS OF FIVE FEET IN DEPTH. THE LOCATION OF ALL UTILITIES LOCATED ON THESE PLANS ARE TAKEN FROM EXISTING PUBLIC RECORDS OR PROVIDED BY THOMPSON AND ASSOCIATES, INC. THE EXACT LOCATION AND ELEVATION OF ALL PUBLIC UTILITIES MUST BE DETERMINED BY THE CONTRACTOR. IT SHALL BE THE DUTY OF THE CONTRACTOR TO ASCERTAIN WHETHER ANY ADDITIONAL FACILITIES OTHER THAN THOSE SHOWN ON THE PLANS
- WHETHER ANY ADDITIONAL FACILITIES OTHER THAN THOSE SHOWN ON THE PLAN MAY BE PRESENT. EROSION CONTROL SHALL BE REQUIRED DURING ALL PHASES OF CONSTRUCTION. ALL PROPOSED GRADES IN LANDSCAPE AREAS ARE FINISHED GRADE ELEVATIONS. CONTRACTOR TO ALLOW FOR SEEDING OR SODDING OF THESE AREAS
- ALL MATERIALS AND WORKMANSHIP SHALL CONFORM TO THE CONTRACT ALL MATERIALS AND WORKMANSHI SHALL CONFORM TO THE CONTRACT
 DOCUMENTS. TECHNICAL SPECIFICATIONS, OR CITY STANDARDS FOR THE PROJECT
 UNLESS OTHERWISE INDICATED IN THIS PLAN SET.
 DURING CONSTRUCTION OF THESE PUBLIC IMPROVEMENTS, ANY DEVIATION FROM
 THESE SPECIFICATIONS WILL REQUIRE APPROVAL FROM THE OWNER OR HIS
- DESIGNEE BEFORE ANY CONSTRUCTION INVOLVING THAT DECISION COMMENCES ASSUMPTIONS ABOUT WHAT THESE DECISIONS MIGHT BE THAT ARE MADE DURING THE BIDDING PROCESS WILL HAVE NOT BEARING ON THE DECISION

- ALL FACILITIES IN THE PUBLIC RIGHT-OF-WAY SHALL BE CONSTRUCTED IN CONFORMANCE WITH THE CITY OF ROCKWALL STANDARD CONSTRUCTION DETAILS. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT ALL PUBLIC UTILITIES DURING THE CONSTRUCTION OF THE PROJECT. ALL MANHOLES, CLEANOUTS, VALVE BOXES, FIRE HYDRANTS, ETC. MUST BE ADJUSTED TO PROPER CLEANOUTS, VALVE BOXES, FIRE HYDRANTS, ETC. MUST BE ADJUSTED TO PROPER LINE AND GRADE BY THE CONTRACTOR PRIOR TO AND AFTER THE PLACING OF FERMANENT PAVING. UTILITIES MUST BE MAINTAINED TO PROPER LINE AND GRADE DURING CONSTRUCTION OF THE PAVING FOR THIS DEVELOPMENT. DRAINAGE SHOULD BE MAINTAINED AWAY FROM THE FOUNDATIONS, BOTH DURING AND AFTER CONSTRUCTION.

 BACKFILL FOR UTILITY LINES SHOULD BE CAREFULLY PLACED SO THAT THEY WILL BE STADE. BUTTERS THE TOTAL OF THE SALVEY.

 - BACKFILL FOR UTLITY LINES SHOULD BE CAREFULLY PLACED SO THAT THEY WILL BE STABLE. WHERE UTLITY LINES PASS THROUGH THE PARKING LOT, THE TOP 6 ° SHOULD BE COMPACTED SIMILARLY TO THE REMAINDER OF THE LOT. UTLITY DITCHES SHOULD BE VISUALLY INSPECTED DURING THE EXCAVATION PROCESS TO ENSURE THAT UNDESIRABLE FILL IS NOT USED. IF ROCK IS ENCOUNTERED IN THE TRENCH, ROCK SPOILS SHALL NOT BE USED IN THE LIBBELL OF CHIEF TRENCH.
 - UPPER 1.5' OF THE TRENCH.
 - ALL SIDEWALK AND CROSSWALK SLOPES SHALL CONFORM TO ADA REQUIREMENTS AS FOLLOWS:

1.20 LONGITUDINAL (ALONG THE WALK) MAX
1.50 TRAVERSE (ALONG THE WALK) MAX
ALL EARTHWORK OPERATIONS SHALL CONFORM TO THE RECOMMENDATIONS PER THE GEOTECHNICAL INVESTIGATION (PROJECT NO.15-0416) BY D & S ENGINEERING (OCTOBER 2015)



NECESSARY PRECAUTIONS IN ORDER TO PROTECT ALL FACILITIES ENCOUNTERED. THE CONTRACTOR SHALL PRESERVE AND PROTECT ALL EXISTING UTILITIES FROM DAMAGE DURING CONSTRUCTION.



DESIGN, 8 PLANNING


CREEK


CITY OF ROCKWALL, TEXAS STONE PLA] AT SITE ARK THIE


WHS MHS OCT 2015 AS SHOWN

OF 16

15-006







SANDBLASTING WASTE MANAGEMENT

The objective of the management program is to minimize the potential of storm water quality degradation from sandblasting activities at construction sites. The key issues in this program are prudent handling and storage of sandblast media, dust suppression, and proper collection and disposal of spent media. It is not the intent of this program to outline all of the worker safety issues pertinent to this practice. Safety issues should be addressed by construction safety programs as well as local, state, and and federal regulation. utilized at sites in which Sandblasting waste is present.

INSTALLATION/APPLICATION CRITERIA

Since the media consists of fine abrasive granules, it can be easily transported by running water. Sandblasting activities typically create a significant dust problem which must be contained and collected to prevent off—site migration problem which must be contained and collected to to prevent off—site migration or fines.

Operational Procedures

Use only inert, non-degradable sandblast media. Use only inert, non-degradable sandblast media.

Use appropriate equipment for the job, do not over-blast.

Wherever possible, blast in a downward direction.

Install a wind sock or other wind direction instrument.

Cease blasting activities in high winds or if wind direction could transport grit to drainage facilities.

Install dust shielding around sandblasting areas.

Collect and dispose of all spent sandblast grit, use dust containment fobrics and dust collection hoppers and barrels.

Non-hazardous sandblast grit may be disposed in permitted construction debris landfills or permitted sanitary landfills.

If sandblast media cannot be fully contained, construct sediment traps downstream from blasting area where appropriate.

downstream from blasting area where appropriate. Use sand fencing where appropriate in areas where blast media cannot be

fully contained.

If necessary, install misting equipment to remove sandblast grit from the air – prevent runoff from misting operations from entering drainage

systems. Use vacuum grit collection systems where possible. Keep records of sandblasting materials, procedures, and weather conditions

on a daily basis.

Take all reasonable precautions to ensure that sandblasting grit is contained and kept away from drainage structures.

Educational Issues

Educate all on-site employees of potential dangers to humans and the environment from sandblast grit.

Instruct all on-site employees of the potential hazardous nature of sandblast grit and possible symptoms of overexposure to sandblast grit not possible symptoms of overexposure to sandblast grit.

Instruct operators of sandblasting equipment on safety procedures and personal protection equipment.

Instruct operators on proper procedures regarding storage, handling, and containment of sandblast grit.

Instruct operators to recognize unfavorable weather conditions regarding

sandblasting activities.

Instruct operators and supervisors on current local, state, and federal federal regulations regarding fugitive dust and hazardous waste from sandblast grit. Have weekly meetings with operators to discuss and reinforce proper

have weekly meetings with operation operational procedures.
Establish a continuing education program to indoctrinate new employees.

Material Handling Recommendations

Compliance by supervisors and workers.

Sandblast media should always be stored under cover away from drainage

structures.

Ensure that stored media or grit is not subject to transport by wind.

Ensure that all sandblasting equipment as well as storage containers comply with local, state, and federal regulations.

Refer to Hazardous Waste BMP lact sheet if sandblast grit is known or

or suspected to contain hazardous components.

Capture and treat runoff which comes into contact with sandblasting material or waste.

Foreman and/or construction supervisor should monitor all sandblasting activities and safety procedures.

Educate, and if necessary, discipline workers who violate procedures. Take all reasonable precautions to ensure that sandblast grit is not transported off-site or into drainage facilities.

Education and awareness program for all employees regarding control of sandblasting and potential dangers to humans and the environment. Operator and supervisor education program for those directly involved in sandblasting activities — instructions on material handling, proper equipment operation, personal protective equipment, fugitive dust control, record keeping and reporting, fugitive dust control, record keeping and reporting to the substantial proper sandblast equipment for the job.

Site-specific futilities dust control, and containment equipment. Site—specific fugitive dust control and containment equipment. Site—specific fugitive dust control procedure.

Minimal cost for training and monitoring.
Potential for significant cost for containment procedures on large jobs.
Potential for significant costs associated with cleanup, correction and remediation if containment occurs.

Site specific solutions to sandblasting problems may be required. Sandblasting operations on structures known to contain hazardous materials require special procedures not specifically outlined above including professional hazardous waste specialists.

Where hazardous materials are known or suspected, a site assessment and remediation plan may be necessary.

This management program is one part of a comprehensive construction site waste management program.

HAZARDOUS WASTE MANAGEMENT

DESCRIPTION

DESCRIPTION
The hazardous waste management BMP addresses the problem of storm water
Polluted with hazardous waste through spills or other forms of contact. The
Objective of the Management Program is to minimize the potential of
Storm water contamination from common construction site hazardous wastes
Through appropriate recognition, handling, storage, and disposal practices.

It is not the intent of this Management Program to supersede or replace normal site assessment and remediation procedures. Significant spills and/or contamination warrant immediate response by trained professionals. Suspected job-site contamination should be immediately reported to regulatory Authorities and protective actions taken. The General Permit requires reporting Of significant spills to the National Response Center (NRC) at (800)424-880

These management practices along with applicable OSHA and EPA guidelines. Should be incorporated at all construction sites which use or generate Hazardous wastes. Many wastes such as fuel, oil, grease, fertilizer, and pesticide are present at most construction sites.

INSTALLATION, APPLICATION AND DISPOSAL CRITERIA INSTALLATION, APPLICATION AND DISPOSAL CRITERIA
The hazardous waste management techniques presented here are based on
Proper recognition, handling, and disposal practices by construction workers
And supervisors. Key elements of the management program are education,
Proper disposal practices, as well as provisions for safe storage and disposal.
Following are lists describing the targeted materials and recommended procedures: Targeted Hazordous Waste Materials

Stains
Wood preservatives
Cutting oils
Greases
Roofing tar
Pesticides

Pesticides Fuel and lube oils

Lead based paints (Demolition)

Storage Procedures
Wherever possible, minimize use of hazardous materials.
Minimize generation of hazardous wastes on the job—site.
Segregate potentially hazardous waste from non-hazardous
Construction site debris.
Designate a foreman or supervisor to oversee hazardous materials
Handlian procedures. Handling procedures. Keep liquid or semi—liquid hazardous waste in appropriate containers

(closed drums or similar) and under cover.

Other enclosed trash container that limits contact with rain and Store waste materials away from drainage ditches, swales, and catch basins.

Use containment berms in fueling and maintenance areas and where the potential for spills is bight berms.

for spills is high.

Ensure that adequate hazardous waste storage volume is available.

Ensure that hazardous waste collection containers are conveniently located.

Do not allow potentially hazardous waste materials to accumulate on the ground.

Enforce Hazardous waste handling and storage procedures.

Clearly mark on all hazardous waste containers which materials are acceptable for

Disposal Procedures Regularly schedule hazardous waste removal to minimize on-site storage. Use only reputable, licensed hazardous waste haulers.

Education Instruct workers in identification of hazordous waste Educate workers of potential dangers to humans and the environment from

hazardous wastes Instruct workers on safety procedures for common construction site hazardous wastes Educate all workers on hazardous waste storage and disposal procedures Have regular meetings to discuss and reinforce identification, handling and disposal procedures (incorporate in regular safety seminars). Establish a continuing education program to indoctrinate new employees

Quality Assurance

Foreman and/or construction supervisor shall monitor on—site hazardous waste storage and disposal procedures.

Educate, and if necessary, discipline workers who violate procedures.

Ensure that the hazardous waste disposal contractor is reputable and licensed.

Job—site waste handling and disposal education and awareness program Job—site waste handling and disposal education and awareness program Commitment by management to implement hazardous waste management practices. Compliance by workers. Sufficient and appropriate hazardous waste storage containers. Timely removal of stored hazardous waste materials.

Possible modest cost impact for additional hazardous storage containers Small cost impact for training and monitoring
Potential cost impact for hazardous waste collection and disposal by licensed hauler

actual cost depends on type of material and volume.

LIMITATIONS

his practice is not intended to address site-assessments and pre-existing contamination.

Major contamination, large spills and other serious hazardous waste incidents

require immediate response from specialists.

Demolition activities and potential pre-existing materials, such as asbestos, are not addressed by this program. Site specific information on plans is necessary. Contaminated soils are not addressed. One port of a comprehensive construction site waste management program.

SOLID WASTE MANAGEMENT

DESCRIPTION

Large volumes of solid waste are often generated at construction sites large voluntes of solid waste are often generated at construction sites including; packaging, pollets, wood waste, concrete waste, soil, electrical wiring, cuttings, and a variety of other materials. The solid waste management practice lists techniques to minimize the potential of storm water contamination from solid waste through appropriate storage and disposal practices.

PRIMARY USE

PRIMARY USE.

These practices should be a part of all construction practices. By limiting the trash and debris on site, storm water quality is improved along with reduced clean up requirements at the completion of the project.

APPLICATIONS

APPLICATIONS
The solid waste management practice for construction sites is based on proper storage and disposal practices by construction workers and supervisors. Key elements of the program are education and modification of improper disposal habits. Cooperation and vigilance is required on the part of supervisors and workers to ensure that the recommendations and procedures are followed. Following are lists describing the targeted materials and recommended procedures:

Targeted Solid Waste Materials Paper and cardboard containers Paper and cardboard containers
Plastic packaging
Styrofoam packing and forms
Insulation materials (non-hazardous)
Wood pallets
Wood cuttings
Wood cuttings
Concrete, brick, and mortar
Shingle cuttings and waste
Roofing tar
Steel (cuttings nails rust residue) Steel (cuttings, nails, rust residue)

Gypsum board cuttings and waste Sheathing cuttings and waste Miscellaneous cutting and waste Food waste

Storage Procedures Wherever possible, minimize production of solid waste materials.

Designate a foreman or supervisor to oversee and enforce proper solid waste procedures. Instruct construction workers in proper solid waste procedures. Segregate potentially hazardous waste from non-hazardous construction site debris. Keep solid waste materials under cover in either a closed dumpster or

other enclosed trash container that limits contact with rain and run Store waste materials away from drainage ditches, swales and catch

Do not allow trash containers to overflow.

Do not allow waste materials to accumulate on the ground.

Prohibit littering by workers and visitors.

Police site daily for litter and debris.

Enforce solld waste handling and storage procedures.

Disposal Procedures

If feasible, segregate recycloble wastes from non-recycloble waste materials and dispose of properly.

General construction debris may be hauled to a licensed construction debris landfill.

(typically less expensive than a sanitary landfill). Use waste facilities approved by local jurisdiction. Runoff which comes into contact with unprotected waste shall be directed into structural treatment such as silt fence to remove debris.

Educate all workers on solid waste storage and disposal procedures.
Instruct workers in identification of solid waste and hazardous waste.
Have regular meetings to discuss and reinforce disposal procedures (incorporate in regular safety seminars). Clearly mark on all solid waste containers which materials are acceptable

Foreman and/or construction supervisor shall monitor on-site solid waste storage and disposal procedures. Discipline workers who repeatedly violate procedures

Jobsite waste handling and disposal education and awareness program Commitment by management to implement and enforce Solid Waste Management Program.
Compliance by workers.
Sufficient and appropriate waste storage containers.
Timely removal of stored solid waste materials.
Possible modest cost impact for additional waste storage containers.
Small cost impact for training and monitoring

Only addresses non-hazardous solid waste.
One part of a comprehensive construction site management program.

CONCRETE WASTE MANAGEMENT

DESCRIPTION

Recommended Disposal Practices Avoid unacceptable dumping practices listed above. Develop predetermined, safe concrete disposal areas Provide a washout area with a minimum of 6 cubic feet of containment area volume for every 10 cubic yards of concrete poured. Never dump waste concrete illicitly or without property owners knowledge and consent.

Treat runoff from storage area through the use of structural controls.

as required. Education

Drivers and equipment operators should be instructed on proper disposal and equipment washing practices (see above).

Supervisors must be made aware of the potential environmental consequences of improperly handling concrete waste.

Demolition Practices

Demolition Proctices

Monitor weather and wind direction to ensure concrete dust is not entering drainage structures and surface waters.

Where appropriate, construct sediment traps or other types of sediment detention devices downstream of demolition activities.

Minimal cost impact for training and monitoring.

Concrete disposal cost depends on availability and distance to suitable disposal areas. Additional costs involved in equipment washing could be significant.

Concrete waste at construction sites comes in two forms; 1) excess fresh concrete mix including truck and equipment washing, and 2) concrete dust and concrete debris resulting from demalition. Both forms have the potential to impact water quality through storm water runoff contact with the waste.

Concrete waste is present at most construction sites. This BMP should be utilized at sites in which concrete waste is present

APPLICATIONS

A number of water quality parameters can be affected by introduction of concrete – especially fresh concrete. Concrete offects the pH of runoff, cousing significant chemical changes in water bodies and harming aquatic life.

Suspended solids in the form of both cement and aggregate dust are also Generated from both fresh and demolished concrete waste:

Current Unacceptable Waste Concrete Disposal Practices Dumping in vacant areas on the job-site Illicit dumping off-jobsite Dumping into ditches or drainage facilities

Thiorcement:
The construction site manager or foreman must ensure that employees and pre-mix companies follow proper procedures for concrete disposal and equipment washing.

Employees violating disposal or equipment cleaning directives must be reducated or disciplined if necessary.

Requirements.
Use predetermined disposal for waste concrete.
Prohibit dumping waste concrete anywhere but predetermined areas.
Assign predetermined truck and equipment washing areas.
Educate drivers and operators on proper disposal and equipment cleaning

LIMITATIONS

This concrete waste management program is one part of a comprehensive

国国 U X ONE 0 Z 0 2 2

S

0

112 West Ninth Street Tyler, Texas 75701 903-597-6606 903-597-0517 Fax TBPE No. F-14571

*

DESIGN,

8

ING

ROCKWALL,


OF

CITY

WHS

CHECKED: MHS DATE: OCT 2015

SCALE: AS SHOWN JOB NO.: 15-006



REFERENCE BENCHMARK

THE BOUNDARY SURVEY, TOPOGRAPHIC SURVEY, BENCHMARKS AND LOCATION OF ALL EXISTING UILLITIES. STRUCTURES, TREES AND IMPROVEMENTS WERE PROVIDED BY THOMPSON AND ASSOCIATES, INC.

X Set in the southwest corner of concrete for a drop inlet located on the west side of State Highway No. 205 Bypass (John King Boulevard) and being located South 11*5555* East a distance of 104.27 feet from a 2* iron pipe fence corner post near the northeast corner of the subject tract. Said benchmark having a Texas State Plain Coordinate Value of (X=2,596,352.27; Y=7,038,932.24\XTNC) and an Elevation of \$29.11 feet.

X Set in the northwest corner of concrete for an drop inlet located on the north side of Feather Stone Drive and being located South 75° 18'43" East a distance of 76.93 feet from the southeast corner of a wing wall near the south line of the subject treat Said benchmark having a Texas State Plain Coordinate Value of (X=2.595,913.75; Y=7.038.591.29)(TNC) and an Elevation of 527.60 feet.

CAUTION!!!

EXISTING UTILITIES
EXISTING UTILITIES, OVERHEAD AND UNDERGROUND, INDICATED ON THESE PLANS HAVE EXISTING UTILITIES, OVERHEAD AND UNDERGROUND, INDICATED ON THESE PLANS HAVE BEEN LOCATED FROM REFERENCE INFORMATION. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY BOTH HORIZONTAILY AND VERTICALLY THE LOCATION OF ALL EXISTING UTILITIES AND UNDERGROUND FACILITIES PRIOR TO CONSTRUCTION, TO TAKE NECESSARY PRECAUTIONS IN ORDER TO PROTECT ALL FACILITIES ENCOUNTERED. THE CONTRACTOR SHALL PRESERVE AND PROTECT ALL EXISTING UTILITIES FROM DAMAGE DURING CONSTRUCTION.

GENERAL NOTES

- ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO THE CITY OF ROCKWALL PLANS AND SPECIFICATIONS, EXCEPT AS NOTED HEREIN AND APPROVED BY THE CITY. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY STANDARDS, TEXAS STATE LAW, AND O.S.H.A. STANDARDS FOR ALL EXCAVATION IN EXCESS OF FIVE FEET IN DEPTH
- U.S.H.A. SI ANDARDS FOR ALL EXCAVATION IN EXCESS OF FIVE FEET IN DEPTH. THE LOCATION OF ALL UILLIFIES LOCATED ON THESE FLANS ARE TAKEN FROM EXISTING PUBLIC RECORDS OR PROVIDED BY THOMPSON & ASSOCIATES, INC. THE EXACT LOCATION AND ELEVATION OF ALL PUBLIC UTILITIES MUST BE DETERMINED BY THE CONTRACTOR. IT SHALL BE THE DUTY OF THE CONTRACTOR TO ASCERTAN WHETHER ANY ADDITIONAL FACILITIES OTHER THAN THOSE SHOWN ON THE PLANS MAY DEED RESENT. MAY BE PRESENT.
- MAY BE PRESENT.

 FROSION CONTROL SHALL BE REQUIRED DURING ALL PHASES OF CONSTRUCTION.

 ALL MATERIALS AND WORKMANSHIP SHALL CONFORM TO THE CONTRACT
 DOCUMENTS, IECHNICAL SPECIFICATIONS, OR CITY STANDARDS FOR THE PROJECT
 UNLESS OTHERWISE INDICATED IN THIS PLAN SET.

 DURING CONSTRUCTION OF THESE PUBLIC IMPROVEMENTS, ANY DEVIATION FROM
- JUGING CURSTRUCTION OF THESE PUBLIC IMPROVEMENTS, ANY DEVIATION FROM THESE SPECIFICATIONS WILL REQUIRE APPROVAL FROM THE OWNER OR HIS DESIGNED BEFORE ANY CONSTRUCTION INVOLVING THAT DECISION COMMENCES. ASSUMPTIONS ABOUT WHAT THESE DECISIONS MIGHT BE THAT ARE MADE DURING THE BIDDING PROCESS WILL HAVE NOT BEARING ON THE DECISION ALL FACILITIES IN THE PUBLIC RIGHT-OF-WAY SHALL BE CONSTRUCTED IN CONFORMANCE WITH THE CITY OF ROCKWALL STANDARD CONSTRUCTION DETAILS.
- T SHALL BE THE RESPONSIBILITY OF THE CONTRACTION TO PROTECT ALL PUBLIC.
 UTILITIES DURING THE CONSTRUCTION OF THE PROJECT. ALL MANHOLES, CLEANOUTS,
 VALVE BOXES, FIRE HYDRANTS, ETC. MUST BE ADJUSTED TO PROPER LINE AND GRADE
 BY THE CONTRACTOR PRIOR TO AND AFTER THE PLACING OF PERMANENT PAYING,
 UTILITIES MUST BE MAINTAINED TO PROPER LINE AND GRADE
 BY THE CONTRACTOR PRIOR TO AND AFTER THE PLACING OF PERMANENT PAYING,
 UTILITIES MUST BE MAINTAINED TO PROPER LINE AND GRADE DURING CONSTRUCTION
 OF THE PAYING FOR THIS DEVELOPMENT.

5 89'24'38" W 560.6

- BACKFILL FOR UTILITY LINES SHOULD BE CAREFULLY PLACED SO THAT THEY WILL BE BACKFILL FOR UTILITY LINES SHOULD BE CAREFULLY PLACED SO THAT THEY WILL BE STABLE WHERE UTILITY LINES PASS THROUGH THE PARKING LOT, THE TOP 6" SHOULD BE COMPACTED SIMILARLY TO THE REMAINDER OF THE LOT. UTILITY DITCHES SHOULD BE VISUALLY INSPECTED DURING THE EXCAVATION PROCESS TO ENSURE THAT UNDESKRABLE FILL IS NOT USED IF ROCK IS ENCOUNTERED IN THE TRENCH, ROCK SPOILS SHALL NOT BE USED IN THE UPPER I. 5" OF THE TRENCH. THE UPPER I. 5" OF THE TRENCH IS TO BE BACKFILLED ONLY WITH OUALITY TOPSOIL.
- WITH QUALITY TOPSOIL
- WITH QUALITY TOPSOIL.

 ANY UTILITY INSTALLED OUTSIDE OF AN EASEMENT SHALL BE INSTALLED BY A
 PLUMBER AND INSPECTED BY CODE ENFORCEMENT.

 ALL DUCTILE IRON FITTINGS SHALL BE OF THE MECHANICAL JOINT TYPE OR SLIP JOINT
 AND SHALL BE CLASS D, OR CLASS 250 ON SIZES 12" AND SMALLER IN ACCORDANCE
 WITH A W.W.A. SPECIFICATIONS C-110-64 AND C-111-64 UNLESS OTHERWISE APPROVED

 DATE: CONT.
- BY THE CITY.

 ALL 6" AND SMALLER WATER MAINS SHALL HAVE A MINIMUM COVER OF 42"; ALL 8"
 AND LARGER WATER MAINS SHALL HAVE A MINIMUM COVER OF 48" OR SUFFICIENT
 COVER TO CLEAR OTHER UTILITIES AS MEASURED FROM TOP OF PIPE TO EXISTING
 GROUND LEVEL OR FINISHED GRADE, WHICHEVER IS GREATER.
- ALL GATE VALVES SHALL BE CITY APPROVED.
- ALL WATER AND SANITARY MAINS AND SERVICES SHALL HAVE A 10' MIN. LATERAL
- CONCRETE BLOCKING SHALL BE PROVIDED ON WATER MAINS AT ALL TEES, FIRE HYDRANTS, AND BENDS PER CITY STANDARDS. PAYMENTS FOR CONCRETE BLOCKING SHALL BE SUBSIDIARY TO PIPE INSTALLATION AND SHALL BE INCLUDED IN THE BID PRICE THEREOF.
- CLASS "H" EMBEDMENT, PER SD-20, SHALL BE USED FOR PVC WATER MAINS.
- ALL WATER METERS TO BE PLACED IN A NON-TRAFFIC AREA

AREA LABEL AREA (ac)

FLOW (cfs) Q = cIA

DRAINAGE AREA CALCULATIONS

OEFFICIEN

0.35

0.35

0.35

0.35

0.95

0.35

TIME OF CONCENTRATION

c = 0.35I = 6.83 (in/hr)tc = 20 (min.)

> TOTAL AREA

(AC.)

0.66

1.45

1.08

0.08

0.04

DRAINAGE



GRAPHIC SCALE

1'' = 30'

Q(100)

CFS

1.58

3.47

5.38

7.01

0.19

1.63

1(100)

6.83

6.83

6.83

6.83

6.83



DESIGN, LLC


8 PLANNING


> 国 国 ROCKWALL, TEXAS STONE AT OF] ARK CITY


WHS CHECKED: MHS OCT 2015 SCALE: AS SHOWN 15-006

of 16

Feat. (Concre







*

DESIGN,

8

STONE CREEK

ARK


2

WHS

OCT 2015 N/A 15-006

of 16

CITY OF ROCKWALL, TEXAS



West Ninth Stre ler, Texas 75701 903-597-6606 3-597-0517 Fax



SHM


PLAYGROUND DETAIL
THE PARK AT STONE CREEK
CITY OF ROCKWALL, TEXAS

DRAWN: HNR
CHECKED: MHS

DATE: OCT 2015

SCALE: AS SHOWN JOB NO.: 15-006

ALL SITE FURNITURE TO BE PROVIDED & INSTALLED BY CITY



PAVILION TO BE IBC 2009 PAVILION LOADS TO BE 90 MPH WINDS AND 5 LBS SNOW nth Street s 75701


212 West Ninth Str Tyler, Texas 7570, 903-597-6606 903-597-0517 Fax



LANNING & DESIGN, LLC

PAVILION DETAILS
THE PARK AT STONE CREEK
CITY OF ROCKWALL, TEXAS

DRAWN: HNR
CHECKED: MHS
DATE: OCT 2015
SCALE: AS SHOWN
JOB NO.: 15-006



ION PLAN
STONE CREEK

UNTER N. RUS

DESIGN,

8


PLANNING


IRRIGATION PLA
THE PARK AT STONE CR
CITY OF ROCKWALL, TEXAS

DRAWN: HNR
CHECKED: MHS

OCT 2015

CALE: AS SHOWN OB NO.: 15-006








& DESIGN


S STONE CREEK DET ATION AT ST THE PARK CNIC

CITY OF ROCKWALL, TEXAS

HNR HECKED: MHS OCT 2015 SCALE: AS SHOWN

PI






NOTICE TO CONTRACTORS

THE CONTRACTOR SHALL NOTIFY THE CONSULTANT IMMEDIATELY, IN WRITING, OF ANY DISCREPANCIES OR OMISSIONS TO THE TOPOGRAPHIC INFORMATION. THE CONTRACTOR(S) SHALL BE RESPONSIBLE FOR CONFIRMING THE LOCATION (HORIZONTAL/VERTICAL) OF ANY BURIED CABLES, CONDUITS, PIPES, AND STRUCTURES (STORM SEWER, SANITARY SEWER, WATER, GAS, TELEVISION, TELEPHONE, ETC.) WHICH IMPACT THE CONSTRUCTION SITE. THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND CONSULTANT IF ANY DISCREPANCIES ARE FOUND BETWEEN THE ACTUAL CONDITIONS VERSUS THE DATA CONTAINED IN THE CONSTRUCTION PLANS. ANY COSTS INCURRED AS THE RESULT OF NOT CONFIRMING THE ACTUAL LOCATION (HORIZONTAL/VERTICAL) OF SAID CABLES, CONDUITS, PIPES, AND STRUCTURES SHALL BE BORNE BY THE CONTRACTOR. ADDITIONALLY, THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND CONSULTANT IF ANY ERRORS OR DISCREPANCIES ARE FOUND ON THE CONSTRUCTION DOCUMENTS (PS&E), WHICH NEGATIVELY IMPACT THE PROJECT. CONSULTANT AND OWNER SHALL BE INDEMNIFIED OF PROBLEMS AND/OR COST WHICH MAY RESULT FROM CONTRACTOR'S FAILURE TO NOTIFY CONSULTANT AND OWNER.

*** STOP! CALL BEFORE YOU DIG! ***


AS REQUIRED BY "THE TEXAS UNDERGROUND FACILITY DAMAGE PREVENTION AND SAFETY ACT," TEXAS ONE CALL SYSTEM MUST BE CONTACTED (800-245-4545) AT LEAST 48 HOURS PRIOR TO ANY EXCAVATION OPERATIONS BEING PERFORMED, IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT TEXAS ONE CALL SYSTEM.

NOTE: SEE GRASSING PLAN FOR LOCATION OF SIGN & BOULDER



BOULDER FOR BRONZE PLAQUE LOCATION TO BE STAKE AND APPROVED BY CONSULTAN

NOTE: 30" L x 24" D x 24" H BOULDER W/ FLAT SURFACE LARGE ENOUGH TO MOUNT BRONZE PLAQUE. SANDBLAST AREA FOR PLAQUE TO ½" DEEP RECESS AND MOUNT PER MANUFACTURERS INSTRUCTIONS.



FISHING PIER DETAIL

6" DURASLOT® WITH 6" SLOT






PLAN VIEW

ELEVATION

HCPS DWG #PI-3




PERMANENT BRONZE PLAQUE BY OWNER

PLAQUE SPECIFICATIONS
BRONZE TABLET SHALL BE AS MANUFACTURED BY THE SOUTHWELL COMPANY, P.O. BOX 299, SAN ANTONIO, TEXAS 78291-0299, OR APPROVED EQUAL. PLAQUE TO BE CAST OF VIRGIN NOOTS (85-5-5-5 STD U.S. BRONZE ALLOY,) CASTING SHALL BE FREE OF PITS AND GAS HOLES AND ALL LETTERS SHALL BE SHAPE AND HAND TOOLED. BORDER AND FACES OF RAISED LETTERS ARE TO BE SATIN FINISH AND BACKGROUND IS TO BE LEATHERETTE TEXTURE.


BACKGROUND SHALL BE OXIDIZED, PLAQUE SHALL BE CHEMICALLY CLEANED, AND TWO COATS OF CLEAR ACRYLIC LACQUER SHALL BE SPRAYED ON COMPLETED PLAQUE.


TABLET IS TO BE OF SIZE SHOWN ON PLANS WITH A DOUBLE LINE BORDER DESIGN, LETTER STYLE SHALL BE CLASSIC.


CONTRACTOR SHALL FURNISH CONSULTANT WITH RUBBING OF ACTUAL PATTERN FOR APPROVAL PRIOR TO CASTING













8

S AIII

DET.

NEOUS

MISCELL

STONE CREEK ROCKWALL, TEXAS AT PARK OF CITY ((+)

HNR CHECKED: MHS OCT 2015 SCALE: AS SHOWN

JOB NO.: 15-006