

1+40.1
CONST. 4" M.H.
ON EXIST. 6" SAN. SEWER

P.C. 1+40.1
A = 44° 20' 00"
R = 120.00'
T = 32.34'
L = 63.70'

P.T. 2+03.8

2+43
CONST. 4" M.H.

SAWCUT, REMOVE &
REPLACE CONC. PAVING.

5+24
END OF C.O.

INSTALL:
1- TAPPING & SLEAVE
1- 4" GATE VALVE

INSTALL:
1- FLUSH VALVE

ALAMO STREET

EXIST. 16" WATER

NOTES:

1. All Water and Sanitary sewer lines are 6" unless otherwise noted.
2. Water meter boxes are 18" off back of curb.
3. Sanitary sewer services to have not less than 1.00 % min. grade or more than 25.0 % max. grade. If service exceeds max. grade, a drop connection should be used.
4. All Water services are to the center of lot.
5. All Sanitary sewer services are 10' off center of Lot on the downstream side, unless otherwise noted.

LINE "A"

Existing Ground @ Pipe



AS BUILT

WATER & SANITARY SEWER
AMACHRIS PLACE
ROCKWALL, TEXAS
HAROLD L. EVANS & CONSULTING ENGINEER

DESIGN	DRAWN	DATE	SCALE	NOTES	FILE	NO.
G.C.N	P.N.	6-9-80	1" = 20' H 1" = 6' V.			8037