



**LEGEND**

- 6" CONC. PAVEMENT @ 4000 PSI
- FIRELANE STRIPPING
- ACCESS EASEMENT
- EXISTING WATER LINE
- PROPOSED WATER LINE
- EXISTING SANITARY SEWER
- PROPOSED SANITARY SEWER LINE
- PROPOSED SANITARY SEWER MANHOLE
- EXISTING SANITARY SEWER MANHOLE

NOTE: MARK FIRELANE TO CITY SPECIFICATIONS. "NO PARKING FIRELANE" EVERY 25' IN WHITE 4" LETTERS ON A 6" RED STRIPED BACKGROUND

NOTE:  
PLUMBING CONTRACTOR SHALL CONNECT GREASE TRAP TO EXISTING SANITARY SERVICE.

ALL DIMENSIONS AND RADII ARE TO FACE OF CURB

NOTE: ALL SERVICES TO HAVE DOUBLECHECK VALVES AND BACKFLOW PREVENT.

ALL WATER TO BE CLASS 200 PVC

MANHOLES TO BE SEALED.

FIRELANE MUST BE INSPECTED BY FIRE DEPARTMENT PRIOR TO COVERING.

FIRELANE MINIMUM 6" CONCRETE @ 3600 PSI (6 SACK FOR MACHINE AND 6.5 SACK FOR PULLED)

NO SAND UNDER PAVEMENT

**RECORD DRAWING**

THIS DRAWING HAS BEEN REVISED TO REFLECT CONSTRUCTION RECORDS MAINTAINED AND PROVIDED BY THE CONTRACTOR FOR THIS PROJECT.

CONTRACTOR = DEAN CATHY  
DATE REVISED = 5-14-09



THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY W.L. DOUPHRATE II TEXAS P.E. NO. 60102 ON

**DOUPHRATE & ASSOCIATES, INC.**  
ENGINEERING - PROJECT MANAGEMENT - SURVEYING  
22535 RIDGE RD., # 200 ROCKWALL, TEXAS 75087  
PHONE: (972)771-9004 FAX: (972)771-9005

PAVING AND DIMENSIONAL CONTROL PLAN  
BIN 303 RESTAURANT  
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS

REVISION	
W.L.D.	CHECKED
D.A.C.	DRAWN
09/08	DATE
0808 PAV-DC	PROJECT