



APPROX. WALL FACIA = 250 SQ. FT.
 APPROX. FLAGSTONE FACE AREA = 315 SQ. FT.
 APPROX. FILTER FABRIC = 100 SQ. YDS.

APPROX. DRAIN ROCK = 9 CU. YDS.
 APPROX. 8"x12" RIP RAP FILL = 15 CU. YDS.

MAX. 3(H):1(V) SLOPE BEHIND WALL
 NO LIVE OR DEAD LOADS WITHIN 10.0 FT.
 BEHIND WALL

LAYOUT WALL PER CIVIL PLANS
 CONSIDERING WALL FACE
 BATTER OF 1(H):16(V)

SCALE WALL STEP LOCATIONS FROM WALL
 PROFILE, STEP LOCATIONS MAY VARY BY
 1-3 FEET HORIZONTALLY

LOOKING AT FACE OF WALL

MIN. WALL EMBEDMENT = 1.0 FT.
 LEVEL SLOPE IN FRONT OF WALL

WALL 1 PROFILE

SCALE: HORIZ. 1" = 10'
 VERT. 1" = 5'

Scott Miller Consulting Engineer, Inc.
 Texas Registered Engineering Firm
 F-003643



CARENOW MASONRY WALL		
ROCKWALL, TEXAS		
WALL PROFILE		
DRAWN BY: SAM	DATE: 10/11/17	SHEET 3 OF 6