

[illegible]

1. All necessary conduit installations shown on print.
2. Developer to furnish and install all conduit as shown on print.
3. Texas Power and Light to furnish cable markers.
4. Developer to install 1 (one) cable marker at each end of conduit.
5. All conduit to be Schedule 40 and minimum of 3" in diameter.
(Unless otherwise noted.)
6. Each conduit must be buried a minimum of 40" deep (after land is brought to final grade).
7. Each conduit must have a pull wire installed and be capped at both ends.
8. It shall be the responsibility of the Developer to obtain inspection and approval of conduit installation from Texas Power and Light.
9. The Developer shall contact Texas Power and Light prior to construction to insure proper layout.

1. Where water pipelines either cross or otherwise come within 9 feet of a Sanitary Sewer Pipeline the sewer pipeline shall be either cast iron or PVC pipe with a minimum working pressure class of 150 PSI.
2. It shall be the responsibility of the contractor to locate and verify all existing utilities prior to the beginning of construction to insure no conflicts between all utility lines.

SCALE	DATE	JOB NO.
1" = 50'	8-14-86	72122



AS BUILT