

SANITARY SEWER SYSTEM SUMMARY							
LINE DESIGNATION	MANHOLE		RESIDENTIAL FLOW		PEAK INFILTRATION		
	FROM	TO	CUMULATIVE POPULATION	AVE. DRY DAY FLOW (gpm)	MAX. DRY DAY FLOW (gpm)	INFL. (gpm)	(gpm)
LINE "A"	14+37.03	16+63.45	(2) 5.6	0.39	0.97	0.03	0.41
	11+33.67	14+37.03	(10) 28	1.94	4.86	0.04	1.98
	8+76.13	11+33.67	(20) 56	3.89	9.72	0.03	3.91
	6+20.32	8+76.13	(9) 86.8	6.03	15.07	0.03	6.06
	3+71.37	6+20.32	(34) 95.2	8.61	16.53	0.03	8.64
	1+47.70	3+71.37	(39) 109.2	7.58	18.96	0.03	7.61
LINE "A"	0+85.49	1+47.70	(40) 112	7.78	19.44	0.02	7.80
LINE "B"	0+00	1+65	(2) 5.6	0.39	0.97	0.02	0.41
LINE "C"	0+00	1+95	(4) 11.2	0.78	1.94	0.02	0.80
LINE "D"	0+00	3+45	(9) 25.2	1.75	4.37	0.04	1.79
LINE "E"	0+00	2+55	(6) 22.4	1.56	3.89	0.03	1.59
LINE "F"	0+00	2+15	(6) 16.8	1.17	2.92	0.03	1.20
LINE "G"	0+00	3+50	(7) 19.6	1.36	3.40	0.04	1.40
LINE "H"	0+00	6+03	(7) 19.6	1.36	3.40	0.08	1.42

