

NOTE: NO WORK IN 404 AREA

LAKEFRONT TRAIL
VARIABLE WIDTH R.O.W.

NOTE: CONTOURS SHOWN ON BUILDINGS AND
BETWEEN BUILDINGS ARE SUB-GRADE.
CONTOURS SHOWN IN PARKING AREAS
ARE FINISHED GRADE.

NOTE: FOR RETAINING WALL DETAILS & SECTIONS
SEE TBG PARTNERS PLANS.
FOR GRADING OUTSIDE OF PARKING
SEE TBG PARTNERS PLANS.

FIRE LANES
6" THICK 3600 PSI REINF.
CONC. PAVING W/ #3 BARS
24" O.C.E.W.

PARKING AREAS
5" THICK 3600 PSI REINF.
CONC. PAVING W/ #3 BARS
24" O.C.E.W.
18.5' SPECIAL SPACE
W/ 2' OVERHANG
20.5 REGULAR

6" THICK LIME
STABILIZED SUB GRADE
COMPACTED TO 95% STANDARD
PROCTOR DENSITY
TYPICAL PAVING DETAIL
(INVERT MAY BE LOCATED IN PARKING STALLS)

LEGEND
X TC ELEVATION
X EXIST. TOP OF CURB
X PROPOSED TOP OF CURB
X ELEVATION
X PROPOSED FINISHED PAVING
ADD 400 TO PROPOSED ELEVATIONS



Received from Engineer
8/15/08
RECORD DRAWINGS

REV.		10/4/04	SOLID STRUCTURAL SOLUTIONS, INC.			GRADING AND PAVING		SHEET NO.
REV.		7/27/04	P.O. BOX 851830			THE HARBOR - ROCKWALL		14
REV.		7/15/04	MESQUITE, TX 75185-1880					26
REV.		5/29/04	PHONE: 972.417.8830					
REV.		6/3/04	FAX: 972.288.9714					
REVISION DESCRIPTION			DATE	SCALE	DESIGN	DRAWN	JOB NO.	
0136RDS				1" = 30'	H.L.E.		0136	
						CITY OF ROCKWALL		