



NOTE - Electrical Service to Lift Station to be by underground conduit from nearest TP & L Co. power pole. Contractor to install meter on TP & L pole with Nema 3R Enclosure below with 3 pole circuit breaker in accordance with local and State code requirements.

- LIFT STATION NO. 2**
- * AVERAGE FLOW = 99,980 gpd = 69.43 gpm (Ave) = 225 max.
 - * 225 gpm @ 40.0 T.D.H.
 - * 40 SW TORAN DUAL IMPELLER
 - * 5 H.P.

LIFT STATION DETAILS

HAROLD L. EVANS
CONSULTING ENGINEER
2331 GUS THOMSON RD. SUITE 102
DALLAS, TEXAS 75228
PHONE (214) 328-8133

SAN. SEWER IMPROVEMENTS
FOR HARLAN PARK - PHASE ONE
CITY OF ROCKWALL
ROCKWALL COUNTY, TEXAS

SCALE	DATE	JOB NO.
N.T.S.	6-18-85	03213