



- GENERAL NOTES**
- 1) EXISTING 15' CURB INLET SHALL BE MODIFIED TO 7.5' CURB INLET.
 - 2) 3,000 P.S.I. CONCRETE SHALL BE USED FOR REPLACEMENT.
 - 3) WHEN SAWCUTTING EXISTING CONCRETE REBARS SHALL BE SALVAGED OR NEW REBARS SHALL BE DOWELED INTO EXISTING CONCRETE.
 - 4) CONCRETE CURB AND PAVEMENT RECONSTRUCTION SHALL CONFORM TO THE CITY OF ROCKWALL STANDARD SPECIFICATIONS.

AS BUILT

REVISION DESCRIPTION		DATE	SCALE	DESIGN	DRAWN	HAROLD L. EVANS & ASSOCIATES Consulting Engineers P.O. Box 28355 2331 Gus Thomasson Road, Suite 102 Dallas, Texas 75228 (214) 328-8133	HARRIS HEIGHTS ADDN. PHASE TWO CITY OF ROCKWALL ROCKWALL COUNTY, TEXAS	SHEET NO. 1/1 JOB NO. 83235
		4-27-87	1" = 100'	H.L.E. & A.	H.L.E. & A.			

TELETYPE POST