



LEGEND

- 635 -	EXISTING CONTOURS
- 635 -	PROP. CONTOURS
[Pattern]	STABILIZED CONSTRUCTION ENTRANCE 20'x50' MIN. 12" THICK MIN., 4"-6" STONES
[Dashed Line]	SILT FENCE
[Pattern]	STONE OVERFLOW STRUCTURE
[Dashed Box]	INLET PROTECTION

SITE ACRES = 11.235 AREA OF DISTURBANCE = 10.232 ACRES

- GENERAL CONSTRUCTION SEQUENCING & PHASING**
- I. INSTALL TEMPORARY STAGING AREAS, STABILIZED CONSTRUCTION ENTRANCE & SILT FENCE PRIOR TO COMMENCEMENT OF WORK.
 - II. DEMOLISH EXISTING STRUCTURES.
 - III. STRIP SITE.
 - IV. ROUGH GRADE SITE.
 - V. CONSTRUCT BUILDING PAD.
 - VI. INSTALL UTILITIES & INLET PROTECTION.
 - VII. PAVE SITE & REMOVE STABILIZED CONSTRUCTION ENTRANCE.
 - VIII. SOIL STABILIZATION/SEEDING THROUGHOUT THE SITE EXCEPT AREAS TO BE PAVED.
 - IX. RELOCATE SILT FENCING AS NECESSARY & REMOVE INLET PROTECTION.

*****NOTICES TO CONTRACTOR*****

EXISTING UNDERGROUND/BURIED PUBLIC, PRIVATE, AND FRANCHISE UTILITIES/FACILITIES AFFECT THIS SITE, AND ARE DEPICTED ON THE PLANS FOR THE BEST AVAILABLE INFORMATION AT THE TIME THE PLANS WERE PRODUCED. WINKELMANN & ASSOC., INC. SHALL NOT BE RESPONSIBLE FOR KNOWING THE EXACT LOCATION OF ALL FACILITIES OR DEPICTING EXACT LOCATIONS OF SAID FACILITIES ON THE PLANS BEYOND WHAT IS STATED ABOVE.

CONTRACTOR(S) SHALL CALL "811" A MINIMUM OF 48 HOURS PRIOR TO BEGINNING WORK ON THE SITE, AND SHALL NOT BEGIN ANY EXCAVATION OR DEMOLITION ACTIVITIES UNTIL AFTER SAID FACILITIES HAVE BEEN MARKED AND/OR FLAGGED PER "811" OR THE FACILITY OWNERS.

CONTRACTOR(S) SHALL BE WHOLLY RESPONSIBLE FOR ANY DAMAGE THAT MAY OCCUR TO SAID FACILITIES DUE TO WORK BEING DONE WITHOUT FOLLOWING THE PROCEDURES ABOVE.

COORDINATION BETWEEN SITE GENERAL CONTRACTOR AND BUILDING GENERAL CONTRACTOR WILL BE NECESSARY. DAMAGE TO ANY EROSION CONTROL MEASURE MUST BE REPAIRED IMMEDIATELY BY THE PARTY RESPONSIBLE FOR THE DAMAGE.

ALL RESPONSIBILITY FOR ADEQUACY OF DESIGN REMAINS WITH THE DESIGN ENGINEER. THE CITY OF ROCKWALL, IN REVIEWING AND RELEASING PLANS FOR CONSTRUCTION, ASSUMES NO RESPONSIBILITY FOR ADEQUACY OR ACCURACY OF DESIGN.

- NOTES:**
1. STABILIZED CONSTRUCTION ENTRANCE, SILT FENCE TO BE INSTALLED PRIOR TO DEMOLITION, STRIPPING OF THE SITE AND GRADING.
 2. STONE OVERFLOW STRUCTURE ON SILT FENCE SHOULD BE LOCATED EVERY 300'.
 3. REFER TO PROJECT MANUAL, DIVISION 31, SECTION 31 25 00.

BENCH MARKS:

BM#1 - "X" cut inside of "a" cut at the centerline of a curb inlet, southeasterly curb line of Quail Run, ±23.6 feet northeast of the POINT OF BEGINNING.
ELEVATION - 482.71 feet

BM#2 - "X" cut at the southeast end of a curb inlet, northeasterly curb line of Memorial Drive, ±13.4 feet southeast of the southeast property corner.
ELEVATION - 472.19 feet

AS-BUILT

THIS RECORD DRAWING IS COMPILATION OF A COPY OF THE SEALED ENGINEERING DRAWING FOR THIS PROJECT, MODIFIED BY ADDENDA, CHANGE ORDERS, AND INFORMATION FURNISHED BY THE CONTRACTOR. THE INFORMATION SHOWN ON THE RECORD DRAWINGS IS PROVIDED BASED ON SURVEYING AT THE SITE AND INFORMATION PROVIDED BY THE CONTRACTOR OR OTHERS NOT ASSOCIATED WITH THE DESIGN ENGINEER. THE ORIGINAL SEALED DRAWING ARE ON FILE AT THE OFFICES OF WINKELMANN AND ASSOCIATES, INC.

Maria L. Bonilla
WINKELMANN AND ASSOCIATES, INC. 10-19-2016 DATE

LEGEND

PP	Power Pole	IRF	Iron Rod Found
GW	Guy Wire	IRS	Iron Rod Set
MH	Manhole	CIRS	Iron Rod Set w/ cap "WAI"
WV	Water Valve	CIRF	Iron Rod Found w/ cap
TP	Telephone Pedestal	XCS	"X" Cut in Concrete Set
WM	Water Meter	XCF	"X" Cut in Concrete Found
FH	Fire Hydrant	PKS	PK Nail Set
LP	Light Pole	PKF	PK Nail Found
IV	Irrigation Valve	SS	Sanitary Sewer
CO	Clean Out	SW	Storm Sewer
AC	Air Conditioner	TF	Transformer pad
TV	Cable Box	GM	Gas Meter
SB	Signal Box	GMK	Gas Marker
SP	Signal Pole	TSN	Traffic Sign
SN	Sign	UGC	Underground Cable Marker
CM	Control Monument	EB	Electric Box
		EM	Electric Meter

6.					
5.					
4.					
3.					
2.	12/18/2015	ISSUE FOR CONSTRUCTION	M.B.		
1.	12/09/2015	BULLETIN #1	M.B.		
No.		REVISION			APPROV

Winkelmann & Associates, Inc.
CONSULTING CIVIL ENGINEERS ■ SURVEYORS
720 HILGRET PLAZA DRIVE, SUITE 325
ROCKWALL, TEXAS 75087
(972) 460-7099
FAX (972) 460-7098
Professional Registration No. 89
Professional Engineer Registration No. 100866-00
Professional Surveyor Registration No. 100866-00
Professional Land Surveyor Registration No. 100866-00

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MARIA C. BONILLA-NICHOLS, P.E. # 100106

10-19-2016

EROSION CONTROL PLAN PHASE 1
SEC N. GOLIAD ST. AND E. QUAIL RUN RD., ROCKWALL, TEXAS

C-14.01
DAL574

LAST SAVED BY: WINKELMANN October 20, 2016