



GENERAL NOTES:

1. ALL CONCRETE PAVING TO BE 3600 PSI (6.5 SACK) CONCRETE
2. ALL CONCRETE PAVING TO BE OVER 6" LIME STABILIZED SUBGRADE.
3. ALL CONCRETE TO BE TESTED BY CONTRACTOR.
4. ALL FILL WILL BE COMPACTED TO 95% STANDARD DENSITY BY MEANS OF A SHEEP'S FOOT ROLLER