

DATE	2/1/01	SCALE	1" = 60'	H.T.R.	
DESIGN		DRAWN			
CONSULTING ENGINEER	HAROLD G. EVANS				
P.O. BOX 28365	2331 CUS THOMASSON ROAD, SUITE 102				
PHONE	DALLAS, TEXAS 75228, (214) 328-8133				

REVISION DESCRIPTION	DATE
REV. PER 2nd CITY REVIEW	5/12/01
REV. PER 4th CITY REVIEW	7/13/01
REV. PER 5th CITY REVIEW	7/25/01
ADDED WALL	7/13/02
REVISED POND GRADE	8/24/02



BENCH MARK IN CONCRETE AT BASE OF SAVANNAH CUT  
 60D MALL IN 34' PECAN TREE (TREE NO. 2314)  
 PAY STA. 1+83.138 RT. AUDOBON LANE  
 ELEV. 480.88

BENCH MARK  
 3048E CUT  
 CONCRETE APPROACH TO BRIDGE OVER  
 SQUABLE CREEK ON HWY. 205  
 ELEV. 422.41

BENCH MARK  
 60D MALL IN 18' PECAN TREE (TREE NO. 2114)  
 60D MALL IN 8+30.71 RT. MEMORIAL DRIVE  
 PAY STA. 10+97.635 RT. AUDOBON LANE  
 ELEV. 466.79



**NTMWD Notes**

A. North Texas Municipal Water District (NTMWD) 30-inch water transmission pipeline is located within limits of construction.

B. Operation of heavy earthmoving equipment, compaction equipment or heavy construction equipment, such as concrete trucks, shall be restricted to specific crossings designated and verified to provide a minimum of five-feet of cover.

C. To assure that placing of significant loads over the NTMWD pipeline does not damage the existing pipeline, no materials shall be stockpiled on the NTMWD easement without authorization from the NTMWD. If the contractor desires to use NTMWD's easement for stockpile of materials, contact NTMWD Engineering at 972-442-5405 so your plans for use NTMWD's easement can be reviewed.

D. In areas where the cover between the top of NTMWD pipeline and the bottom of the sub-grade is three (3) feet or less, it is requested that sub-grade preparation be deleted and a thickened pavement section be used to limit construction activities over the pipeline.

E. Crossing of the NTMWD easement with other utilities, such as TV cable, phone, gas, and electric, shall be coordinated with the NTMWD to avoid damage to the NTMWD facilities.

F. Outdoor lighting, landscaping screening walls or other facilities shall not be installed in NTMWD easements without written approval of the NTMWD.

G. Unless otherwise shown or required, a minimum of one-foot clearance shall be provided for all utilities crossing the NTMWD easements.

H. Water and sewer lines crossing the NTMWD easements shall be installed in compliance with the Rules and Regulations for Public Water Systems Paragraph 290.44(e). Location of Water Lines

I. The contractor shall contact NTMWD Engineering at 972-442-5405 at least 48 hours prior to performing any work in the vicinity of the NTMWD facilities.

Without the Associates, Inc., hereby shall the contractor, Whitehorn & Associates, Inc. does not warrant the accuracy of the information provided by the contractor. Whitehorn & Associates, Inc. does not warrant the accuracy of the information provided by the contractor. Whitehorn & Associates, Inc. does not warrant the accuracy of the information provided by the contractor.

DATE 9-27-02

