



**CONSTRUCTION NOTES**

- ① PROPOSED FIRE HYDRANT
- ② PARKING STALLS REFER TO DETAIL SHEET 13
- ③ HANDICAP SYMBOLS REFER TO DETAIL SHEET 13
- ④ WHEEL STOPS REFER TO DETAIL SHEET 13
- ⑤ HANDICAP SIGNAGE REFER TO DETAIL SHEET 13
- ⑥ PROPOSED DUMPSTER (SEE ARCH PLANS)
- ⑦ 10' STORM CURB INLET REFER TO DETAIL SHEET 13
- ⑧ PROPOSED 30' SQUARE LIGHT POLES (SEE M.E.P. PLANS)
- ⑨ OIL / WATER SEPARATOR REFER TO ARCH PLANS
- ⑩ RETAINING WALL REFER TO ARCH PLANS
- ⑪ 4:1 TYPE "C" SLOPED HEADWALL
- L.A. LANDSCAPE AREA

**LEGEND:**

- SIDEWALK PAVEMENT  
4" - 3,000 psi (REF TO GEOTECH REPORT)  
5.5 SACK MIN. #3 BARS, 18" O.C.E.W.
  - LIGHT DUTY PAVEMENT  
5" - 3,000 psi (REF TO GEOTECH REPORT)  
5.5 SACK MIN. #3 BARS, 18" O.C.E.W.
  - HEAVY DUTY PAVEMENT  
6" - 3,600 psi (REF TO GEOTECH REPORT)  
6.0 SACK MIN. (MACHINE PLACED)  
6.5 SACK MIN. (HAND PLACED)  
#4 BARS, 18" O.C.E.W.
  - DUMPSTER & TRUCK DRIVE PAVEMENT  
7" - 3,600 psi (REF TO GEOTECH REPORT)  
6.0 SACK MIN. (MACHINE PLACED)  
6.5 SACK MIN. (HAND PLACED)  
#4 BARS, 18" O.C.E.W.
  - EXISTING CONCRETE PAVEMENT
- CITY MINIMUMS LISTED ABOVE REFER TO GEOTECHNICAL REPORT BY RONE ENGINEERS (#17-22244) FOR PAVING AND LIME TREATED SUBGRADE RECOMMENDATIONS.

**PARKING LEGEND**

- STANDARD SINGLE PARKING STALL (11'x20')
- HANDICAP PARKING STALL (11'x20')
- BACK OF CURB (11'x11')
- BACK OF CURB (11'x9'x11')

**RECORD DRAWINGS**

To the best of our knowledge Engineering Concepts & Design, L.P., hereby states that this plan is As-Built. This information provided is based on surveying at the site and information provided by the contractor.

*Todd Winters* 6-13-19  
TODD WINTERS DATE

BENCHMARK:  
"X" CUT IN CURB 23± SOUTH OF EAST DRIVE APPROACH OF EXISTING RAYBURN COUNTRY ELECTRIC BUILDING.

**ENGINEERINGCONCEPTS & DESIGN, L.P.**

ENGINEERING / PROJECT MANAGEMENT / CONSTRUCTION SERVICES - FIRM REG. #F-001145  
201 WINDCO CIR, STE 200, WYLIE, TX 75098  
972-941-8400 FAX: 972-941-8401 WWW.ECDLP.COM

REVISIONS: ADDENDUM 1 NOTE

2. 06-07-2018 MOVED WATER AND F.L.A.U.E. FOR TOWER. ADDED RETAINING WALL.	2
---	---

DRAWN: TONY	DATE: JUNE 7, 2018
CHECKED: TW	DATE: MAY 23, 2018
PROJECT NO.: 3560	
DWG FILE NAME:	

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF CONSTRUCTION.



**PAVING & DIMENSION CONTROL PLAN**  
RAYBURN ELECTRIC COOP. PHASE 2  
LOT 5, BLK 1 RAYBURN COUNTRY ADDITION  
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS