



RETAINING WALL SCHEDULE

h1	h3	L1	L2	t1	t2	REINFORCING						
						a	b	c	d	e	f	g
4'-0"	—	1'-6"	2'-6"	12"	18"	#4@12" O.C.	#5@12" O.C.	#5@12" O.C.	#4@12" O.C.	#4@12" O.C.	#4@16" O.C.	#4@12" O.C.
6'-0"	0'-9"	2'-0"	3'-9"	12"	18"	#5@10" O.C.	#5@12" O.C.	#5@12" O.C.	#4@18" O.C.	#4@12" O.C.	#4@16" O.C.	#4@12" O.C.
8'-0"	1'-3"	2'-9"	5'-0"	12"	18"	#6@10" O.C.	#7@12" O.C.	#5@12" O.C.	#4@18" O.C.	#4@12" O.C.	#4@16" O.C.	#4@12" O.C.
10'-0"	2'-0"	3'-6"	6'-3"	12"	18"	#8@10" O.C.	#8@12" O.C.	#5@12" O.C.	#4@12" O.C.	#4@12" O.C.	#4@16" O.C.	#4@12" O.C.
12'-0"	2'-6"	4'-3"	7'-9"	12"	18"	#8@7" O.C.	#8@7" O.C.	#5@10" O.C.	#4@9" O.C.	#4@12" O.C.	#4@16" O.C.	#4@12" O.C.
14'-0"	3'-0"	5'-0"	9'-3"	12"	18"	#8@7" O.C.	#8@7" O.C.	#5@10" O.C.	#4@9" O.C.	#4@12" O.C.	#4@16" O.C.	#4@12" O.C.

NOTE: FOR FOOTINGS WHERE "h1" IS BETWEEN SCHEDULED HEIGHTS USE THE TALLER SCHEDULE HEIGHT.

① TYPICAL RETAINING WALL SCHEDULE  
1/2" = 1'-0"

Retaining wall detail Sheet S3.02/01. Retaining wall height varies from 4ft to 3ft. Retaining walls have stone face and cap.