



WATER & WASTEWATER PLAN
ROCKWALL WATERFRONT PARK PACKAGE 2
ROCKWALL, TEXAS

B BROCKETTE • DAVIS • DRAKE, INC.
 Consulting Engineers
 Civil & Structural Engineering • Surveying
 4144 North Central Expressway, Suite 1100 • Dallas, Texas 75204
 (214) 824-3447 • fax (214) 824-7064

DESIGNED	DRAWN	DATE	SCALE	NOTES	FILE	NO.
TMA	BDD	10/2005	1"=50'	BDD	C03360	C4

- GENERAL NOTES:**
- ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO THE CITY STANDARD CONSTRUCTION DETAILS AND SPECIFICATIONS.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING TRAFFIC SAFETY, AND OSHA STANDARDS FOR ALL EXCAVATION OF FIVE FEET OR DEEPER.
 - THE LOCATION OF ALL UTILITIES LOCATED ON THESE PLANS ARE TAKEN FROM PUBLIC UTILITIES MUST BE DETERMINED BY THE CONTRACTOR. IT SHALL BE THE DUTY OF THE CONTRACTOR TO VERIFY THE LOCATION OF ALL UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT ALL PUBLIC UTILITIES IN THE CONSTRUCTION OF THIS PROJECT.
 - ALL WATER LINES, 6" AND LARGER SHALL BE ALL-Pipe Schedule 40 PVC LINES SMALLER THAN 2" SHALL BE SCHEDULE 80 PVC.
 - ALL DUCTILE IRON FITTINGS SHALL BE OF THE MECHANICAL JOINT TYPE OR SHALL BE IN ACCORDANCE WITH A.M.W.A. SPECIFICATION C-100-84 AND SHALL BE SMALLER IN ACCORDANCE WITH A.M.W.A. SPECIFICATION C-100-84 AND ALL WATER LINES SHALL HAVE A MINIMUM COVER OF 36" OR SUFFICIENT TO EXISTING GROUND LEVEL OR FINISHED GRADE, WHICHEVER IS GREATER.
- LEGEND:**
- PROPOSED WATER LATERAL
 - PROPOSED SANITARY SEWER LATERAL
- POST-BID ADDENDUM 2-01-08**

Copyright 2005 Brockette/Davis/Drake, Inc. All Rights Reserved. Any modification or use of the drawings without the express written authorization of Brockette/Davis/Drake, Inc. is prohibited.