



NOTES:
 1. ALL RESPONSIBILITY FOR ADEQUACY OF DESIGN REMAINS WITH THE DESIGN ENGINEER. THE CITY OF ROCKWALL, IN REVIEWING AND RELEASING PLANS FOR CONSTRUCTION, ASSUMES NO RESPONSIBILITY FOR ADEQUACY OR ACCURACY OF DESIGN.

LEGEND

- UNDISTURBED BUFFER
- EXISTING CONTOUR
- PROPOSED CONTOUR
- SILT FENCE PER NCTCOG DRAWING 1020 (NO WOOD POSTS)
- INLET PROTECTION - DROP PER NCTCOG DRAWING 1130
- INLET PROTECTION - CURB PER NCTCOG DRAWING 1140
- ROCK CHECK DAM PER NCTCOG DRAWING 1060 A & B (CRUSHED CONCRETE NOT ALLOWED)
- 50'x20' STABILIZED CONSTRUCTION ENTRANCE PER NCTCOG DRAWING 1070 A & B 12" MIN THICKNESS, 4"-6" ROCK (CRUSHED CONCRETE NOT ALLOWED)
- CONCRETE WASHOUT
- DIRECTION OF FLOW
- PROPOSED STORM SEWER
- EXISTING STORM SEWER
- EX 30" RCP

TOTAL SITE AREA (INCLUDING ADJOINING ROW) ~ 2.1 ACRES
 TOTAL DISTURBED AREA ~ 1.7 ACRES

OWNER/DEVELOPER
 CLAY SHIPMAN FIRE PROTECTION, LLC
 7700 CODY LANE
 SUITE 2705
 SACHSE, TEXAS 75048



April 14, 2019

RECORD DRAWING
 TO THE BEST OF OUR KNOWLEDGE, USA PROFESSIONAL SERVICES GROUP, INC. HEREBY STATES THAT THIS RECORD DRAWING IS BASED ON VISUAL SITE OBSERVATIONS, SURVEY INFORMATION, AND INFORMATION PROVIDED BY THE CONTRACTOR.
 DATE: JUNE 16, 2020

BENCHMARKS:
 #1 "□" CUT ON EXISTING "Y" INLET ±74' FROM THE NORTHWEST CORNER OF PROPERTY. ELEV. 493.46
 #2 "□" CUT ON BACK OF CURB ±12' IN FRONT OF EXISTING SANITARY SEWER MANHOLE ±66' FROM THE NORTHEAST CORNER OR PROPERTY LINE. ELEV. 497.98

14
 15

EROSION CONTROL PLAN	
SHIPMAN OFFICE BUILDING	
CITY OF ROCKWALL	
ROCKWALL COUNTY, TEXAS	
USA PROFESSIONAL SERVICES GROUP, INC. 1525 MCEROY DRIVE, DALLAS, TX 75235 214-434-3300 PHONE 214-634-3338 FAX REGISTERED ENGINEERING FIRM F-1845 REGISTERED SURVEYING FIRM 101074-00	USA JOB NUMBER 2018006.00