



The seal appearing on this document was authorized by Warren L. Corwin, P.E. 57875, on May 29, 2009

0 25 50 100
SCALE: 1" = 50'

AS-BUILT MAY 2009
TO THE BEST OF OUR KNOWLEDGE CORWIN ENGINEERING, INC., HEREBY STATES THAT THIS PLAN IS AS-BUILT, THIS INFORMATION PROVIDED IS BASED ON SURVEYING AT THE SITE AND INFORMATION PROVIDED BY THE CONTRACTORS.

- Wall Notes:**
- No part of the wall/footing, tie back etc. shall be const. offsite, in an easement or in the R.O.W. Walls must be on one property.
 - All walls 4' or taller shall require a signed/sealed set of engineered drawings. Wall engineer shall submit signed/sealed letter prior to acceptance stating that the walls were constructed per drawings.
 - All fill to be compacted to 95% std. density using a sheep's foot roller.

- RETAINING WALL
- EXIST. TREE
- 500.61 100-YEAR WATER SURFACE ELEVATION

2.	CHANGED TOP OF WALL ELEVATIONS ON BLOCK B		
1.	ADDED WALLS SEE CLOUDED AREAS		
NO.	REVISIONS	BY	DATE
CORWIN ENGINEERING, INC. 200 W. BELMONT, SUITE E ALLEN, TEXAS 75013 (972) 396-1200 TBPE FIRM #5951			
DEVELOPMENT PLANS FOR STONE CREEK PHASE I ROCKWALL, TEXAS			
GRADING PLAN			
DRAWN BY	DESIGNED BY	CHECKED BY	SHEET NO.
	CEI	CEI	
JOB NUMBER	DATE	SCALE:	
08033	JANUARY 2008	1"=50'	59 of 62