


**CIVIL CONSTRUCTION PLANS FOR
 ROCKWALL ASC EXPANSION & REMODEL
 LOT 3R, BLOCK B
 THE WOODS AT ROCKWALL ADDITION NO. 1
 825 YELLOW JACKET LANE
 OCTOBER, 2011**

**NOT
 AS-BUILT**

FILE



LOCATION MAP

NTS
 MAPSCO : 30C-C

SHEET INDEX

| SHEET NO. | DESCRIPTION |
|-----------|---|
| C1 | COVER SHEET |
| A1.02 | SITE PLAN |
| C2 | CIVIL PLANS (GRADING AND DRAINAGE PLAN) & (DIMENSIONAL CONTROL PLAN) |
| C3 | EROSION CONTROL & DEMOLITION PLAN |

OWNER
 ROCKWALL ASC REAL ESTATE, L.L.C.
 ATTN. MS. GINGER WHITE
 825 W. YELLOW JACKET LANE
 ROCKWALL, TEXAS 75032
 (972) 772-6166
 gwhite@uspl.com

ENGINEER/SURVEYOR
 GONZALEZ & SCHNEEBERG
 ATTN. ROBERT SCHNEEBERG
 660 N. CENTRAL EXPRESSWAY, SUITE 250
 PLANO, TEXAS 75074
 (972) 516-8855
 (972) 516-8901 fax
 robert.schneeberg@gs-engineers.com

RELEASED FOR CONSTRUCTION
 ALL RESPONSIBILITY FOR ADEQUACY OF DESIGN
 REMAINS WITH THE DESIGN ENGINEER. THE CITY
 OF ROCKWALL, IN REVIEWING AND RELEASING
 PLANS FOR CONSTRUCTION, ASSUMES NO
 RESPONSIBILITY FOR ADEQUACY OR ACCURACY
 OF DESIGN.

"ALL RESPONSIBILITY FOR ADEQUACY OF
 DESIGN REMAINS WITH THE DESIGN
 ENGINEER. THE CITY OF ROCKWALL, IN
 REVIEWING AND RELEASING PLANS FOR
 CONSTRUCTION, ASSUMES NO
 RESPONSIBILITY FOR ADEQUACY OR
 ACCURACY OF DESIGN."



THE SEAL APPEARING ON THIS DOCUMENT WAS
 AUTHORIZED BY ROBERT W. SCHNEEBERG, P.E. 68352 ON
 10/07/2011. ALTERATION OF A SEALED DOCUMENT
 WITHOUT PROPER NOTIFICATION TO THE RESPONSIBLE
 ENGINEER IS AN OFFENSE UNDER THE TEXAS
 ENGINEERING PRACTICE ACT.




CITY *ajw* 1-10-12
 DATE

| NO. | DATE | REVISION |
|-----|------|----------|
| | | |

DATE: SEPTEMBER, 2011
 PROJ. NO.: 4950-11-03-01
 DWG. NO.: 4950cov.dwg

ROCKWALL ASC EXPANSION & REMODEL
 LOT 3R, BLOCK B, THE WOODS AT ROCKWALL ADDITION NO. 1

C1



NOTES REGARDING RETAINING WALL

Contractor shall remove existing retaining wall as shown and extend wall in the general location shown. Site shall be graded as necessary to obtain smooth transitions at the end of the wall and to conform with the requirements of the wall design described herein. In no case shall any slope on this property exceed the ratio of 1 foot of vertical rise in 3 feet of horizontal distance.

Wall shall be constructed of Segmental Block Units of size and color to match existing wall construction. Contractor shall provide drawings detailing this construction which have been signed and sealed by a Professional Engineer licensed to practice in the State of Texas. Additionally, the Contractor shall be responsible for submittal and approval of the drawings by the City of Rockwall.



Record drawings of the existing retaining wall are available from the project architect.

ADA COMPLIANCE:

Contractor shall be responsible for insuring that all sidewalks and accessible routes are constructed with a maximum running slope of less than 5% and a maximum side slope of less than 2%. Additionally he shall insure that all applicable rules and requirements of the ADA accessibility standards are met.

LEGEND

| | |
|-----------|---|
| TW=491 | PROPOSED TOP OF WALL |
| BW=486 | BOTTOM OF WALL |
| TC=493.02 | PROPOSED TOP OF CURB |
| G=492.52 | GUTTER |
| | EXISTING TOP OF CURB |
| | GUTTER |
| | PROPOSED 6" CONCRETE PAVEMENT |
| | * 8" THICK FOR NEW PAVEMENT IN FIRELANE |
| | PROPOSED 4" CONCRETE SIDEWALK |
| | DOWELL ON CONCRETE PAVEMENT |



PLANS FOR CONSTRUCTION

RESPECTABILITY FOR ADEQUACY OF DESIGN

CONSTRUCTION ENGINEER'S SEAL

Robert W. Schneberg
 Registered Professional Engineer
 No. 66552
 State of Texas

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY ROBERT W. SCHNEBERG, P.E. 66552 ON 10/07/2011. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO THE RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.

Gonzalez & Schneberg
 engineers - surveyors
 680 N. Central Expressway
 Suite 250, Plano, Texas 75074
 (972) 616-8855 Fax: (972) 616-8801

CIVIL PLANS

LOT 3R, BLOCK B, THE WOODS AT ROCKWALL ADDITION NO. 1


ROCKWALL ASC EXPANSION & REMODEL

CITY OF ROCKWALL, TEXAS

| DESIGN | DRAWN | DATE | SCALE | NOTES | FILE | NO. |
|--------|-------|----------------|--------|-------|------|-----|
| GSES | GSES | SEPTEMBER 2011 | 1"=20' | | | |

REVISIONS

| NO. | DATE | REVISION |
|-----|------|----------|
| | | |



| Solid Waste Management | | Concrete Waste Management | |
|---|--|--|--|
| DESCRIPTION | Applications | DESCRIPTION | Applications |
| Large volumes of solid waste are often generated at construction sites including packaging, pallets, wood waste, concrete waste, soil, electrical wiring, cuttings, and a variety of other materials. The solid waste management practices listed herein are intended to minimize the potential of storm water contamination from solid waste through appropriate storage and disposal practices. | <ul style="list-style-type: none"> Perimeter Control Slope Protection Sediment Trapping Channel Protection Temporary Stabilization Permanent Stabilization Housekeeping Practices | Concrete waste at construction sites comes in two forms: 1) excess fresh concrete mix including truck and equipment washings, and 2) concrete dust and concrete debris resulting from demolition. Both forms have the potential to impact water quality through storm water runoff contact with the waste. | <ul style="list-style-type: none"> Perimeter Control Slope Protection Sediment Trapping Channel Protection Temporary Stabilization Permanent Stabilization Housekeeping Practices |
| APPLICABLE REGULATIONS | Targeted Constituents | APPLICABLE REGULATIONS | Targeted Constituents |
| These practices should be a part of all construction practices. By limiting the iron and debris on site, storm water quality is improved along with reduced clean up requirements at the completion of the project. | <ul style="list-style-type: none"> Sediment Nutrients Toxic Materials Oil & Grease Floccable Materials Other Construction Waste | A number of water quality parameters can be affected by introduction of concrete - especially fresh concrete. Concrete affects the pH of runoff, causing significant chemical changes in water bodies and harming aquatic life. Suspended solids in the form of both cement and demolition concrete waste are also generated from both fresh and demolition concrete waste. | <ul style="list-style-type: none"> Sediment Nutrients Toxic Materials Oil & Grease Floccable Materials Other Construction Waste |
| APPLICABLE REGULATIONS | Implementation Requirements | APPLICABLE REGULATIONS | Implementation Requirements |
| The solid waste management practices for construction sites is based on proper storage and disposal practices by construction workers and supervisors. Key elements of the program are education and vigilance in required on the part of supervisors and workers to ensure that the recommendations and procedures are followed. Following are lists describing the targeted materials and recommended procedures: | <ul style="list-style-type: none"> Capital Costs Maintenance Training Liability for Slope > 5% | Current Unacceptable Waste Concrete Disposal Practices | <ul style="list-style-type: none"> Capital Costs Maintenance Training Liability for Slope > 5% |
| APPLICABLE REGULATIONS | Legend | Current Unacceptable Waste Concrete Disposal Practices | Legend |
| Targeted Solid Waste Materials | <ul style="list-style-type: none"> Significant Impact Medium Impact Low Impact Unknown or Questionable Impact | <ul style="list-style-type: none"> Targeted Solid Waste Materials Paper and cardboard containers Flammable packaging Styrofoam packing and foam insulation materials (non-hazardous) Wood pallets Wood cuttings Pipe and electrical cuttings Concrete, brick, and mortar waste Shingles cuttings and waste Steel (cuttings, nails, rust residue) Green board cuttings and waste Shredding cuttings and waste Miscellaneous cuttings and waste Food waste Demolition waste | <ul style="list-style-type: none"> Significant Impact Medium Impact Low Impact Unknown or Questionable Impact |
| Storage Procedures | W-1 | Recommended Disposal Practices | W-3 |
| <ul style="list-style-type: none"> Whenever possible, minimize production of solid waste materials. Designate a foreman or supervisor to oversee and enforce proper solid waste procedures. Instruct construction workers in proper solid waste procedures. Segregate potentially hazardous waste from non-hazardous construction site debris. Keep solid waste materials under cover in either a closed dumpster or other enclosed trash container that limits contact with rain and runoff. Store waste materials away from drainage ditches, water and soil bodies. Do not allow waste materials to overflow. Do not allow waste materials to accumulate on the ground. Prohibit workers from using equipment cleaning devices that are not designed for this purpose. Police areas daily for litter and debris. Enforce solid waste handling and storage procedures. | | <ul style="list-style-type: none"> Develop pre-determined, safe concrete disposal areas. Provide a washout area with a minimum of 6 cubic feet of containment area volume for every 10 cubic yards of concrete poured. Never dump waste concrete liberally or without proper owner knowledge and consent. Treat runoff from storage areas through the use of structural controls as required. | |
| Disposal Procedures | | Disposal Procedures | |
| <ul style="list-style-type: none"> If feasible, segregate recyclable waste from non-recyclable waste materials and dispose of properly. General construction debris may be hauled to a licensed construction debris landfill (typically less expensive than a sanitary landfill). Use waste facilities approved by local jurisdiction. Residue which comes into contact with unapproved waste shall be directed into structural decontamination such as all fences to remove debris. | | <ul style="list-style-type: none"> Monitor weather and wind direction to ensure concrete dust is not entering drainage structures and surface waters. Where appropriate, construct sediment traps or other types of sediment retention devices downstream of demolition activities. | |
| Education | | Education | |
| <ul style="list-style-type: none"> Educate all workers on solid waste handling and disposal procedures. Instruct workers in identification of solid waste and hazardous waste. Have regular meetings to discuss and reinforce disposal procedures (incorporate in regular safety meetings). Clearly mark on all solid waste containers which materials are acceptable. | | <ul style="list-style-type: none"> Use pre-determined disposal sites for waste concrete. Prohibit dumping waste concrete anywhere but pre-determined area. Assign pre-determined truck and equipment washing areas. Prohibit dumping waste concrete anywhere but pre-determined area. Assign pre-determined truck and equipment washing areas. Prohibit dumping waste concrete anywhere but pre-determined area. | |
| Quality Control | | Quality Control | |
| <ul style="list-style-type: none"> Foreman and/or construction supervisor shall monitor on-site solid waste storage and disposal procedures. Designate workers who repeatedly violate procedures. | | <ul style="list-style-type: none"> Use pre-determined disposal sites for waste concrete. Prohibit dumping waste concrete anywhere but pre-determined area. Assign pre-determined truck and equipment washing areas. Prohibit dumping waste concrete anywhere but pre-determined area. Assign pre-determined truck and equipment washing areas. Prohibit dumping waste concrete anywhere but pre-determined area. | |
| Requirements | | Requirements | |
| <ul style="list-style-type: none"> Job-site waste handling and disposal education and awareness program. Compliance by workers. Sufficient and appropriate waste storage containers. Timely removal of stored solid waste materials. Possible model cost budget for additional waste storage containers. Minimal overall cost impact. | | <ul style="list-style-type: none"> Use pre-determined disposal sites for waste concrete. Prohibit dumping waste concrete anywhere but pre-determined area. Assign pre-determined truck and equipment washing areas. Prohibit dumping waste concrete anywhere but pre-determined area. Assign pre-determined truck and equipment washing areas. Prohibit dumping waste concrete anywhere but pre-determined area. | |
| LIMITATIONS | | LIMITATIONS | |
| <ul style="list-style-type: none"> Only addresses non-hazardous solid waste. One part of a comprehensive construction site management program. | | <ul style="list-style-type: none"> This concrete waste management program is one part of a comprehensive construction site waste management program. | |

MAINTENANCE AND INSPECTION PROCEDURES: CONTROL MEASURES WILL BE INSPECTED AT LEAST ONCE A WEEK OR WITHIN 24 HOURS OF ANY STORM EVENT OR 0.5 INCHES OR GREATER. IF A REPAIR IS NECESSARY IT WILL BE DONE AT THE EARLIEST PRACTICABLE DATE BUT WITHIN 48 HOURS.

PROJECT NAME & LOCATION: ROCKWALL ASC EXPANSION & REMODEL LOT 3R, BLOCK B THE WOODS AT ROCKWALL ADDITION NO. 1 825 YELLOW JACKET LANE SOUTHLAKE, TEXAS

OWNER NAME & ADDRESS: ROCKWALL ASC REAL ESTATE, L.L.C. ATTN: MS. GINGER WHITE 825 W. YELLOW JACKET LANE ROCKWALL, TEXAS 75032

PROJECT DESCRIPTION: PAVEMENT IMPROVEMENTS

TOTAL PROJECT AREA: 1.1988 ACRES

TOTAL AREA TO BE DISTURBED: 0.145 ACRES

ESTIMATED PROJECT START DATE: OCTOBER, 2011

ESTIMATED PROJECT END DATE: MARCH, 2012

STRUCTURAL CONTROL PRACTICES TO BE USED: SILT FENCING AND INLET PROTECTION

ALLOWABLE NON-STORM WATER DISCHARGES

- DISCHARGES FROM FIRE FIGHTING ACTIVITIES.
- FIRE HYDRANT FLUSHINGS.
- WATER USED TO WASH VEHICLES OR CONTROL DUST.
- POTABLE WATER SOURCES (INCLUDING WATERLINE FLUSHINGS CONTAINING LESS THAN 1000 GALLONS).
- UNCONTAMINATED GROUND WATER (INCLUDING DETERMINED GROUNDWATER INFILTRATION).
- FOUNDATION OR FOOTING DRAINS WHERE FLOWS ARE NOT CONTAMINATED WITH PROCESS MATERIALS SUCH AS SOLVENTS.
- SEWERAGES, SEWAGE HABITATS, WETLANDS AND UNCONTAMINATED GROUNDWATER.
- IRRIGATION WATER.
- EXTERIOR BUILDING WASH DOWN WITHOUT DETERGENTS.
- PAVEMENT WASH WATERS WHERE SPILLS OR LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE NOT OCCURRED (UNLESS ALL SPILL MATERIAL HAS BEEN REMOVED) AND WHERE DETERGENTS ARE NOT USED.
- AIR CONDITIONING CONDENSATE.
- HEAVILY CHLORINATED WATER (3.5 MG/L OR GREATER FREE CHLORINE) RESULTING FROM WATER LINE STERILIZATION SHALL BE DIRECTED UNDER PERMIT TO THE SANITARY SEWER UNLESS OTHERWISE NOTED. THE CONTRACTOR SHALL APPLY TO THE ENGINEERING DEPARTMENT FOR A SANITARY SEWER DISCHARGE PERMIT AFTER THE MANDATORY CHLORINE RETENTION TIME (USUALLY 24 HOURS). THE HEAVILY CHLORINATED WATER MAY BE DISCHARGED TO THE SANITARY SEWER, BEGINNING TWO WORKING DAYS AFTER PERMIT APPLICATION.

SIGNATORY REQUIREMENT

I CERTIFY THAT THE INFORMATION PROVIDED IN THIS DOCUMENT REPRESENTS EROSION CONTROL MEASURES PLANNED FOR THE SUBJECT PROJECT AND IS TRUE, ACCURATE AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF. I FURTHER CERTIFY THAT I UNDERSTAND MY RESPONSIBILITIES UNDER THE CONDITIONS OF THIS EROSION CONTROL PLAN.



PROJECT OWNER: _____ CONTRACTOR: _____

SIGNATURE: _____ TITLE: _____ COMPANY NAME: _____ DATE: _____

SIGNATURE: _____ TITLE: _____ COMPANY NAME: _____ DATE: _____

DRIVERS LICENSE # _____ DATE OF BIRTH: _____ RACE: _____ SEX: _____

PLAN REVIEWER: _____ DATE: _____



SILT FENCE GENERAL NOTES:

- Posts which support the silt fence shall be braced on a slight angle beyond the anticipated runoff source. Posts must be embedded a minimum of 12" into the soil.
- The top of the silt fence shall be horizontal to within a grade or mechanical transfer, so that the drainage face of the fabric is flat and perpendicular to the line of flow. Where fabric cannot be installed in one piece, overlap fabric top with rock on uphill side to prevent flow from seeping under fabric.
- The trench must be a minimum of 8 inches deep and 8 inches wide to allow for the 8" fabric fabric to be laid in the ground and backfilled with compacted material.
- Silt fence shall be equally fastened to each steel support post or to ground with 1/2" x 4" lag bolts. Posts shall be secured to ground with 1/2" x 4" lag bolts. Posts shall be secured to ground with 1/2" x 4" lag bolts.
- Inspection shall be made every day, and after each 1/2" rainfall. Repair or replacement shall be made promptly as needed.
- Silt fence shall be removed when the site is completely stabilized so as not to block or impede storm flow or drainage.
- Unauthorized fill shall be removed when it reaches a depth of half the height of the fence. The fill shall be disposed of on approved site and in such a manner as to not contribute to additional erosion.

NOTE: 75% - 80% OF ALL DISTURBED AREAS WILL HAVE 1" HIGH GRASS ESTABLISHED PRIOR TO CITY ACCEPTANCE.

LEGEND

- SILT FENCE
- CONSTRUCTION ENTRANCE
- INLET PROTECTION
- EXISTING CONCRETE PAVEMENT AND SIDEWALK TO BE REMOVED

BENCHMARKS:

TOP OPERATING NUT OF FIRE HYDRANT AT INTERSECTION OF YELLOW JACKET LN. AND KYLE DR. ELEV. = 529.26

| NO. | DATE | REVISION |
|-----|------|----------|
| | | |

STATE OF TEXAS
ROBERT W. SCHNEBERG
Professional Engineer
No. 65552

"ALL RESPONSIBILITY FOR ADEQUACY OF DESIGN REMAINS WITH THE DESIGN ENGINEER. THE CITY OF ROCKWALL, IN REVIEWING AND RELEASING PLANS FOR CONSTRUCTION, ASSUMES NO RESPONSIBILITY FOR ADEQUACY OR ACCURACY OF DESIGN."

DATE: _____

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY ROBERT W. SCHNEBERG, P.E. 65552 ON 10/07/2011. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO THE RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.

PROJ. NO. 4956-11-03-01 DWG. NO. 4956 Eros.dwg


Gonzalez & Schneberg
engineers - surveyors
800 N. Central Expressway
Suite 250, Plano, Texas 75074
(972) 516-8855 Fax: (972) 516-8900

EROSION CONTROL & DEMOLITION PLAN

LOT 3R, BLOCK B, THE WOODS AT ROCKWALL ADDITION NO. 1

ROCKWALL ASC EXPANSION & REMODEL
CITY OF ROCKWALL, TEXAS

| DESIGN | DRAWN | DATE | SCALE | NOTES | FILE | NO. |
|--------|-------|----------------|--------|-------|------|-----|
| GSES | GSES | SEPTEMBER 2011 | 1"=20' | | | |



OFF-SITE PARKING
LOCATION

YELLOWJACKET LANE

GREENCREST BLVD.

MODIFY PAVEMENT AS REQ. TO
ENSURE MAX 2% SLOPE (ANY
DIRECTION) WITHIN PARKING AND
ACCESSIBLES

WILL EXIST RAMP &
REMOVE LOT STRIPS

EXISTING STRUCTURE
6,387 S.F.
BUILDING HEIGHT:
APPROX 34' AFF.

EXPANSION
3,166 S.F.
NEW PARAPET
HT: 16'-0" AFF.

RELOCATED STORY
SEWER REFER CIVL.


EXTEND RETAINING
WALL, REFER STRUCT.

Site Plan
Scale: 1/4"=0'-0"
Actual Plan



Key Notes

- NOTE:
1 GENERAL REQUIREMENTS-NOT USED
- 2 SITE WORK
2.1 4" THK CONC WALK, REFER 2/A1.02
2.2 4" WIDE PAVEMENT MARKINGS
2.3 ADA COMPLIANT DETECTABLE WARNING RAMP,
REFER 19/AO.01
2.4 HANDICAP SIGN REFER 21/AO.01
2.5 6" CONCRETE CURB, REFER CIVL
2.6 LANDSCAPING, BY OWNER
- 3 CONCRETE
3.1 CONC FOUNDATION, REFER STRUCTURAL
3.2 CONCRETE SLAB, REFER STRUCTURAL
3.3 VOID CARTONS, REFER STRUCTURAL
- 4 MASONRY
4.1 FACE BRICK (+)
4.2 ADJUSTABLE MASONRY TIES PER MASONRY
ADVISORY CONC. RECOMMENDATIONS
4.3 T MASONRY CONTROL JOINT
4.4 MORTAR SCREEN (+)
4.5 CAST STONE, REFER 10/A4.03 (S)
- 5 METALS
5.1 STEEL STRUCTURAL FRAMING, REFER STRUCTURAL
5.2 STEEL ROOF JOIST, REFER STRUCTURAL
5.3 METAL ROOF DECK, REFER STRUCTURAL
5.4 METAL, SIZE AS INDICATED
5.5 FASTENERS AS NOTED
5.6 PRE-FABRICATED ACCESS LADDER (+)
- 6 WOODS & PLASTICS
6.1 TREATED WOOD S JOCKING, AS NOTED
6.2 PLYWOOD, AS NOTED
6.3 METAL CORNER BRACKET, (+)
6.4 TACK SURFACE (+)
6.5 NOT USED
6.6 WINDOW STOOL, P-LAY ON 2 PLYWOOD
6.7 WOOD TRIM, PAINT
6.8 1/2" MDO/EXT - APA BOARD
- 7 THERMAL AND MOISTURE PROTECTION
7.1 SINGLE PLY MEMBRANE WALK PAD, BY ROOFING
MANUF.
7.2 NOT USED
7.3 PRE FINISHED 24 GA. BENT METAL TRIM / FLASHING (+)
7.4 CONT. 24 GA. GALV. BASE FLASHING W/ WEEP
HOLES @ 18" O.C.
7.5 PRE FINISHED 20 GA. CONT. GUTTER AND
DOWNSPOUT (+)
7.6 NOT USED
7.7 THERMAL BATT INSULATION AS NOTED
7.8 ISO RIGID INSULATION, PER ROOFING MANUF.
7.9 GYPSUM SHEATHING (+)
7.10 WEATHER RESISTANT BARRIER (+)
7.11 VAPOR RETARDENT BARRIER
7.12 COMPOSITE WALL PANEL (+)
7.13 EXTERIOR INSULATION AND FINISH SYSTEM, E.I.F.S. (+)
7.14 PRE-FABRICATED ROOF HATCH, REFER 2/A2.03 (+)
7.15 SEALANT AND BACKER ROD
7.16 INT. CALK
7.17 STANDING SEAM ROOF (+)
- 8 DOORS AND WINDOWS
8.1 WINDOW, REFER WINDOW TYPES
8.2 FRAME & DOOR, REFER DOOR TYPES
- 9 FINISHES
9.0 5/8" GYPSUM WALL BOARD
9.1 FIBERGLASS REINFORCED PANEL (+)
9.2 BASE AS SCHEDULED
9.3 CEILING AS SCHEDULED
9.4 22 GA. METAL STUD AT 16" O.C., SIZE AS NOTED
9.5 POLYURETHANE COATING (+)
- 10 SPECIALTIES
10.1 SIGNAGE, REFER MAT. LEGEND, SIZE AS INDICATED (+)
10.2 INTERIOR SIGNAGE (+)
10.3 WALL CORNER GUARD (+)
10.4 THROUGH WALL LOUVER (+)
- 11 EQUIPMENT - NOT USED
11.1 FIRE DEPARTMENT KEY LOCK BOX (+)
- 12 FURNISHINGS - NOT USED
- 13 SPECIAL CONSTRUCTION-NOT USED
- 14 CONVEYING SYSTEMS-NOT USED
- 15 MECHANICAL
15.1 ROOF DRAIN, REFER PLUMBING
15.2 WALL DOWNSPOUT, REFER PLUMBING
15.3 PLUMBING FIXTURE REFER MEP
- 16 ELECTRICAL
16.1 LIGHT FIXTURE, REFER TO ELECTRICAL
- (+) REFER MATERIAL LEGEND, SHEET 0.00
(S) REFER SPECIFICATION SHEETS



Flatwork Detail
Scale: 1/2"=1'-0"

Building Information

OWNER
ROCKWALL SURGERY CENTER
825 W. YELLOWJACKET LANE
ROCKWALL, TEXAS 75087
972-772-8988

BUILDING USE
EXPANDING EXISTING ACUTE SURGERY CENTER

Jurisdiction of Project
REGULATORY AUTHORITIES
CITY OF ROCKWALL
385 SOUTH SOLAD
ROCKWALL, TEXAS 75087
972-77-7700

TEXAS DEPARTMENT OF LICENSING AND REGULATION
ELIMINATION OF ARCHITECTURAL BARRIERS
E.O. THOMPSON STATE OFFICE BUILDING
920 COLORADO
AUSTIN, TEXAS 78707
(512) 463-3211
(512) 475-2686 (FAX)

BUILDING DESIGN CODE
2006 INTERNATIONAL BUILDING CODE W/ LOCAL AMENDMENTS
2006 INTERNATIONAL MECHANICAL CODE W/ LOCAL AMENDMENTS
2006 INTERNATIONAL PLUMBING CODE W/ LOCAL AMENDMENTS
2006 INTERNATIONAL FIRE ALARM CODE W/ LOCAL AMENDMENTS
2006 NATIONAL ELECTRICAL CODE W/ LOCAL AMENDMENTS
2006 INTERNATIONAL ENERGY CONSERVATION CODE W/ LOCAL AMENDMENTS

Property Information
SITE LOCATION
825 W. YELLOWJACKET LANE
ROCKWALL, ROCKWALL COUNTY, TEXAS

DESCRIPTION
LOT 3A, BLOCK B, WOODS AT ROCKWALL, ADDITION NO. 1 TO CITY OF ROCKWALL,
TEXAS

ZONING: C - COMMERCIAL DISTRICT
LOCATED WITHIN SCENIC OVERLAY DISTRICT (SOV)

LOT AREA: 52,222 S.F. (1,888 ACRES)

Building Information

OCCUPANCY:
GROUP B

BUILDING TYPE
TYPE I-B SPRINKLED

SINGLE STORY

BUILDING AREA
EXISTING OCCUPIED AREA: 6,387 S.F.
NEW EXPANSION: 3,166 S.F.
TOTAL BUILDING: 9,553 S.F.


Site Information

LOT AREA: 52,222 SQ. FT.
PREVIOUS AREA: 30,845 SQ. FT.
COVERAGE: 59%
REQUIRED COVERAGE: COMMERCIAL: 5%

PARKING
MEDICAL OFFICE REQUIREMENTS:
1,765 S.F. / 200 S.P. + 56 SPACES REQUIRED
ON SITE PARKING: 52 SPACES
OFF SITE PARKING (PER AGREEMENT): 26 SPACES
TOTAL PARKING PROVIDED: 58 SPACES

RELEASED FOR CONSTRUCTION
ALL RESPONSIBILITY FOR ADEQUACY OF DESIGN
REMAINS WITH THE DESIGN ENGINEER. THE
CITY OF ROCKWALL, IN REVIEWING AND RELEASING
PLANS FOR CONSTRUCTION, ASSUMES NO
RESPONSIBILITY FOR ADEQUACY OR ACCURACY
OF DESIGN.

CITY _____ DATE _____



Vicinity Map
No Scale

Seitz Architects, Inc.
2231 Ridge Road, Suite 201, Rockwall, Texas 75087
972.772.9006 Fax: 972.772.7002 www.seitzarchitects.com



**Rockwall ASC
Expansion & Remodel**
Rockwall, Texas

- Rev #
10-09 Site
project #
10-018
date
21 June 2011
revisions
15 July 2011
H.C. Parking Access
23 September 2011
Response to City
10 October 2011
Response to City

A1.02