



SITE VIEW
 SCALE: 1/8"=1'-0"

NOTES:

1. NEW BACKFLOW PREVENTER TO BE ZURN WILKINS MODEL 350A-OSY WITH STRAINER OPTION OR EQUIVALENT.
2. NEW PIPE AND FITTINGS TO BE BLUE BRUTE (AWWA C900 - DR 14 CLASS 200) WITH BELL AND SPIGOT JOINTS TO MATCH EXISTING.
3. REPLACE CONCRETE PAVING AS REQUIRED WITH 6" THK. CONCRETE WITH #4 REBARS @ 18" E.W., (3600 PSI THAT REQUIRES 6.5 SACK MIX MINIMUM). BATCH DESIGN WILL NEED TO BE APPROVED BY ENGINEERING PRIOR TO PLACEMENT. AN ENGINEERING INSPECTION OF THE REBAR AND SUBGRADE IS REQUIRED PRIOR TO PLACEMENT OF CONCRETE.

AS-BUILT
 07/13/2018

 Pegasus Foods, Inc.		PEGASUS FOODS, INC. BACKFLOW PREVENTER & WATER MAIN RELOCATION PLANS & ELEVATIONS SITE LOCATION: ROCKWALL, TEXAS																																												
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>NO.</th> <th>COMMENTS</th> <th>BY</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>ISSUED FOR CONSTRUCTION</td> <td>WPJ</td> <td>08/09/2017</td> </tr> <tr> <td>1</td> <td>POUR BACK CONCRETE NOTE ADDITION</td> <td>WPJ</td> <td>09/13/2017</td> </tr> <tr> <td>2</td> <td>TEE ADDITION</td> <td>WPJ</td> <td>10/19/2017</td> </tr> <tr> <td>3</td> <td>AS-BUILT PER CONTRACTOR COMMENTS</td> <td>JH</td> <td>07/13/2018</td> </tr> </tbody> </table>	NO.	COMMENTS	BY	DATE	0	ISSUED FOR CONSTRUCTION	WPJ	08/09/2017	1	POUR BACK CONCRETE NOTE ADDITION	WPJ	09/13/2017	2	TEE ADDITION	WPJ	10/19/2017	3	AS-BUILT PER CONTRACTOR COMMENTS	JH	07/13/2018	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>REVISIONS</th> <th>BY</th> <th>DATE</th> <th>REFERENCE DRAWINGS</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	REVISIONS	BY	DATE	REFERENCE DRAWINGS					<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>ENGINEERED BY</th> <th>CHECKED BY</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>WPJ</td> <td>JCG</td> <td>06/28/2017</td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	ENGINEERED BY	CHECKED BY	DATE	WPJ	JCG	06/28/2017				<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>DESIGNER</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>WPJ</td> <td>06/30/2017</td> </tr> <tr> <td> </td> <td> </td> </tr> </tbody> </table>	DESIGNER	DATE	WPJ	06/30/2017		
NO.	COMMENTS	BY	DATE																																											
0	ISSUED FOR CONSTRUCTION	WPJ	08/09/2017																																											
1	POUR BACK CONCRETE NOTE ADDITION	WPJ	09/13/2017																																											
2	TEE ADDITION	WPJ	10/19/2017																																											
3	AS-BUILT PER CONTRACTOR COMMENTS	JH	07/13/2018																																											
REVISIONS	BY	DATE	REFERENCE DRAWINGS																																											
ENGINEERED BY	CHECKED BY	DATE																																												
WPJ	JCG	06/28/2017																																												
DESIGNER	DATE																																													
WPJ	06/30/2017																																													
 TEXAS REGISTERED ENGINEERING FIRM No. F-15521		JOB NUMBER 17161 SCALE AS NOTED DRAWING NO. M-101	APPROVED BY MJR DATE 08/30/2017 REV. 3																																											