


ROCKWALL ELEMENTARY #8

ROCKWALL INDEPENDENT SCHOOL DISTRICT


ROCKWALL, TEXAS

FINAL PLANS FOR BIDDING AND CONSTRUCTION





SHW Group Inc.
 Architects + Engineers

SHEET NUMBER: **C 2.20**
 OF: [Blank]
 SET NUMBER: [Blank]



MODEL	SIZE	L1	W1	H1	WEIGHT LBS.
BP3	3"	6'-0"	3'-6"	4'-0"	3,500
BP4	4"	6'-0"	3'-6"	4'-0"	3,500
BP6	6"	7'-10"	4'-4"	5'-6"	8,000
BP8	8"	8'-6"	5'-0"	6'-6"	17,000
BP10	10"	9'-2"	5'-6"	6'-6"	18,000

1/4" THICK CHECKER PLATE FRAME AND COVER, PRIMERED AND PAINTED WITH (1) COAT OF INDUSTRIAL BLACK ENAMEL PAINT.





MODEL	SIZE	BY-PASS	L1	W1	H1	WEIGHT LBS.
DMTCH3	3"	2"	11'-6"	6'-0"	4'-3"	14,500
DMTCH4	4"	2"	11'-6"	6'-0"	4'-3"	15,000
DMTCH6	6"	4"	13'-6"	6'-0"	4'-3"	19,500
DMTCH8	8"	4"	13'-6"	6'-0"	4'-3"	20,000
DMTCH10	10"	4"	17'-6"	7'-6"	4'-3"	25,000

DOMESTIC WATER COMPOUND METER ASSEMBLY

- Specifications**
- CONCRETE:** Class 1 concrete with design strength of 4500 PSI at 28 days. Unit is of monolithic construction of floor and first stage of wall with sectional riser to required depth.
- REINFORCEMENT:** Grade 60 reinforced. Steel rebar conforming to ASTM A615 on required centers or equal.
- STEEL COVER:** All steel fabrication shall be in accordance to AIA D1.1. Steel shall be ASTM A36 carbon steel, and hot dipped galvanized after fabrication in accordance to ASTM A123. Standard cover is reted for 50 PSF.
- Engineering Data**
- Field excavation and preparation shall be completed prior to delivery of assembly. Use dimensional data as shown. Pipe, valves and fittings of the assembly are approved by one or more of the following associations:
-

- Specifications**
- CONCRETE:** Class 1 concrete with design strength of 4500 PSI at 28 days. Unit is of monolithic construction of floor and first stage of wall with sectional riser to required depth.
- REINFORCEMENT:** Grade 60 reinforced. Steel rebar conforming to ASTM A615 on required centers or equal.
- STEEL COVER:** 1/4" steel skid-resistant floor plate welded to 3" angle frame with (2) 3"x2-3/8" I beam supports (300 PSF).
- Engineering Data**
- Field excavation and preparation shall be completed prior to delivery of assembly. Use dimensional data as shown. Pipe, valves and fittings of the assembly are approved by one or more of the following associations:
-

- METER VAULT & BYPASS SPECIFICATIONS**
1. NOTIFY THE CONSTRUCTION INSPECTION DEPARTMENT (542-2676) PRIOR TO CONSTRUCTION OF VAULT OR BY-PASS ASSEMBLY.
 2. THE METER VAULT CAN BE EITHER POURED IN PLACE OR PREFABRICATED. IF THE VAULT IS POURED IN PLACE, CONCRETE SHALL BE AT LEAST 8-INCHES THICK AND BE 3000 PSI REINFORCED WITH #4 STEEL BARS ON 12-INCH CENTERS EACH WAY. PREFABRICATED VAULTS SHALL BE AT LEAST 4-INCHES THICK AND 4500 PSI CONCRETE #4 STEEL BARS ON 8-INCH CENTERS.
 3. THE VAULT SHALL NOT BE LOCATED IN ANY DRIVE OR PARKING AREAS AND MUST BE LOCATED IN A UTILITY EASEMENT.
 4. A DRAWING WITH THE EXACT MEASUREMENTS OF THE VAULT SHALL BE GIVEN FOR THE METER AND BY-PASS ASSEMBLY.
 5. THE VAULT LID SHALL BE A BILCO LID, TYPE Q-4 SINGLE LEAF DESIGN. ANGLE FRAME IS 1/4-INCH STEEL WITH STRAP ANCHORS BOLTED TO THE EXTERIOR. THE LEAF IS 1/4-INCH STEEL DIAMOND PATTERN PLATE, PIVOTING ON TORSION BARS FOR EASY OPERATION. THE MINIMUM LIVE LOAD CAPACITY IS 150 LBS. PER SQUARE FOOT. THE SIZE OF THE LID IS 3-FEET BY 3-FEET.
 6. THE LID SHALL BE PAINTED WITH 43-38 TMEC DIFFUSED ALUMINUM PAINT OR APPROVED EQUAL.
 7. CONTRACTOR MUST PROVIDE A 2-INCH TEST TAP LOCATED AT LEAST TWO PIPE DIAMETERS DOWNSTREAM OF METER. THE TAP MUST BE MADE USING AN APPROVED SERVICE SADDLE.
 8. THE STRAINER METER AND FLEXIBLE COUPLING SHALL NOT BE SET UNTIL METER VAULT AND TAPS ARE INSPECTED BY THE CITY OF MCKINNEY CONSTRUCTION INSPECTION DEPARTMENT.
 9. THE GATE VALVES ARE REQUIRED TO BE MUELLER A-2370-6 FLANGED RESILIENT SEAT GATE VALVES.
 10. THE BOTTOM OF THE METER VAULT MUST BE 8-INCHES THICK CONCRETE WITH #4 REBAR ON 12-INCH CENTERS AND HAVE A 4-INCH FILL SAND CUSHION UNDERNEATH. A SUMP 4-INCHES DEEP AND 12-INCHES IN DIAMETER SHALL BE INSTALLED TO ONE SIDE OF THE CENTER OF THE BOTTOM SLAB. IF PRECAST VAULT IS USED WHERE SIDES JOIN THE BOTTOM, A LAYER RANNEK SHALL BE USED TO SEAL THE JOINT.
 11. CONTRACTOR SHALL HAVE A CHOICE OF EITHER HAVING A LINK SEAL WALL SLEEVE MODEL WS-8-32-S-6 FOR A 4-INCH PIPE, WS-1036-S-6 FOR WS-12-37-S-6 FOR 8-INCH PIPE CAST IN THE VAULT FOR HAVE THE VAULT WALL CORED BEFORE INSTALLATION OF VAULT AND PIPING IN EITHER CASE. A LINK SEAL, MODEL NO. LS-400-C MUST BE USED TO SEAL THE ANNULAR SPACE BETWEEN THE PIPE AND WALL GREYING. BREAKING OF THE WALL WITH A JACKHAMMER IS NOT PERMITTED.
 12. THERE SHALL BE A CONCRETE SUPPORT UNDER EACH VALVE.
 13. DEPTH OF VAULT SHALL BE A MINIMUM OF 4-1/2 FEET.



These Drawings have been modified to conform to the Construction Records.
 Glenn Engineering Corporation
 By: [Signature] Date: 2-22-04