

GRADING SUMMARY

STATION	EXCAVATION (RDWY)	EMBANKMENT (DENS CONT) (TY C) (CL3)	EMBANKMENT (DENS CONT) (TY C MOD) (CL3)	FURNISH AND PLACE TPSL (CL 2) (4*)
	CY	CY	CY	SY
F.M. 740				
100+00				
101+00	106	78	-	261
102+00	222	276	-	411
103+00	359	291	-	378
104+00	548	135	-	294
105+00	783	106	312	256
106+00	959	85	312	256
107+00	1059	63	312	256
108+00	1096	59	312	239
109+00	1163	54	312	222
110+00	1106	74	286	261
111+00	981	67	286	200
112+00	1126	56	312	161
113+00	1333	70	312	211
114+00	1304	65	312	183
115+00	1111	57	312	144
116+00	922	54	312	172
117+00	954	56	312	189
118+00	930	78	286	233
119+00	830	126	286	294
120+00	854	169	331	311
121+00	1143	161	355	428
122+00	1719	120	370	500
122+39	558	55	149	262
TOTAL	21,166	2355	5781	6122
F.M. 3097				
0+63				
1+13	304	36	149	117
1+63	162	50	149	128
2+13	120	47	65	142
2+63	104	41	-	142
3+13	64	24	-	78
3+63	15	7	-	36
4+13	18	11	-	47
4+63	13	4	-	11
TOTAL	800	220	363	701
TOTAL PROJECT	21,966	2575	6144	6823

SUMMARY OF BLOCK SOD, VEGETATIVE WATERING, SIDEWALK AND COLORED-TEXTURIZED CONCRETE

LOCATION	BLOCK SOD (PRAIRIE BUFFALO)	VEGETATIVE WATERING	SIDEWALK (4")	COLORED-TEXTURIZED CONCRETE		
	SY	MG	SY	4" INTER WALKS ISLANDS & RAMPS SY	6" MEDIAN SY	8" STREET SY
FM 740-STA 100+00 TO STA 122+39	6122	51	1597	85		
FM 3097-STA 0+45.08 TO STA 4+60	701	6			79	
HORIZON RD.	72	1				
MEDIAN-STA 104+00 TO STA 105+05					74	
FM 740, FM 3097 & HORIZON RD INTER.				538		615
STA 106+36 TO STA 109+17					171	
STA 110+84 TO STA 113+40					171	
STA 114+45 TO STA 117+01					171	
STA 119+00				44		
STA 122+00				38		
STA 124+00				38		
IH 30 INTERSECTION			83	1419		
TOTAL	6895	58	1680	2162	666	615

SUMMARY OF BALED HAY & SEDIMENT CONTROL FENCE

LOCATION	TEMP SEDMT CONT FENCE	TEMP SEDMT CONT FENCE (REMOVE & REPLACE)	TEMP SEDMT CONT FENCE (REMOVE)	BALED HAY	BALED HAY (REMOVE & REPLACE)	BALED HAY (REMOVE)
	LF	LF	LF	EA	EA	EA
FM 3097-STA 4+80(LT & RT)				10	20	10
FM 740 -STA 100+00(LT & RT)				10	20	10
FM 740-STA 104+50(RT)				5	10	5
FM 740-STA 106+00(RT)				5	10	5
FM 740-STA 107+60(LT)				14	28	14
FM 740-STA 108+80(RT)				14	28	14
FM 740-STA 110+00(LT)				5	10	5
FM 740-STA 118+80(RT)				14	28	14
FM 740-STA 122+20(RT)				14	28	14
FM 740-STA 100+00 TO STA 106+40(RT)	674	674	674			
FM 740-STA 107+00 TO 108+15(RT)	158	158	158			
FM 740-STA 114+15 TO STA 119+00(LT)	485	485	485			
FM 740-STA 117+28 TO STA 120+16(RT)	315	315	315			
FM 740-STA 122+78	22	22	22			
FM 740-STA 123+97	27	27	27			
TOTAL	1681	1681	1681	91	182	91

SUMMARY SHEET SHEET 1 OF 4

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		SHEET NO.
6	STP 96(830)MM		10
STATE	STATE DIST. NO.	COUNTY	
TEXAS	DALLAS	ROCKWALL	
CONTROL SECTION	JOB	HIGHWAY NO.	
1014	03	041 FM 740	