



City of Rockwall

Planning & Zoning Department 385 S. Goliad Street Rockwall, Texas 75032 (P): (972) 771-7745 (W): www.rockwall.com The City of Rockwall GIS maps are continually under development and therefore subject to change without notice. While we endeavor to provide timely and accurate information, we make no guarantees. The City of Rockwall makes no warranty, express or implied, including warranties of merchantability and fitness for a particular purpose. Use of the information is the sole responsibility of the user.





January 17, 2020

City of Rockwall Planning & Zoning Dept 385 S. Goliad St Rockwall, Texas 75087 972-771-7745

RE: Tree Removal Application 3005 N. Goliad St WA # 19022

Dear Planning and Zoning Staff,

PRINCIPALS JOHN P. WIER, P.E., R.P.L.S. ULYS LANE III, P.E., R.P.L.S., GFM CARLO SILVESTRI, P.E. GREGG MADSEN, R.P.L.S.

SENIOR ASSOCIATES PHILIP L. GRAHAM, P.E. JAKE H. FEARS, P.E., LEED AP BD+C RANDALL S. EARDLEY, P.E.

> ASSOCIATES TOBY W. RODGERS CASEY D. YORK PRIYA ACHARYA, P.E.

The developer of the property located at 3005 N. Goliad St would like the request the removal of additional trees. The original tree removal and mitigation plan (SP2019-023) was approved by the Planning and Zoning Commission on July 9, 2019 and by City Council on July 15, 2019. The additional protected trees requested to be removed within the property limits include the following (as identified on the attached Tree Preservation Plan):

No.	Caliper	Species			
2474	20"	Elm			
2561	22″	Pecan			
2562	16"	Pecan			
2563	24"	Pecan			
2564	32″	Pecan*			
2596	8″	Pecan			
2597	24″	Pecan			
2598	29"	Pecan*			
2599	24″	Pecan			
2701	19"	Pecan			
2714	17"	Pecan			
* Represents Feature Tree					

Tree numbers 2169, 2607, 2707, 2708, 2709, and 2710 proposed to be removed are located within TxDOT right-of-way and outside of the property limits; therefore, these trees are not counted towards the City's mitigation requirements.

A copy of the tree mitigation plan is included with this submittal, along with the application and fee. If you have questions or need additional information, please do not hesitate to contact us.


Respectfully, E Plus

Jake Fears, P.E., LEED AP

FAX (817) 467-7713

121 S. MAIN ST. HENDERSON, TEXAS 75654-3559 (903) 722-9030 TOLL FREE FAX (844) 325-0445

WWW.WIERASSOCIATES.COM



	TREE				MITIO	NOTEO
NO. 2043	CALIPER 32	TREE SPECIES Pecan	REMAIN/REMOVE To Be Removed	MITIGATION REQ. 2 to 1	MITIGATION 64	NOTES
2086	20	Elm	To Be Removed	1 to 1	20	
2097	18	Elm	To Be Removed	1 to 1	18	
2105 2123	16 18	Elm Hackberry	To Be Removed	1 to 1 50%	16 9	
2123	18	Elm	To Be Removed	1 to 1	18	
2143	20	Elm	To Be Removed	1 to 1	20	
2147	24	Cedar	To Be Removed	50%	12	
2169	14	Elm	To Be Removed			Not on Property
2171 2176	28 24	Bois D'Arc Pecan	To Be Removed To Remain	0%		
2176	30	Walnut	To Be Removed	2 to 1	60	
2185	20	Elm	To Be Removed	1 to 1	20	
2186	16	Elm	To Be Removed	1 to 1	16	
2187	16	Elm	To Be Removed	1 to 1	16	
2188 2189	16 16	Elm	To Be Removed To Be Removed	1 to 1 1 to 1	16 16	
2190	12	Elm	To Be Removed	1 to 1	12	
2191	16	Elm	To Be Removed	1 to 1	16	
2192	24	Cedar	To Be Removed	50%	12	
2193 2195	16 18	Elm	To Be Removed	1 to 1 1 to 1	16	
2195	10	Elm	To Be Removed	1 to 1	12	
2197	16	Elm	To Be Removed	1 to 1	16	
2207	12	Elm	To Be Removed	1 to 1	12	
2208	14	Elm	To Be Removed	1 to 1	14	
2210 2211	16 18	Elm	To Be Removed To Be Removed	1 to 1 1 to 1	16 18	
2219	16	Elm	To Be Removed	1 to 1	16	
2221	16	Elm	To Be Removed	1 to 1	16	
2222	12	Elm	To Be Removed	1 to 1	12	
2224 2225	17 17	Elm	To Be Removed	1 to 1 1 to 1	17 17	
2223	17	Elm	To Remain	1.01	17	
2243	4	Elm	To Be Removed	0		
2268	12	Elm	To Remain			
2269 2290	18 20	Elm	To Remain To Remain			
2290	 	Elm	To Be Removed	1 to 1	16	
2301	16	Elm	To Be Removed	1 to 1	16	
2303	18	Elm	To Remain			
2304	16	Elm	To Remain		10	
2305 2306	12 12	Elm	To Be Removed To Be Removed	1 to 1 1 to 1	12	
2307	12	Elm	To Be Removed	1 to 1	12	
2324	8	Elm	To Remain			Not on Property
2325	6	Elm	To Remain			Not on Property
2335 2336	13 6	Elm Elm	To Remain To Remain			Not on Property; Multi-trunk
2336	6	Elm	To Remain			Not on Property Not on Property; Bent
2340	12	Elm	To Remain			Not on Property
2350	12	Elm	To Remain			Not on Property
2351	10	Elm	To Remain			Not on Property
2352 2353	<u> </u>	Elm Elm	To Remain To Remain			Not on Property Not on Property
2353	9	Elm	To Remain			Not on Property
2355	14	Elm	To Remain			Not on Property
2356	6	Elm	To Remain			Not on Property
2372 2465	8	Bean Tree Elm	To Be Removed To Be Removed	0% 1 to 1	14	
2465	20	Elm	To Be Removed	1 to 1	<u>14</u> 20	
2476	22	Pecan	To Be Removed	1 to 1	22	
2477	18	Pecan	To Be Removed	1 to 1	18	
2553	32	Walnut	To Be Removed	2 to 1	64	Multi-trunk
2559 2561	22 22	Pecan Pecan	To Be Removed To Be Removed	1 to 1 1 to 1	22 22	
2562	16	Pecan	To Be Removed	1 to 1	16	
2563	24	Pecan	To Be Removed	1 to 1	24	
2564	32	Pecan	To Be Removed	2 to 1	64	
2566 2567	18 22	Pecan Pecan	To Be Removed To Be Removed	1 to 1 1 to 1	18 22	
2568	22	Walnut	To Be Removed	1 to 1	22	
2596	8	Pecan	To Be Removed	1 to 1	8	
2597	24	Pecan	To Be Removed	1 to 1	24	
2598	29	Pecan	To Be Removed	1 to 1	29	
2599 2605	24 15	Pecan Walnut	To Be Removed To Be Removed	1 to 1 1 to 1	24 15	
2606	24	Pecan	To Remain		10	
2607	40	Bois D'Arc	To Be Removed			Not on Property
2655	6	Chinaberry	To Be Removed	0%		Multi-trunk
2656 2676	9 5	Chinaberry	To Be Removed	0%		
2676	5 15	Chinaberry Pecan	To Be Removed	0%		In ROW
2701	19	Pecan	To Be Removed	1 to 1	19	
2707	24	Pecan	To Be Removed			Not on Property
2708	16	Pecan	To Be Removed	4 +- 4	0.4	Not on Property
2709 2710	24 7	Pecan Pecan	To Be Removed To Be Removed	1 to 1 1 to 1	24	
2710	17	Pecan	To Be Removed	1 to 1	17	
2716	27	Bois D'Arc	To Be Removed	0%		Multi-trunk
2750	12	Elm	To Remain			
2751	16	Elm	To Remain			
2752 2753	16 16	Elm	To Remain To Remain			Sanitary Sewer Easement Sanitary Sewer Easement
2755	40	Elm	To Remain			40 credit
2813	16	Walnut	To Be Removed	1 to 1	16	
2834	48	Elm	To Remain			48 credit
2806 2813 2834	40 16	Elm Walnu Elm	t	To Remain t To Be Removed	t To Remain t To Be Removed 1 to 1	To Remain t To Be Removed 1 to 1 16

THE TREE MAY BE IN DANGER OF BEING DAMAGED BY CONSTRUCTION EQUIPMENT OR OTHER ACTIVITY, THE CONTRACTOR OR SUBCONTRACTOR SHALL PROTECT THE TREE WITH 2" X 4" LUMBER ENCIRCLED WITH WIRE OR OTHER MEANS THAT DO NOT DAMAGE THE BARK OF THE TREE. THE INTENT IS TO PROTECT THE TRUNK OF THE TREE AGAINST INCIDENTAL CONTACT BY LARGE

1160-88 Credit = 1072 mitigation inches





AWR Designs, LLC P.O. Box 1746 Aledo, Texas 76008 amanda@awr-designs.com . 512.517.5589

TREE PRESERVATION NOTES

CONSTRUCTION METHODS:

BORING: BORING OF UTILITIES UNDER PROTECTED TREES MAY BE REQUIRED. WHEN REQUIRED, THE MINIMUM LENGTH OF THE BORE SHALL BE THE WIDTH OF THE CRITICAL ROOT ZONE AND SHALL BE A MINIMUM DEPTH OF FORTY (48) INCHES.

TRENCHING: ALL TRENCHING SHALL BE DESIGNED TO AVOID TRENCHING ACROSS CRITICAL ROOT ZONES OF ANY PROTECTED TREE. THE PLACEMENT OF UNDERGROUND UTILITY LINES SUCH AS ELECTRIC, PHONE, GAS, ETC., IS ENCOURAGED TO BE LOCATED OUTSIDE THE CRITICAL ROOT ZONE. TRENCHING FOR IRRIGATION SYSTEMS SHALL BE PLACED OUTSIDE THE CRITICAL ROOT ZONE EXCEPT THE MINIMUM REQUIRED SINGLE HEAD SUPPLY LINE. THIS LINE IS ALLOWED TO EXTEND INTO THE CRITICAL ROOT ZONE PERPENDICULAR TO THE TREE TRUNK WITH THE LEAST POSSIBLE DISTURBANCE.

TREES TO BE REMOVED: ALL TREES TO BE REMOVED FROM THE SITE SHALL BE FLAGGED BY THE CONTRACTOR WITH BRIGHT RED VINYL TAPE WRAPPED AROUND THE MAIN TRUNK AT A HEIGHT OF FOUR (4') FEET ABOVE GRADE.

TREES TO REMAIN: ALL TREES TO REMAIN, AS NOTED ON DRAWINGS, SHALL HAVE PROTECTIVE FENCING LOCATED AT THE TREE'S DRIP LINE. THE PROTECTIVE FENCING SHALL BE LOCATED AS INDICATED ON THE TREE PROTECTION DETAIL.

EXISTING TREES NOTED TO REMAIN SHALL BE PROTECTED DURING CONSTRUCTION FROM DAMAGE AND COMPACTION OF SOIL UNDER AND AROUND DRIP LINE OF TREE.

UNDER NO CIRCUMSTANCE SHALL THE CONTRACTOR PRUNE ANY PORTION OF THE DAMAGED TREE WITHOUT THE PRIOR APPROVAL BY THE OWNER'S AUTHORIZED REPRESENTATIVE.

PROHIBITED ACTIVITIES IN CRITICAL ROOT ZONE: THE FOLLOWING ACTIVITIES ARE PROHIBITED IN THE AREAS NOTED AS THE CRITICAL ROOT ZONE.

MATERIAL STORAGE: NO MATERIALS INTENDED FOR USE IN CONSTRUCTION, OR WASTE MATERIALS ACCUMULATED DUE TO EXCAVATION OR DEMOLITION, SHALL BE PLACED WITHIN THE LIMITS OF THE CRITICAL ROOT ZONE OF ANY PROTECTED TREE.

EQUIPMENT CLEANING/LIQUID DISPOSAL: NO EQUIPMENT SHALL BE CLEANED, OR OTHER LIQUIDS DEPOSITED OR ALLOWED WITHIN THE LIMITS OF THE CRITICAL ROOT ZONE OF A PROTECTED TREE. THIS INCLUDES, WITHOUT LIMITATION: PAINT, OIL, SOLVENTS, ASPHALT, CONCRETE, MORTAR OR SIMILAR MATERIALS.

TREE ATTACHMENTS: NO SIGNS, WIRES, OR OTHER ATTACHMENTS, OTHER THAN THOSE OF A PROTECTIVE NATURE, SHALL BE ATTACHED TO ANY PROTECTED TREE.

VEHICULAR TRAFFIC: NO VEHICULAR AND/OR CONSTRUCTION, EQUIPMENT, TRAFFIC, OR PARKING SHALL TAKE PLACE WITHIN THE LIMITS OF THE CRITICAL ROOT ZONE OF ANY PROTECTED TREE OTHER THAN ON EXISTING STREET PAVEMENT.


GRADE CHANGES: A MINIMUM OF 75% OF THE DRIP LINE AND ROOT ZONE SHALL BE PRESERVED AT NATURAL GRADE. ANY FINE GRADING DONE WITHIN THE CRITICAL ROOT ZONES OF THE PROTECTED TREES MUST BE DONE WITH LIGHT MACHINERY SUCH AS A BOBCAT OR LIGHT TRACTOR. NO EARTH MOVING EQUIPMENT WITH TRACKS IS ALLOWED WITHIN THE CRITICAL ROOT ZONE OF THE TREES.

PROCEDURES REQUIRED PRIOR TO CONSTRUCTION: PROTECTIVE FENCING: PRIOR TO CONSTRUCTION, THE CONTRACTOR OR

SUBCONTRACTOR SHALL CONSTRUCT AND MAINTAIN, FOR EACH PROTECTED TREE ON A CONSTRUCTION SITE, A PROTECTIVE FENCING WHICH ENCIRCLES THE OUTER LIMITS OF THE CRITICAL ROOT ZONE OF THE TREE TO PROTECT IT FROM CONSTRUCTION ACTIVITY. ALL PROTECTIVE FENCING SHALL BE IN PLACE PRIOR TO COMMENCEMENT OF ANY SITE WORK, AND REMAIN IN PLACE UNTIL ALL EXTERIOR WORK HAS BEEN COMPLETED.


BARK PROTECTION: IN SITUATIONS WHERE A PROTECTED TREE REMAINS IN THE IMMEDIATE AREA OF INTENDED CONSTRUCTION, AND THE LANDSCAPE ABCHITECT OB OWNERS'S REPRESENTATIVE DETERMINES THE TREE BARK TO BE IN DANGER OF DAMAGE BY CONSTRUCTION EQUIPMENT OR OTHER ACTIVITY, THE CONTRACTOR OR SUBCONTRACTOR SHALL PROTECT THE TREE BY ENCLOSING THE ENTIRE CIRCUMFERENCE OF THE TREE WITH 2"X4" LUMBER ENCIRCLED WITH WIRE OR OTHER MEANS THAT DO NOT DAMAGE THE TREE. THE INTENT IS TO PROTECT THE BARK OF THE TREE AGAINST INCIDENTAL CONTACT BY LARGE CONSTRUCTION EQUIPMENT.

TREE PRESERVATION LEGEND



TREE TO REMAIN





GRAPHIC SCALE Scale 1"=30' - 0


TREE PRESERVATION PLAN MIXED-USE DEVELOPMENT 3005 N. GOLIAD ST ROCKWALL, TEXAS

ALL THAT CERTAIN LOT, TRACT OR PARCEL OF LAND SITUATED IN THE S. KING SURVEY, ABSTRACT No. 131, CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS, AND BEING PART OF THAT TRACT OF LAND DESCRIBED IN A DEED FROM ARKOMA REALTY, LTD., TO ARKOMA DEVELOPMENT, L.L.C., AS RECORDED IN VOLUME 4411, PAGE 290 OF THE REAL PROPERTY RECORDS OF *Rockwall county, texas* January 16, 2020

WIR & ASSOCIATES, INC. ENGINEERS SURVEYORS LAND PLANNERS 2201 E. LAMAR BLVD., SUITE 200E ARLINGTON, TEXAS 76006 METRO (817)467-7700

Texas Firm Registration No. F-2776 www.WierAssociates.com CASE No.: SP2019-023

DATE: 1/16/2020 W.A. No. 19022



WIER & ASSOCIATES CONTACT: JAKE FEARS, P.E. 2201 E. LAMAR BLVD., SUITE #200E ARLINGTON, TX 76006 PHONE: (817) 467-7700 FAX: (817) 467-7713 JAKEF@WIERASSOCIATES.COM

60 FFF Scale 1"=30' - 0"

GRAPHIC SCALE



EROSION CONTROL AND SOIL PREPARATION: THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TOP SOIL AT THE CORRECT GRADES, CONTRACTOR TO FINE GRADE AREAS TO REACH FINAL CONTOURS AS SPECIFIED PER CIVIL PLANS. ALL CONTOURS SHOULD ACHIEVE POSITIVE DRAINAGE AWAY FROM BUILDINGS AND STRUCTURES. WATER SHOULD NOT BE ABLE TO POOL IN ANY AREAS UNLESS SPECIFIED OTHERWISE. EROSION FABRIC SUCH AS JUTE MATTING OR OPEN WEAVE TO BE USED WHERE

NECESSARY TO PREVENT SOIL EROSION. ANY LOSS OF TOPSOIL OR GRASS DUE TO EROSION IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL IT IS 100% ESTABLISHED.

CONTRACTOR TO REMOVE ANY ROCKS 3/4" AND LARGER, STICKS AND DEBRIS PRIOR TO INSTALLATION OF TOPSOIL AND SOD.

FOUR (4") OF TOPSOIL SHALL BE APPLIED TO AREAS DISTURBED BY CONSTRUCTION RECEIVING SOD. IF TOPSOIL IS NOT AVAILABLE ON SITE, THE CONTRACTOR SHALL PROVIDE TOPSOIL AS APPROVED BY THE OWNER OR OWNERS REPRESENTATIVE.

TOPSOIL SHALL BE FRIABLE, NATURAL LOAM, FREE OF ROCKS, WEEDS, BRUSH, CLAY LUMPS, ROOTS, TWIGS, LITTER AND ENVIRONMENTAL CONTAMINANTS.

CONTRACTOR SHALL BE RESPONSIBLE FOR SOD UNTIL ACCEPTANCE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: MOWING, WATERING, WEEDING, CULTIVATING, CLEANING AND REPLACING DEAD OR BARE AREAS TO KEEP PLANTS IN A VIGOROUS, HEALTHY CONDITION. SOD SHALL BE REPLACED IF

SOLID SOD SHALL BE PLACED ALONG ALL IMPERVIOUS EDGES, AT A MINIMUM. THIS SHALL INCLUDE CURBS, WALKS, INLETS, MANHOLES AND PLANTING BED AREAS. SOD SHALL COVER OTHER AREAS COMPLETELY AS INDICATED BY PLAN.

SOD SHALL BE STRONGLY ROOTED DROUGHT RESISTANT SOD, NOT LESS THAN 2 YEARS OLD. FREE OF WEEDS AND UNDESIRABLE NATIVE GRASS AND MACHINE CUT TO PAD THICKNESS OF 3/4" (+1/4"), EXCLUDING TOP GROWTH AND THATCH. PROVIDE ONLY SOD CAPABLE OF VIGOROUS GROWTH AND DEVELOPMENT WHEN

DO NOT INSTALL SOD IF IT IS DORMANT OR GROUND IS FROZEN. LAY SOD WITH TIGHTLY FITTING JOINTS, NO OVERLAPS WITH STAGGERED STRIPS TO OFFSET

SOD SHALL BE ROLLED TO CREATE A SMOOTH EVEN SURFACE. SOD SHOULD BE WATERED THOROUGHLY DURING INSTALLATION PROCESS.

SCARIFY SURFACE TO A MINIMUM OF 2" DEPTH PRIOR TO THE IMPORT TOPSOIL APPLICATION. TOP SOIL SHALL BE PLACED 2" IN DEPTH IN ALL AREAS TO BE SEEDED. CONTRACTOR TO SUPPLY HIGH QUALITY IMPORTED TOPSOIL HIGH IN HUMAS AND ORGANIC CONTENT FROM A LOCAL SUPPLY. IMPORTED TOPSOIL SHALL BE REASONABLY FREE OF CLAY LUMPS, COARSE SANDS, STONES, ROOTS AND OTHER FOREIGN DEBRIS.

IF INADEQUATE MOISTURE IS PRESENT IN SOIL, APPLY WATER AS NECESSARY FOR OPTIMUM MOISTURE FOR SEED APPLICATION.

ALL SEED SHALL BE HIGH QUALITY, TREATED LAWN TYPE SEED AND IS FREE OF NOXIOUS GRASS SEEDS. THE SEED APPLICATION SHALL BE UNIFORMLY DISTRIBUTED ON THE AREAS INDICATED ON PLANS HYDROMUL CH WITH BERMUDA GRASS SEED AT A RATE OF TWO POUNDS PER ONE THOUSAND

AFTER APPLICATION, NO EQUIPMENT SHALL OPERATE OVER APPLIED AREAS. WATER SEEDED AREAS IMMEDIATELY AFTER INSTALLATION TO SATURATION. ALL LAWN AREAS TO BE HYDROMULCHED SHALL ACHIEVE 75-80% COVERAGE WITH AN INCH TALL STAND PRIOR TO FINAL ACCEPTANCE.

ALL RIGHT-OF-WAY TO BE SODDED BEFORE ACCEPTANCE.

LANDSCAPE NOTES

REFERENCE SITEWORK AND SPECIFICATIONS FOR INFORMATION NEEDED FOR LANDSCAPE WORK.

CONTRACTOR TO VERIFY AND LOCATE ALL PROPOSED AND EXISTING STRUCTURES. NOTIFY LANDSCAPE ARCHITECT OR DESIGNATED REPRESENTATIVE FOR ANY LAYOUT DISCREPANCIES OR ANY CONDITION THAT WOULD PROHIBIT THE INSTALLATION AS SHOWN.

CONTRACTOR SHALL CALL 811 TO VERIFY AND LOCATE ANY AND ALL UTILITIES ON SITE PRIOR TO COMMENCING WORK. LANDSCAPE ARCHITECT SHOULD BE NOTIFIED OF ANY CONFLICTS.

A MINIMUM OF 2% SLOPE SHALL BE PROVIDED AWAY FROM ALL STRUCTURES. LANDSCAPE ISLANDS SHALL BE CROWNED, AND UNIFORM THROUGHOUT THE SITE.

ALL PLANTING AREAS SHALL BE GRADED SMOOTH TO ACHIEVE FINAL CONTOURS AS INDICATED ON PLAN WITH 3" OF TOPSOIL AND 3" OF COMPOST AND CONSISTENTLY BLENDED TO A DEPTH OF 9". ALL BEDS SHALL BE CROWNED TO ANTICIPATE SETTLEMENT AND ENSURE PROPER DRAINAGE.

PLANTING AREAS AND SOD TO BE SEPARATED BY STEEL EDGING. EDGING TO BE GREEN IN COLOR AND A MINIMUM OF 3/16" THICK. EDGING SHALL BE STAKED FROM THE INSIDE OF BED. EDGING NOT TO BE MORE THAN 1/2" ABOVE FINISHED GRADE.

MULCH SHALL BE INSTALLED AT 1/2" BELOW THE TOPS OF SIDEWALKS AND CURBING. QUANTITIES ON THESE PLANS ARE FOR REFERENCE ONLY. THE SPACING OF PLANTS SHOULD BE AS INDICATED ON PLANS OR OTHERWISE NOTED. ALL TREES AND SHRUBS

SHALL BE PLANTED PER DETAILS. CONTAINER GROWN PLANT MATERIAL IS PREFERRED HOWEVER BALL AND BURLAP PLANT MATERIAL CAN BE SUBSTITUTED IF NEED BE AND IS APPROPRIATE TO THE SIZE

AND QUALITY INDICATED ON THE PLANT MATERIAL LIST. TREES SHALL BE PLANTED AT A MINIMUM OF 5' FROM ANY UTILITY LINE, SIDEWALK OR

CURB. TREES SHALL ALSO BE 10' CLEAR FROM FIRE HYDRANTS.

4" OF SHREDDED HARDWOOD MULCH (2" SETTLED THICKNESS) SHALL BE PLACED OVER 4.1 OZ WOVEN, WEED BARRIER FABRIC OR APPROVED EQUAL. WEED BARRIER FABRIC SHALL BE USED IN PLANT BEDS AND AROUND ALL TREES AND SHALL BE DE WITT 'WEED BARRIER' OR APPROVED EQUAL. MULCH SHALL BE SHREDDED BARK OR RUBBER LANDSCAPE MULCH. PINE STRAW MULCH IS PROHIBITED.

CONTRACTOR TO PROVIDE UNIT PRICING OF LANDSCAPE MATERIALS AND BE RESPONSIBLE FOR OBTAINING ALL LANDSCAPE AND IRRIGATION PERMITS.

N THE ABSENCE OF AN IRRIGATION SYSTEM OR AREAS BEYOND THE COVERAGE LIMITS OF A PERMANENT IRRIGATION SYSTEM, CONTRACTOR SHALL WATER SOD TEMPORARILY, BY ANY MEANS AVAILABLE, TO DEVELOP ADEQUATE GROWTH. TURF SHALL BE IN 100% ESTABLISHMENT AT THE TIME OF ACCEPTANCE.

ALL PLANTING BEDS SHALL HAVE AN AUTOMATIC IRRIGATION SYSTEM WITH A FREEZE/RAIN SENSOR. SYSTEM SHALL ALSO HAVE AN ET WEATHER BASED CONTROLLER AND BE DESIGNED AND INSTALLED BY A LICENSED IRRIGATOR.

MAINTENANCE REQUIREMENTS: VEGETATION SHOULD BE INSPECTED REGULARLY TO ENSURE THAT PLANT MATERIAL IS ESTABLISHING PROPERLY AND REMAINS IN A HEALTHY GROWING

CONDITION APPROPRIATE FOR THE SEASON. IF DAMAGED OR REMOVED, PLANTS MUST BE REPLACED BY A SIMILAR VARIETY AND SIZE. MOWING, TRIMMING, EDGING AND SUPERVISION OF WATER APPLICATIONS SHALL

BE THE RESPONSIBILITY OF THE CONTRACTOR UNTIL THE OWNER OR OWNER'S REPRESENTATIVE ACCEPTS AND ASSUMES REGULAR MAINTENANCE.

ALL LANDSCAPE AREAS SHOULD BE CLEANED AND KEPT FREE OF TRASH, DEBRIS, WEEDS AND OTHER MATERIAL.

MISCELLANEOUS MATERIALS:

STEEL EDGING SHALL BE 3/16" X 4 X 16' DARK GREEN DURAEDGE STEEL LANDSCAPE EDGING.

DECOMPOSED GRANITE SHALL CONSIST OF A NATURAL MIX OF GRANITE AGGREGATE NOT TO EXCEED 1/8" IN DIAMETER AND COMPOSED OF VARIOUS STAGES OF DECOMPOSED EARTH BASE. DG SHALL BE PLACED OVER FILTER FABRIC AT A MINIMUM OF 3" DEPTH.

IT SCHEDULE								
.ABEL	COMMON NAME	SCIENTIFIC NAME	SIZE	NOTES				
	SHADE TREES							
3O-M	Bur Oak - Mitigation	Quercus macrocarpa	4" cal.	14' ht., 4' spread				
Ε	Cedar Elm	Ulmus crassifolia	4" cal.	14' ht., 4' spread, matching				
.E	Lacebark Elm	Ulmus parvifolia 'Sempervirens'	4" cal.	14' ht., 4' spread				
60 0	Shumard Oak	Quercus shumardii	4" cal.	14' ht., 4' spread				
	ORNAMENTAL TREES							
/IP	Mexican Plum	Prunus mexicana	30 gal.	8' ht., 4' spread min.				
	SHRUBS							
ЪВН	Dwarf Burford Holly	llex cornuta ' Burford Nana'	5 gal.	full, 20" spread, 36" o.c.				
ΟY	Dwarf Yaupon Holly	llex vomitoria 'Condeaux'	5 gal.	full, 24" sprd, 24" o.c.				
/IS	Morning Light Miscanthus	Miscanthus sinensis 'Morning Light'	5 gal.	full, 20" spread, 36" o.c.				
IRS	Nellie R Stevens Holly	Illex x 'Nellie R. Stevens'	7 gal.	full, 40" o.c.				
S	Texas Sage 'Thundercloud'	Leucophyllum frutescens 'Thundercloud'	5 gal.	full, 24" sprd, 30" o.c.				
	GROUNDCOVER/VINES/GRASS							
BL	Big Blue Liriope	Liriope muscari 'Big Blue'	1 gal.	full, 18" o.c.				
SC	Seasonal Color		4" pots	full, 12" o.c.				
	Bermuda Solid Sod	Cynodon dactylon						
	Decomposed Granite							
	•							

Plant list is an aid to bidders only. Contractor shall verify all quantities on plan. All heights and spreads are minimums. Trees shall have a strong central leader and be of matching specimens. All plant material shall meet or exceed remarks as indicated.





AWR Designs, LLC P.O. Box 1746 Aledo, Texas 76008 amanda@awr-designs.com . 512.517.5589

3005 N. GOLIAD ST ROCKWALL, TEXAS ALL THAT CERTAIN LOT, TRACT OR PARCEL OF LAND SITUATED IN THE S. KING SURVEY, ABSTRACT No. 131, CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS, AND BEING PART OF THAT TRACT OF LAND DESCRIBED IN A DEED FROM ARKOMA REALTY, LTD., TO ARKOMA DEVELOPMENT, L.L.C., AS RECORDED IN VOLUME 4411, PAGE 290 OF THE REAL PROPERTY RECORDS OF *Rockwall county, Texas* January 16, 2020

LANDSCAPE PLAN

MIXED-USE DEVELOPMENT

WIER & ASSOCIATES, INC. ENGINEERS SURVEYORS LAND PLANNERS 2201 E. LAMAR BLVD., SUITE 200E ARLINGTON, TEXAS 76006 METRO (817)467-7700 Texas Firm Registration No. F-2776 www.WierAssociates.com

CASE No.: SP2019-023

DATE: 1/16/2020 W.A. No. 19022