



DEVELOPMENT APPLICATION

City of Rockwall
Planning and Zoning Department
385 S. Goliad Street
Rockwall, Texas 75087

STAFF USE ONLY

PLANNING & ZONING CASE NO. P2021-016

NOTE: THE APPLICATION IS NOT CONSIDERED ACCEPTED BY THE CITY UNTIL THE PLANNING DIRECTOR AND CITY ENGINEER HAVE SIGNED BELOW.

DIRECTOR OF PLANNING: _____

CITY ENGINEER: _____

Please check the appropriate box below to indicate the type of development request [SELECT ONLY ONE BOX]:

Platting Application Fees:

- Master Plat (\$100.00 + \$15.00 Acre)¹
- Preliminary Plat (\$200.00 + \$15.00 Acre)¹
- Final Plat (\$300.00 + \$20.00 Acre)¹ CONVEYANCE PLAT
- Replat (\$300.00 + \$20.00 Acre)¹
- Amending or Minor Plat (\$150.00)
- Plat Reinstatement Request (\$100.00)

Site Plan Application Fees:

- Site Plan (\$250.00 + \$20.00 Acre)¹
- Amended Site Plan/Elevations/Landscaping Plan (\$100.00)

Zoning Application Fees:

- Zoning Change (\$200.00 + \$15.00 Acre)¹
- Specific Use Permit (\$200.00 + \$15.00 Acre)¹
- PD Development Plans (\$200.00 + \$15.00 Acre)¹

Other Application Fees:

- Tree Removal (\$75.00)
- Variance Request (\$100.00)

Notes:

¹: In determining the fee, please use the exact acreage when multiplying by the per acre amount. For requests on less than one acre, round up to one (1) acre.

PROPERTY INFORMATION [PLEASE PRINT]

Address S. Hwy 205

Subdivision Dalton Goliad Addition Lot 4 & 5 Block A

General Location northwest corner of Dalton Road and S.H. 205

ZONING, SITE PLAN AND PLATTING INFORMATION [PLEASE PRINT]

Current Zoning GR w/N SH 205 Overlay Current Use vacant/detention pond

Proposed Zoning Same Proposed Use commercial/retail uses

Acreage 1.927 Lots [Current] 2 Lots [Proposed] 2

SITE PLANS AND PLATS: By checking this box you acknowledge that due to the passage of HB3167 the City no longer has flexibility with regard to its approval process, and failure to address any of staff's comments by the date provided on the Development Calendar will result in the denial of your case.

OWNER/APPLICANT/AGENT INFORMATION [PLEASE PRINT/CHECK THE PRIMARY CONTACT/ORIGINAL SIGNATURES ARE REQUIRED]

<input type="checkbox"/> Owner	<u>Rockwall 205-552, LLC</u>	<input checked="" type="checkbox"/> Applicant	<u>Vasquez Engineering, LLC</u>
Contact Person	<u>Donald L. Silverman</u>	Contact Person	<u>Juan J. Vasquez</u>
Address	<u>4622 Maple Ave.</u> <u>Suite 200</u>	Address	<u>1919 S. Shiloh Road</u> <u>Suite 440</u>
City, State & Zip	<u>Dallas, TX 75219</u>	City, State & Zip	<u>Garland, TX 75042</u>
Phone	<u>214-393-3983</u>	Phone	<u>972-278-2948</u>
E-Mail	<u>jholman@voyagerinvestments.com</u>	E-Mail	<u>jvasquez@vasquezengineering.com</u>

NOTARY VERIFICATION [REQUIRED]


Before me, the undersigned authority, on this day personally appeared Donald L. Silverman [Owner] the undersigned, who stated the information on this application to be true and certified the following:


"I hereby certify that I am the owner for the purpose of this application; all information submitted herein is true and correct; and the application fee of \$ 150.00, to cover the cost of this application, has been paid to the City of Rockwall on this the 6 day of April, 20 21. By signing this application, I agree that the City of Rockwall (i.e. "City") is authorized and permitted to provide information contained within this application to the public. The City is also authorized and permitted to reproduce any copyrighted information submitted in conjunction with this application, if such reproduction is associated or in response to a request for public information."


Given under my hand and seal of office on this 6th day of April, 20 21.

Owner's Signature [Signature]

Notary Public in and for the State of Texas [Signature]





P2021-016- LOTS 8 & 9, BLOCK A,
 DALTON GOLIAD ADDITION
 REPLAT - LOCATION MAP = 



City of Rockwall

Planning & Zoning Department
 385 S. Goliad Street
 Rockwall, Texas 75032
 (P): (972) 771-7745
 (W): www.rockwall.com

The City of Rockwall GIS maps are continually under development and therefore subject to change without notice. While we endeavor to provide timely and accurate information, we make no guarantees. The City of Rockwall makes no warranty, express or implied, including warranties of merchantability and fitness for a particular purpose. Use of the information is the sole responsibility of the user.





CHECKLIST FOR PLAT SUBMITTALS

City of Rockwall
 Planning and Zoning Department
 385 S. Goliad Street
 Rockwall, Texas 75087

Case Type:

- Minor/Amending Plat
 Final Plat
 Master Plat
 Replat
 Preliminary Plat
 Vacation Plat

Case Number

Reviewed By:

Review Date:

NOTES: The requirements listed below are based on the case type, which is indicated in the '[]' below the requirement description. On the checklist below a Replat, Minor Subdivision Plat, and Vacation Plat would be required to meet all the same requirements as a Final Plat.

Requirements	✓ = OK	N/A	Comments
Case Number [Final Plat, Preliminary Plat & Master Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	The case number will be provided by staff and placed in the lower right-hand corner of all new submittals.
Items Necessary for Plat Review:			
✓ Plat	<input checked="" type="checkbox"/>	<input type="checkbox"/>	[Final Plat, Preliminary Plat & Master Plat]
✓ Treescap Plan	<input type="checkbox"/>	<input checked="" type="checkbox"/>	If Applicable [Final Plat & Preliminary Plat]
✓ Landscape Plan	<input type="checkbox"/>	<input checked="" type="checkbox"/>	If Applicable [Final Plat & Preliminary Plat]
✓ Plat Reinstatement Request	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Check w/ Planning Staff
Submittal Requirements [Final Plat, Preliminary Plat & Master Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Four (4) large (18" x 24") folded copies and one (1) PDF digital copy of each plat is required at the time of submittal.
Engineering Information [Final Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Provide accurate plat dimensions with all engineering information necessary to reproduce the plat on the ground. ENGINEERING SUBMITTAL AND APPROVAL REQUIRED PRIOR TO SUBMITTING AN APPLICATION FOR FINAL PLAT.
Title Block:			
Type of Plat [Master, Preliminary, Final or Replat]			
Subdivision Name (Proposed or Approved)			
Lot / Block Designation	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide the title block information in the lower right-hand corner.
Number of Lots (Proposed)			
Total Acreage			
City, State, County			
Owner, Developer, and/or Surveyor/Engineer (Name/Address/Phone Number/Date of Preparation) [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	This includes the names and addresses of the sub dividers, record owner, land planner, engineer and/or surveyor. The date of plat preparation should also be put in the lower right-hand corner.
Survey Monuments/State Plane Coordinates [Final Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	The location of the development is required to be tied to a Rockwall monument, or tie two (2) corners to state plan coordinates (NAD 83 State Plane Texas, North Central [7202], US Survey Feet).
Vicinity Map [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	A Vicinity Map should show the boundaries of the proposed subdivision relative to the rest of the city.
North Point [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	The north point or north arrow must be facing true north (or straight up) on all plans, unless the scale of the drawings or scope of the project requires a different position.
Numeric and Graphic Scale [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Plats should be drawn to an Engineering Scale of 1"=50', 1"=100', etc...
Subdivision (Boundary, Acreage, and Square Footage) [Final Plat, Preliminary Plat & Master Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Indicate the subdivision boundary lines, and acreage and square footage. For Master Plats provide a schematic layout of the entire tract to be subdivided, any remainder tracts and its relationship to adjacent property and existing adjoining developments.
Lot and Block (Designation, Width, Depth and Area) [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Identification of each lot and block by number or letter. For each lot indicate the square footage and acreage or provide a calculation sheet. Also provide a lot count.
Dwelling Units/Population Density [Master Plat]	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the proposed number of dwelling units and population densities.
Building Setbacks [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label the building lines where adjacent to a street.
Easements [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label all existing and proposed easements relative to the site and include the type, purpose and width.
City Limits [Final Plat, Preliminary Plat & Master Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Indicate the location of the City Limits, contiguous or within the platting area.
Utilities (P)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the locations of all existing and proposed utilities. Include the size and type of each.

Property Lines <i>[Final Plat, Preliminary Plat & Master Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide all the proposed and platted property lines.
Streets <i>[Final Plat, Preliminary Plat & Master Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label all proposed and existing streets with the proposed or approved names. For Master Plats indicate the existing arterials and collector streets to serve the land to be platted consistent with the Thoroughfare Plan or proposed amendments.
Right-Of-Way and Centerline <i>[Final Plat, Preliminary Plat & Master Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label the right-of-way width and street centerline for each street both within and adjacent to the development.
Additional Right-Of-Way <i>[Final Plat & Preliminary Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the location and dimensions of any proposed right-of-way dedication.
Corner Clips <i>[Final Plat & Preliminary Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate all existing and proposed corner clips and any subsequent dedication.
Median Openings <i>[Preliminary Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Locate and identify existing and/or proposed median openings and left turn channelization.
Topographical Contours <i>[Preliminary Plat & Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Topographical information and physical features to include contours at 2-foot intervals.
Flood Elevations <i>[Preliminary Plat & Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Show 100-Year & 50-Year floodplain and floodway boundaries (if applicable).
Drainage Areas <i>[Preliminary Plat & Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Show all drainage areas and all proposed storm drainages areas with sizes if applicable.
Wooded Areas <i>[Preliminary Plat & Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the boundaries of all adjacent wooded areas.
Zoning and Land Use Information <i>[Preliminary Plat & Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate all proposed land uses, and existing and proposed zoning classifications. For Master Plats indicate the proposed major categories of land use.
Existing Man-Made Features <i>[Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate all significant man-made features such as railroad, roads, buildings, utilities or other physical structures as shown on USGS topographic maps, utility company records and city records when such features affect the plans.
Parks and Open Space <i>[Preliminary Plat & Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Identify the dimensions, names and description of all parks and open spaces, both existing and proposed. For Master Plats also indicate schools and other public uses as consistent with those shown in the comprehensive plan.
Proposed Improvements <i>[Preliminary Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate how the proposed improvements would relate to those in the surrounding area.
Water Sources <i>[Preliminary Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate water sources inside the city limits or in the extraterritorial jurisdiction (ETJ).
Sewage Disposal <i>[Preliminary Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate sewage disposal method inside the city limits or in the extraterritorial jurisdiction (ETJ).
Adjacent Properties <i>[Final Plat & Preliminary Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Record owners of contiguous parcels of subdivided land, names and lot patterns of contiguous subdivisions, approved Concept Plans, reference recorded subdivision plats adjoining platted land by record name and by deed record volume and page.
Phasing Plan <i>[Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Designation of each phase of development within the subdivision, the order of development, and a schedule for the development of each phase of the master plan.
Dedication <i>[Final Plat, Preliminary Plat & Master Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Indicate the boundary lines, dimensions and descriptions, of spaces to be dedicated for public use of the inhabitants of the development.
Statement of Service <i>[Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Provide a detailed statement of how the proposed subdivision will be served by water, wastewater, roadway and drainage facilities that have adequate capacity to serve the development.
Standard Plat Wording <i>[Final Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide the appropriate plat wording provided in the application packet that details the designation of the entity responsible for the operation and maintenance of any commonly held property and a waiver releasing the city of such responsibility, a waiver releasing the City for damages in establishment or alteration of grade.
Legal Description <i>[Final Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Place the Legal Description (Metes and Bounds Description/Field Notes) where indicated in the Owner's Certificate per the application packet.
Storm Drainage Improvements Statement <i>[Final Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Provide the appropriate statement of developer responsibility for storm drainage improvements found in the application packet.
Dedication Language <i>[Final Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide the instrument of dedication or adoption signed by the owners, which is provided in the application packet.
Seal/Signature <i>[Final Plat]</i>	<input type="checkbox"/>	<input type="checkbox"/>	Required to have the seal and signature of surveyor responsible for the surveying the development and/or the preparation of the plat.
Public Improvement Statement <i>[Final Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Provide the appropriate statement indicating that no building permits will be issued until all public improvements are accepted by the City as provided in the application packet.
Plat Approval Signatures <i>[Final Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide a space for signatures attesting approval of the plat.

Compliance with Preliminary Plat <i>[Final Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Does the plat comply with all the special requirements developed in the preliminary plat review?
Review Plans with Franchise Utility Companies <i>[Final Plat, Preliminary Plat & Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Review the proposed plans and plat with electric, gas, cable and phone companies.


LINETYPE TABLE

	BOUNDARY LINE
	ADJOINER LINE
	EASEMENT LINE
	BUILDING LINE
	STREET CENTERLINE

D=90°32'33"
R=40.00'
L=63.21'
CB=N44°12'06"E
CD=56.84'

LOT 26, BLOCK C HARLAN PARK - PHASE TWO CAB. C, SLD. 266 P.R.R.C.T.
LOT 27, BLOCK C HARLAN PARK - PHASE TWO CAB. C, SLD. 266 P.R.R.C.T.
LOT 28, BLOCK C HARLAN PARK - PHASE TWO CAB. C, SLD. 266 P.R.R.C.T.
LOT 29, BLOCK C HARLAN PARK - PHASE TWO CAB. C, SLD. 266 P.R.R.C.T.
LOT 30, BLOCK C HARLAN PARK - PHASE TWO CAB. C, SLD. 266 P.R.R.C.T.

NOTE:
Lot 4R will require screening/buffering from the adjacent residential properties in accordance with the residential screening requirements of the Unified Development Code.




STATE HIGHWAY NO. 205
(CALLED 100' RIGHT-OF-WAY)

10' RIGHT-OF-WAY DEDICATION
CABINET J, SLIDE 17


F.M. 552

MINOR PLAT
BEING A CONVEYANCE PLAT FOR
DALTON GOLIAD ADDITION
LOTS 4R AND 5R, BLOCK A
BEING A REPLAT OF LOTS 4 AND 5, BLOCK A,
DALTON GOLIAD ADDITION
T. R. BAILEY SURVEY, ABSTRACT NO. 30
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS



CASE NO. P -		PEISER & MANKIN SURVEYING, LLC www.peisersurveying.com		SHEET
JOB NO.:	15-1216		1604 HART STREET SOUTH LAKE, TEXAS 76092 817-481-1806 (O)	1
DATE:	4/7/2021			OF
SCALE:	1" = 50'	COMMERCIAL RESIDENTIAL BOUNDARIES TOPOGRAPHY MORTGAGE		2
DRAWN:	J.B.W.			FIRM No. 100999-00

VICINITY MAP
N.T.S.



NOTES:

1. IRF – Iron Rod Found
2. IRS – Iron Rod Set w/ "PEISER & MANKIN SURV" red plastic cap
3. Notice: Selling a portion of this addition by metes and bounds is a violation of city subdivisions ordinance and state platting statutes and is subject to fines and withholding of utilities and building certificates.
4. P.O.B. – Point of Beginning.
5. O.P.R.D.C.T. – Official Public Records, Collin County, Texas.
6. D.R.C.C.T. – Deed Records, Collin County, Texas.
7. Bearings based on the Texas State Plane Coordinate System, North Central Zone 4202, NAD83, as derived by field observations utilizing the RTK Network Administrated by Western Data Systems.
8. SLD. – SLIDE
9. CAB. – CABINET
10. This Final Plat is for conveyance only and not for the development of the subject property.
11. A conveyance plat is a record of property approved by the City of Rockwall for the purpose of sale or conveyance in its entirety or interests thereon defined. No building permit shall be issued nor permanent public utility service provided until a final plat is approved, filed of record, and public improvements accepted in accordance with the provisions of the Subdivision Ordinance of the City of Rockwall. Selling a portion of this property by metes and bounds, except as shown on an approved, filed, and accepted conveyance plat, final plat, or replat is a violation of the city ordinance and State law.

RECOMMENDED FOR FINAL APPROVAL

Planning & Zoning Commission, Chairman Date

APPROVED:

I hereby certify that the above and foregoing plat of an addition to the City of Rockwall, Texas, was approved by the City Council of the City of Rockwall on the _____ day of _____, 20__.

This approval shall be invalid unless the approved plat for such addition is recorded in the office of the County Clerk of Rockwall, County, Texas, within one hundred eighty (180) days from said date of final approval.

WITNESS OUR HANDS, this _____ day of _____, 20__.

Mayor, City of Rockwall City Secretary City Engineer

SURVEYOR'S CERTIFICATE

I, Timothy R. Mankin, a Registered Professional Land Surveyor in the State of Texas, do hereby certify that I prepared this plat from an actual on the ground survey of the land and that the monuments shown thereon were properly placed under my personal supervision in accordance with the subdivision regulations of the City of Rockwall, Texas.

4/7/2021 PRELIMINARY, THIS DOCUMENT SHALL NOT BE RECORDED FOR ANY PURPOSE AND SHALL NOT BE USED OR VIEWED OR RELIED UPON AS A FINAL SURVEY DOCUMENT

Timothy R. Mankin Date
Registered Professional Land Surveyor, No. 6122

NOW, THEREFORE, KNOW ALL MEN BY THESE PRESENTS:

STATE OF TEXAS
COUNTY OF ROCKWALL

I the undersigned owner of the land shown on this plat, and designated herein as the **DALTON GOLIAD ADDITION** subdivision to the City of Rockwall, Texas, and whose name is subscribed hereto, hereby dedicate to the use of the public forever all streets, alleys, parks, water courses, drains, easements and public places thereon shown on the purpose and consideration therein expressed. I further certify that all other parties who have a mortgage or lien interest in the **DALTON GOLIAD ADDITION** subdivision have been notified and signed this plat. I understand and do hereby reserve the easement strips shown on this plat for the purposes stated and for the mutual use and accommodation of all utilities desiring to use or using same. I also understand the following:

1. No buildings shall be constructed or placed upon, over, or across the utility easements as described herein.
2. Any public utility shall have the right to remove and keep removed all or part of any buildings, fences, trees, shrubs, or other growths or improvements which in any way endanger or interfere with construction, maintenance or efficiency of their respective system on any of these easement strips; and any public utility shall at all times have the right of ingress or egress to, from and upon the said easement strips for purpose of construction, reconstruction, inspecting, patrolling, maintaining, and either adding to or removing all or part of their respective system without the necessity of, at any time, procuring the permission of anyone.
3. The City of Rockwall will not be responsible for any claims of any nature resulting from or occasioned by the establishment of grade of streets in the subdivision.
4. The developer and subdivision engineer shall bear total responsibility for storm drain improvements.
5. The developer shall be responsible for the necessary facilities to provide drainage patterns and drainage controls such that properties within the drainage area are not adversely affected by storm drainage from the development.
6. All detention/drainage systems to be maintained, repaired, and replaced by property owner.
7. No house dwelling unit, or other structure shall be constructed on any lot in this addition by the owner or any other person until the developer and/or owner has complied with all requirements of the Subdivision Regulations of the City of Rockwall regarding improvements with respect to the entire block on the street or streets on which property abuts, including the actual installation of streets with the required base and paving, curb and gutter, water and sewer, drainage structures, storm structures, storm sewers, and alleys, all according to the specifications of the City of Rockwall; or Until an escrow deposit, sufficient to pay for the cost of such improvements, as determined by the city's engineer and/or city administrator, computed on a private commercial rate basis, has been made with the city secretary, accompanied by an agreement signed by the developer and/or owner, authorizing the city to make such improvements at prevailing private commercial rates, or have the same made by a contractor and pay for the same out of the escrow deposit, should the developer and/or owner fail or refuse to install the required improvements within the time stated in such written agreement, but in no case shall the City be obligated to make such improvements itself. Such deposit may be used by the owner and/or developer as progress payments as the work progresses in making such improvements by making certified requisitions to the city secretary, supported by evidence of work done; or Until the developer and/or owner files a corporate surety bond with the city secretary in a sum equal to the cost of such improvements for the designated area, guaranteeing the installation thereof within the time stated in the bond, which time shall be fixed by the city council of the City of Rockwall. I further acknowledge that the dedications and/or exaction's made herein are proportional to the impact of the Subdivision upon the public services required in order that the development will comport with the present and future growth needs of the City; I, my successors and assigns hereby waive any claim, damage, or cause of action that I may have as a result of the dedication of exactions made herein.

WITNESS MY HAND, this _____ day of _____, 2021

ROCKWALL 205-552, LLC

By: DONALD L. SILVERMAN, MANAGER

STATE OF TEXAS:
COUNTY OF DALLAS:

BEFORE ME, the undersigned authority, a Notary Public in and for the State of Texas, on this day personally appeared DONALD L. SILVERMAN, MANAGER, known to me to be the person whose name is subscribed to the foregoing instrument and acknowledged to me that he executed the same for the purpose and consideration thereof expressed.

GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS _____ DAY OF _____, 2021.

NOTARY PUBLIC in and for the STATE OF TEXAS

OWNER'S CERTIFICATION

WHEREAS ROCKWALL 205-552, LLC, is the sole owner of that tract of land in the County of Rockwall, State of Texas, situated in the T. R. BAILEY SURVEY, ABSTRACT NO. 30, and being a portion of that certain tract of land conveyed to ROCKWALL 205-552, LLC in Warranty Deed recorded under Instrument Number 20150000019501, Deed Records, Rockwall County, Texas, and being all of Lots 4 & 5, Block A, Dalton Goliad Addition, an addition to the City of Rockwall, Rockwall County, Texas, according to the plat thereof recorded in Instrument Number 20210000003578, Official Public Plat Records, Rockwall County, Texas, and being more particularly described as follows:

BEGINNING at a 1/2 inch iron rod found for the northeast corner of said Lot 4, same being in the west right-of-way line of State Highway No. 205 (110 foot right-of-way, at this point), same being in the south line of Block C, Harlan Park – Phase Tow, an addition to the City of Rockwall, Rockwall County, Texas, according to the plat thereof recorded in Cabinet C, Slide 266, Plat Records, Rockwall County, Texas, same being the beginning of a curve to the right having a radius of 2805.03 feet, and a delta angle of 04 deg. 41 min. 34 sec.;

THENCE in a southeasterly direction, along the common line of said Lots 4, 5 and the west right-of-way line of said State Highway No. 205, and along said curve to the right, an arc distance of 229.74 feet, and a chord bearing and distance of South 03 deg. 19 min. 43 sec. East, 229.68 feet to a 1/2 inch iron rod set with "Peiser & Mankin SURV" red plastic cap for angle point;

THENCE South 00 deg. 54 min. 01 sec. East, along the common line of said Lot 5 and said State Highway No. 205, a distance of 49.10 feet to a 1/2 inch iron rod set with "Peiser & Mankin SURV" red plastic cap for the southeast corner of said Lot 5, same being the most easterly northeast corner of Lot 6, Block A, said Dalton Goliad Addition;

THENCE along the common line of said Lot 5 and said Lot 6 as follows:

South 89 deg. 05 min. 59 sec. West, a distance of 302.67 feet to a 1/2 inch iron rod set with "Peiser & Mankin SURV" red plastic cap for the southwest corner of said Lot 5, same being an internal corner of said Lot 6;

North 00 deg. 54 min. 01 sec. West, passing at a distance of 128.81 feet the northwest corner of said Lot 5, same being the southwest corner of aforesaid Lot 4, and continuing along the common line of said Lot 4, and said Lot 6, a total distance of 281.28 feet to a 1/2 inch iron rod found for the northwest corner of said Lot 4, same being the most northerly northeast corner of said Lot 6, same being in the south line of aforesaid Block C;

THENCE North 89 deg. 37 min. 55 sec. East, along the common line of said Lot 4 and said Block C, a distance of 292.95 feet to the POINT OF BEGINNING and containing 83,951 square feet or 1.927 acres of computed land, more or less.

MINOR PLAT
BEING A CONVEYANCE PLAT FOR
DALTON GOLIAD ADDITION
LOTS 4R AND 5R, BLOCK A
BEING A REPLAT OF LOTS 4 AND 5, BLOCK A,
DALTON GOLIAD ADDITION
T. R. BAILEY SURVEY, ABSTRACT NO. 30
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS

CASE NO. P _____

JOB NO.: 15-1216	PEISER & MANKIN SURVEYING, LLC www.peisersurveying.com	1604 HART STREET SOUTHLAKE, TEXAS 76092 817-481-1806 (O)	COMMERCIAL RESIDENTIAL BOUNDARIES TOPOGRAPHY MORTGAGE	Texas Society of Professional Surveyors	SHEET
DATE: 4/7/2021					2
SCALE: NTS					OF
DRAWN: J.B.W.	tmankin@peisersurveying.com	FIRM No. 100999-00	Member Since 1977		2

ENGINEER:

VASQUEZ ENGINEERING, L.L.C.
1919 S. SHILOH ROAD
SUITE 440, LB 44
GARLAND, TEXAS 75042
972-278-2948
CONTACT: JUAN VASQUEZ, P.E.

OWNER:

ROCKWALL 205-552, LLC
4622 MAPLE AVE.
SUITE 200
DALLAS, TEXAS 75219
214-393-3983