



DEVELOPMENT APPLICATION

City of Rockwall
Planning and Zoning Department
385 S. Goliad Street
Rockwall, Texas 75087

STAFF USE ONLY

PLANNING & ZONING CASE NO.

P2021-017

NOTE: THE APPLICATION IS NOT CONSIDERED ACCEPTED BY THE CITY UNTIL THE PLANNING DIRECTOR AND CITY ENGINEER HAVE SIGNED BELOW.

DIRECTOR OF PLANNING:

CITY ENGINEER:

Please check the appropriate box below to indicate the type of development request [SELECT ONLY ONE BOX]:

Platting Application Fees:

- Master Plat (\$100.00 + \$15.00 Acre)¹
- Preliminary Plat (\$200.00 + \$15.00 Acre)¹
- Final Plat (\$300.00 + \$20.00 Acre)¹
- Replat (\$300.00 + \$20.00 Acre)¹
- Amending or Minor Plat (\$150.00)
- Plat Reinstatement Request (\$100.00)

Site Plan Application Fees:

- Site Plan (\$250.00 + \$20.00 Acre)¹
- Amended Site Plan/Elevations/Landscaping Plan (\$100.00)

Zoning Application Fees:

- Zoning Change (\$200.00 + \$15.00 Acre)¹
- Specific Use Permit (\$200.00 + \$15.00 Acre)¹
- PD Development Plans (\$200.00 + \$15.00 Acre)¹

Other Application Fees:

- Tree Removal (\$75.00)
- Variance Request (\$100.00)

Notes:

¹: In determining the fee, please use the exact acreage when multiplying by the per acre amount. For requests on less than one acre, round up to one (1) acre.

PROPERTY INFORMATION [PLEASE PRINT]

Address **3150 Horizon Road, Rockwall, TX 75032**

Subdivision **Presbyterian Hospital of Rockwall Addition**

Lot **25**

Block **A**

General Location **Horizon Road @ Tubbs Road**

ZONING, SITE PLAN AND PLATTING INFORMATION [PLEASE PRINT]

Current Zoning **PD-9**

Current Use

Proposed Zoning **PD-9**

Proposed Use

Acreage **23.0927 acres**

Lots [Current] **1**

Lots [Proposed] **1**

SITE PLANS AND PLATS: By checking this box you acknowledge that due to the passage of HB3167 the City no longer has flexibility with regard to its approval process, and failure to address any of staff's comments by the date provided on the Development Calendar will result in the denial of your case.

OWNER/APPLICANT/AGENT INFORMATION [PLEASE PRINT/CHECK THE PRIMARY CONTACT/ORIGINAL SIGNATURES ARE REQUIRED]

Owner **Rockwall Regional Hospital, LLC**

Applicant **Raymond L. Goodson Jr., Inc.**

Contact Person **Jason Linscott**

Contact Person **Brian R. Wade**

Address **3150 Horizon Road**

Address **12001 N. Central Expy.
Suite 300**

City, State & Zip **Rockwall, TX 75032**

City, State & Zip **Dallas, TX 75243**

Phone **(469) 698-1354**

Phone **(214) 739-8100**

E-Mail **jason.linscott@phrtexas.com**

E-Mail **bwade@rlginc.com**

NOTARY VERIFICATION [REQUIRED]


Before me, the undersigned authority, on this day personally appeared Jason Linscott [Owner] the undersigned, who stated the information on this application to be true and certified the following:


"I hereby certify that I am the owner for the purpose of this application; all information submitted herein is true and correct; and the application fee of \$ ~~780.00~~ \$761.85, to cover the cost of this application, has been paid to the City of Rockwall on this the 19th day of March, 2021. By signing this application, I agree that the City of Rockwall (i.e. "City") is authorized and permitted to provide information contained within this application to the public. The City is also authorized and permitted to reproduce any copyrighted information submitted in conjunction with this application, if such reproduction is associated or in response to a request for public information."

Given under my hand and seal of office on this the 19th day of March, 2021

Owner's Signature

Notary Public in and for the State of Texas





P2021-017- LOT 25, BLOCK A,
 PRESBYTERIAN HOSPITAL OF ROCKWALL ADDITION
 REPLAT - LOCATION MAP =



City of Rockwall

Planning & Zoning Department
 385 S. Goliad Street
 Rockwall, Texas 75032
 (P): (972) 771-7745
 (W): www.rockwall.com

The City of Rockwall GIS maps are continually under development and therefore subject to change without notice. While we endeavor to provide timely and accurate information, we make no guarantees. The City of Rockwall makes no warranty, express or implied, including warranties of merchantability and fitness for a particular purpose. Use of the information is the sole responsibility of the user.





DEVELOPMENT APPLICATION SUBMITTAL REQUIREMENTS

City of Rockwall
Planning and Zoning Department
385 S. Goliad Street
Rockwall, Texas 75087

PLATTING APPLICATION SUBMITTAL REQUIREMENTS [ALL PLAT TYPES]

- PLAT TYPE.
 - MINOR/AMENDING PLAT.
 - MASTER PLAT.
 - PRELIMINARY PLAT.
 - FINAL PLAT.
 - REPLAT.
 - VACATION PLAT.

Staff requires four (4), 18" x 24" copies be submitted at the time the application is submitted. See *Folding Requirements* in this development packet.

- DIGITAL COPY OF THE PLAT. The following is required with all plat submittals:
 - ONE (1) PDF COPY OF THE PLAT
 - ONE (1) SURVEY BOUNDARY CLOSURE REPORT.

* AFTER APPROVAL STAFF WILL REQUIRE ONE (1) AUTOCAD/ESRI (DWG, DXF, OR SHP FILE FORMAT) FILE

- TREESCAPE PLAN [IF APPLICABLE].
- LANDSCAPE PLAN [IF APPLICABLE].
- APPLICATION AND APPLICATION FEE.

SITE PLAN APPLICATION SUBMITTAL REQUIREMENTS

- PLAN SET. A plan set is composed of the following items:
 - SITE PLAN.
 - LANDSCAPE PLAN.
 - TREESCAPE PLAN.
 - PHOTOMETRIC PLAN.
 - BUILDING ELEVATIONS.

Staff requires the submittal of four (4) complete plan sets and one (1) digital copy in .pdf format with a site plan application. All sheets submitted to staff shall be 24" x 36", arranged into sets, and be folded to a 9" x 12" *Tri-Fold* with the project title or identifier facing out.

- BUILDING MATERIAL SAMPLE BOARD. See the *Material Sample Board Design Guidelines* in this development packet.
- VARIANCE REQUEST LETTER. The letter must indicate the variance being requested, the reason for the variance, and the two (2) required compensatory measures being offered to off-set the variance in accordance with the requirements of the UDC.
- APPLICATION AND APPLICATION FEE.

ZONING CHANGE APPLICATION SUBMITTAL REQUIREMENTS

- LEGAL DESCRIPTION. A legal description consists of written words that delineate a specific piece of real property. A legal description may be a metes and bounds description or, if the property is platted, a copy of the plat may be submitted to verify the lot and block survey system.
- ZONING EXHIBIT OR CONCEPT PLAN. A zoning exhibit is generally a survey, plat, concept plan or other visual description of the property [Specific Use Permit (SUP) exhibits can be a site plan or building elevations; check with staff for prior to submitting an application for what is appropriate]. Staff requires four (4), 24" x 36" copies and one digital copy (PDF preferred) be submitted at the time the application is submitted. All submittals should be folded individually so that the project title or identifier is facing out. *In order to reduce the applicant's costs and to conserve paper, staff may accept other sheet sizes for a submittal if an appropriate scale and level of detail is maintained. Check with staff prior to submitting a small or larger drawing size.*
- LETTER OF EXPLANATION. A letter from the applicant or property owner explaining the purpose of the zoning application.
- APPLICATION AND APPLICATION FEE.

IT IS IMPORTANT TO YOU AS AN APPLICANT TO RETURN A FULLY COMPLETED APPLICATION PACKAGE. INCOMPLETE APPLICATION PACKAGES WILL NOT BE ACCEPTED BY STAFF AND WILL BE RETURNED TO APPLICANTS. DUE TO THE PASSAGE OF HB3167, APPLICATIONS AND APPLICATION PACKAGES WILL ONLY BE ACCEPTED ON THE SUBMITTAL DATE AND EARLY AND/OR LATE APPLICATIONS WILL BE RETURNED.



CHECKLIST FOR PLAT SUBMITTALS

City of Rockwall
 Planning and Zoning Department
 385 S. Goliad Street
 Rockwall, Texas 75087

Case Type:

- Minor/Amending Plat
 Final Plat
 Master Plat
 Replat
 Preliminary Plat
 Vacation Plat

Case Number

Reviewed By:

Review Date:

NOTES: The requirements listed below are based on the case type, which is indicated in the '[]' below the requirement description. On the checklist below a Replat, Minor Subdivision Plat, and Vacation Plat would be required to meet all the same requirements as a Final Plat.

Requirements	✓= OK	N/A	Comments
Case Number [Final Plat, Preliminary Plat & Master Plat]	<input type="checkbox"/>	<input type="checkbox"/>	The case number will be provided by staff and placed in the lower right-hand corner of all new submittals.
Items Necessary for Plat Review:			
✓ Plat	<input checked="" type="checkbox"/>	<input type="checkbox"/>	[Final Plat, Preliminary Plat & Master Plat]
✓ Treescape Plan	<input type="checkbox"/>	<input type="checkbox"/>	If Applicable [Final Plat & Preliminary Plat]
✓ Landscape Plan	<input type="checkbox"/>	<input type="checkbox"/>	If Applicable [Final Plat & Preliminary Plat]
✓ Plat Reinstatement Request	<input type="checkbox"/>	<input type="checkbox"/>	Check w/ Planning Staff
Submittal Requirements [Final Plat, Preliminary Plat & Master Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Four (4) large (18" x 24") folded copies and one (1) PDF digital copy of each plat is required at the time of submittal.
Engineering Information [Final Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide accurate plat dimensions with all engineering information necessary to reproduce the plat on the ground. ENGINEERING SUBMITTAL AND APPROVAL REQUIRED PRIOR TO SUBMITTING AN APPLICATION FOR FINAL PLAT.
Title Block:			
Type of Plat [Master, Preliminary, Final or Replat]			
Subdivision Name (Proposed or Approved)			
Lot / Block Designation	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide the title block information in the lower right-hand corner.
Number of Lots (Proposed)			
Total Acreage			
City, State, County			
Owner, Developer, and/or Surveyor/Engineer (Name/Address/Phone Number/Date of Preparation) [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	This includes the names and addresses of the sub dividers, record owner, land planner, engineer and/or surveyor. The date of plat preparation should also be put in the lower right-hand corner.
Survey Monuments/State Plane Coordinates [Final Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	The location of the development is required to be tied to a Rockwall monument, or tie two (2) corners to state plan coordinates (NAD 83 State Plane Texas, North Central [7202], US Survey Feet).
Vicinity Map [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	A Vicinity Map should show the boundaries of the proposed subdivision relative to the rest of the city.
North Point [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	The north point or north arrow must be facing true north (or straight up) on all plans, unless the scale of the drawings or scope of the project requires a different position.
Numeric and Graphic Scale [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Plats should be drawn to an Engineering Scale of 1"=50', 1"=100', etc...
Subdivision (Boundary, Acreage, and Square Footage) [Final Plat, Preliminary Plat & Master Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Indicate the subdivision boundary lines, and acreage and square footage. For Master Plats provide a schematic layout of the entire tract to be subdivided, any remainder tracts and its relationship to adjacent property and existing adjoining developments.
Lot and Block (Designation, Width, Depth and Area) [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Identification of each lot and block by number or letter. For each lot indicate the square footage and acreage or provide a calculation sheet. Also provide a lot count.
Dwelling Units/Population Density [Master Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the proposed number of dwelling units and population densities.
Building Setbacks [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label the building lines where adjacent to a street.
Easements [Final Plat & Preliminary Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label all existing and proposed easements relative to the site and include the type, purpose and width.
City Limits [Final Plat, Preliminary Plat & Master Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Indicate the location of the City Limits, contiguous or within the platting area.
Utilities (P)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the locations of all existing and proposed utilities. Include the size and type of each.

Property Lines <i>[Final Plat, Preliminary Plat & Master Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide all the proposed and platted property lines.
Streets <i>[Final Plat, Preliminary Plat & Master Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label all proposed and existing streets with the proposed or approved names. For Master Plats indicate the existing arterials and collector streets to serve the land to be platted consistent with the Thoroughfare Plan or proposed amendments.
Right-Of-Way and Centerline <i>[Final Plat, Preliminary Plat & Master Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label the right-of-way width and street centerline for each street both within and adjacent to the development.
Additional Right-Of-Way <i>[Final Plat & Preliminary Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Indicate the location and dimensions of any proposed right-of-way dedication.
Corner Clips <i>[Final Plat & Preliminary Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Indicate all existing and proposed corner clips and any subsequent dedication.
Median Openings <i>[Preliminary Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Locate and identify existing and/or proposed median openings and left turn channelization.
Topographical Contours <i>[Preliminary Plat & Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Topographical information and physical features to include contours at 2-foot intervals.
Flood Elevations <i>[Preliminary Plat & Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Show 100-Year & 50-Year floodplain and floodway boundaries (if applicable).
Drainage Areas <i>[Preliminary Plat & Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Show all drainage areas and all proposed storm drainages areas with sizes if applicable.
Wooded Areas <i>[Preliminary Plat & Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the boundaries of all adjacent wooded areas.
Zoning and Land Use Information <i>[Preliminary Plat & Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate all proposed land uses, and existing and proposed zoning classifications. For Master Plats indicate the proposed major categories of land use.
Existing Man-Made Features <i>[Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate all significant man-made features such as railroad, roads, buildings, utilities or other physical structures as shown on USGS topographic maps, utility company records and city records when such features affect the plans.
Parks and Open Space <i>[Preliminary Plat & Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Identify the dimensions, names and description of all parks and open spaces, both existing and proposed. For Master Plats also indicate schools and other public uses as consistent with those shown in the comprehensive plan.
Proposed Improvements <i>[Preliminary Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate how the proposed improvements would relate to those in the surrounding area.
Water Sources <i>[Preliminary Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate water sources inside the city limits or in the extraterritorial jurisdiction (ETJ).
Sewage Disposal <i>[Preliminary Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate sewage disposal method inside the city limits or in the extraterritorial jurisdiction (ETJ).
Adjacent Properties <i>[Final Plat & Preliminary Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Record owners of contiguous parcels of subdivided land, names and lot patterns of contiguous subdivisions, approved Concept Plans, reference recorded subdivision plats adjoining platted land by record name and by deed record volume and page.
Phasing Plan <i>[Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Designation of each phase of development within the subdivision, the order of development, and a schedule for the development of each phase of the master plan.
Dedication <i>[Final Plat, Preliminary Plat & Master Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Indicate the boundary lines, dimensions and descriptions, of spaces to be dedicated for public use of the inhabitants of the development.
Statement of Service <i>[Master Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Provide a detailed statement of how the proposed subdivision will be served by water, wastewater, roadway and drainage facilities that have adequate capacity to serve the development.
Standard Plat Wording <i>[Final Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide the appropriate plat wording provided in the application packet that details the designation of the entity responsible for the operation and maintenance of any commonly held property and a waiver releasing the city of such responsibility, a waiver releasing the City for damages in establishment or alteration of grade.
Legal Description <i>[Final Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Place the Legal Description (Metes and Bounds Description/Field Notes) where indicated in the Owner's Certificate per the application packet.
Storm Drainage Improvements Statement <i>[Final Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide the appropriate statement of developer responsibility for storm drainage improvements found in the application packet.
Dedication Language <i>[Final Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide the instrument of dedication or adoption signed by the owners, which is provided in the application packet.
Seal/Signature <i>[Final Plat]</i>	<input type="checkbox"/>	<input type="checkbox"/>	Required to have the seal and signature of surveyor responsible for the surveying the development and/or the preparation of the plat.
Public Improvement Statement <i>[Final Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Proved the appropriate statement indicating that no building permits will be issued until all public improvements are accepted by the City as provided in the application packet.
Plat Approval Signatures <i>[Final Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide a space for signatures attesting approval of the plat.

Compliance with Preliminary Plat <i>[Final Plat]</i>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Does the plat comply with all the special requirements developed in the preliminary plat review?
Review Plans with Franchise Utility Companies <i>[Final Plat, Preliminary Plat & Master Plat]</i>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Review the proposed plans and plat with electric, gas, cable and phone companies.

Parcel Map Check Report

Client:
Client
Client Company
Address 1
Date: 4/15/2021 2:23:00 PM

Prepared by:
Preparer
Your Company Name
123 Main Street

Parcel Name: Site 1 - ~SURVEY : 1
Description:
Process segment order counterclockwise: False
Enable mapcheck across chord: False

North: 7,010,361.158395' East: 2,590,301.002611'

Segment# 1: Curve

Length: 111.48' Radius: 915.00'
Delta: 6°58'51" Tangent: 55.81'
Chord: 111.41' Course: N27°49'52"E
Course In: N58°40'43"W Course Out: S65°39'34"E
RP North: 7,010,836.810212' East: 2,589,519.350291'
End North: 7,010,459.684386' East: 2,590,353.017558'

Segment# 2: Line

Course: S46°43'37"E Length: 146.22'
North: 7,010,359.454081' East: 2,590,459.479638'

Segment# 3: Line

Course: N43°16'22"E Length: 536.58'
North: 7,010,750.137185' East: 2,590,827.290471'

Segment# 4: Line

Course: S46°43'37"E Length: 566.96'
North: 7,010,361.499696' East: 2,591,240.091323'

Segment# 5: Line

Course: N43°16'22"E Length: 233.23'
North: 7,010,531.314114' East: 2,591,399.964074'

Segment# 6: Line

Course: S45°47'10"E Length: 112.02'
North: 7,010,453.198214' East: 2,591,480.253467'

Segment# 7: Line

Course: S43°16'22"W Length: 231.39'
North: 7,010,284.723498' East: 2,591,321.641986'

Segment# 8: Line

Course: S46°43'37"E Length: 441.68'
North: 7,009,981.962446' East: 2,591,643.227072'

Segment# 9: Line

Course: N43°16'22"E Length: 215.03'
North: 7,010,138.525471' East: 2,591,790.624223'

Segment# 10: Line

Course: S45°37'11"E Length: 307.79'
North: 7,009,923.251800' East: 2,592,010.605883'

Segment# 11: Line

Course: S54°35'45"W Length: 186.78'
North: 7,009,815.042591' East: 2,591,858.364182'

Segment# 12: Curve

Length: 187.99'	Radius: 1,042.50'
Delta: 10°19'56"	Tangent: 94.25'
Chord: 187.74'	Course: S49°25'46"W
Course In: S35°24'16"E	Course Out: N45°44'12"W
RP North: 7,008,965.318711'	East: 2,592,462.330720'
End North: 7,009,692.939021'	East: 2,591,715.755248'
Segment# 13: Line	
Course: N46°43'37"W	Length: 210.30'
North: 7,009,837.094630'	East: 2,591,562.636828'
Segment# 14: Line	
Course: S88°16'25"W	Length: 28.49'
North: 7,009,836.236323'	East: 2,591,534.159760'
Segment# 15: Curve	
Length: 113.81'	Radius: 1,411.52'
Delta: 4°37'11"	Tangent: 56.93'
Chord: 113.78'	Course: S41°05'32"W
Course In: S46°35'53"E	Course Out: N51°13'04"W
RP North: 7,008,866.363755'	East: 2,592,559.701526'
End North: 7,009,750.486200'	East: 2,591,459.376023'
Segment# 16: Line	
Course: S47°48'26"E	Length: 231.97'
North: 7,009,594.688837'	East: 2,591,631.240105'
Segment# 17: Curve	
Length: 149.38'	Radius: 1,042.50'
Delta: 8°12'36"	Tangent: 74.82'
Chord: 149.25'	Course: S33°01'52"W
Course In: S52°51'50"E	Course Out: N61°04'26"W
RP North: 7,008,965.320587'	East: 2,592,462.324851'
End North: 7,009,469.558347'	East: 2,591,549.882781'
Segment# 18: Line	
Course: S28°55'34"W	Length: 94.93'
North: 7,009,386.471415'	East: 2,591,503.966915'
Segment# 19: Line	
Course: N62°45'02"W	Length: 234.77'
North: 7,009,493.964451'	East: 2,591,295.251318'
Segment# 20: Line	
Course: N62°45'02"W	Length: 177.12'
North: 7,009,575.061552'	East: 2,591,137.787816'
Segment# 21: Curve	
Length: 88.86'	Radius: 825.00'
Delta: 6°10'17"	Tangent: 44.47'
Chord: 88.82'	Course: N59°39'53"W
Course In: N27°14'58"E	Course Out: S33°25'15"W
RP North: 7,010,308.504356'	East: 2,591,515.526684'
End North: 7,009,619.920047'	East: 2,591,061.129667'
Segment# 22: Line	
Course: N56°34'45"W	Length: 772.12'
North: 7,010,045.191592'	East: 2,590,416.681525'
Segment# 23: Line	
Course: N33°25'38"E	Length: 200.00'
North: 7,010,212.108837'	East: 2,590,526.856991'

Segment# 24: Line

Course: N56°34'45"W

North: 7,010,361.162074'

Length: 270.62'

East: 2,590,300.984645'

Perimeter: 5,849.54'

Error Closure: 0.018340

Error North : 0.0036790

Area: 1,005,917Sq.Ft.

Course: N78°25'40"W

East: -0.0179668

Precision 1: 318,948.75

LOT 16, BLOCK A
PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION
CAB. G, SLIDE 315
M.R.R.C.T.

BLPT LLC
VOL. 6368, PG. 303
O.P.R.R.C.T.

MAC SPORTS AND
REHAB LLC
VOL. 6749, PG. 148
O.P.R.R.C.T.

LOT 17, BLOCK A
PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION
CAB. G, SLIDE 315
M.R.R.C.T.

24' FIRELANE, PUBLIC
ACCESS AND UTILITY
EASEMENT
CAB. G, SL. 315,
O.P.R.R.C.T.

10' WATER EASEMENT
CAB. G, SL. 43
M.R.R.C.T.

15' SANITARY SEWER EASEMENT
CAB. G, SL. 43, P.R.R.C.T.

24' FIRELANE, PUBLIC
ACCESS AND UTILITY
EASEMENT
CAB. G, SL. 43,
O.P.R.R.C.T.

20'x25' AT&T
EASEMENT
CAB. G, SL. 43
M.R.R.C.T.

10' UTILITY EASEMENT
(INST. NO. 2020000011578,
O.P.R.R.C.T.)


$\Delta=2'06''22''$
 $R=915.00'$
 $T=16.82'$
 $L=33.63'$
 $CB=N32'22''28''E$
 $CD=33.63'$

LOT 9, BLOCK A
HORIZON RIDGE CENTER
CAB. E, SL. 149
M.R.R.C.T.

CITY OF ROCKWALL
VOL. 1738, PG. 8
O.P.R.R.C.T.



LOT 25, BLOCK A
PRESBYTERIAN HOSPITAL OF
ROCKWALL ADDITION
1,005,917 SQ. FT.,
23.0927 ACRES

LOT 24, BLOCK A
PRESBYTERIAN HOSPITAL OF
ROCKWALL ADDITION
INST. NO. 2020000011578
O.P.R.R.C.T.



LEGEND

- PROPERTY LINE
- EASEMENT LINE
- YCIRF 1/2" IRON ROD WITH YELLOW PLASTIC CAP STAMPED " " FOUND
- IRF IRON ROD FOUND
- CMS / CMF CHISELED "X" SET / FOUND
- (CM) CONTROLLING MONUMENT
- M.R.R.C.T. MAP RECORDS, ROCKWALL COUNTY, TX
- P.R.R.C.T. PLAT RECORDS, ROCKWALL COUNTY, TX
- O.P.R.R.C.T. OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TX
- INST. NO. INSTRUMENT NUMBER
- VOL. VOLUME
- PG. PAGE
- CAB. CABINET
- SL. SLIDE



VICINITY MAP
NOT TO SCALE

FINAL PLAT
OF
**PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION**
LOT 25, BLOCK A
BEING A REPLAT
OF
**PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION**
LOT 24, BLOCK A
TOTAL 23.0927 ACRES

EDWARD TEAL SURVEY, ABSTRACT NO. 207
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS
SCALE: 1" = 40' DATE: 01-15-2021


OWNER:
TEXAS HEALTH RESOURCES
9330 AMBERTON PKWY., SUITE #1000
DALLAS, TX 75243
PHONE NUMBER
C/O CINDY PERRIN

SURVEYOR:
RAYMOND L. GOODSON JR., INC.
12001 N. CENTRAL EXPRESSWAY, STE 300
DALLAS, TX 75243
214-739-8100
rlg@rlginc.com
TX PE REG #P-488
TBPELS REG #100341-00

CASE NUMBER:

SHEET 1 OF 7

RECORDED	INST#	-	JOB NO.	1913.017	E-FILE	1913.017RP	DWG NO.	27,503Z
----------	-------	---	---------	----------	--------	------------	---------	---------



MATCHLINE SHEET 1


MATCHLINE SHEET 3

LEGEND


- PROPERTY LINE
- EASEMENT LINE
- YDIRF 1/2" IRON ROD WITH YELLOW PLASTIC CAP STAMPED "Y" FOUND
- IRF IRON ROD FOUND
- CMF / CM CHISELED "X" SET / FOUND
- (CM) CONTROLLING MONUMENT
- M.R.R.C.T. MAP RECORDS, ROCKWALL COUNTY, TX
- P.R.R.C.T. PLAT RECORDS, ROCKWALL COUNTY, TX
- O.P.R.R.C.T. OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TX
- INST. NO. INSTRUMENT NUMBER
- VOL. VOLUME
- PG. PAGE
- CAB. CABINET
- SL. SLIDE

**FINAL PLAT
OF
PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION
LOT 25, BLOCK A
BEING A REPLAT
OF
PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION
LOT 24, BLOCK A
TOTAL 23.0927 ACRES**

EDWARD TEAL SURVEY, ABSTRACT NO. 207
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS
SCALE: 1" = 40' DATE: 01-15-2021



VICINITY MAP
NOT TO SCALE



OWNER:
TEXAS HEALTH RESOURCES
9330 AMBERTON PKWY., SUITE #1000
DALLAS, TX 75243
PHONE NUMBER
C/O CINDY PERRIN

SURVEYOR:
RAYMOND L. GOODSON JR., INC.
12001 N. CENTRAL EXPRESSWAY, STE 300
DALLAS, TX 75243
214-739-8100
rlg@rlginc.com
TX PE REG #F-483
TBPELS REG #100341-00



CASE NUMBER:

SHEET 2 OF 7

RECORDED	INST#	-	JOB NO.	1913.017	E-FILE	1913.017RP	DWG NO.	27,503Z
----------	-------	---	---------	----------	--------	------------	---------	---------

HORIZON ROAD


(F.M. ROAD NO. 3097)
(A VARIABLE WIDTH RIGHT-OF-WAY) CENTERLINE



VICINITY MAP
NOT TO SCALE

LEGEND

- PROPERTY LINE
- EASEMENT LINE
- YDIRF 1/2" IRON ROD WITH YELLOW PLASTIC CAP STAMPED "....." FOUND
- IRF IRON ROD FOUND
- CMS / CMF CHISELED "X" SET / FOUND
- (CM) CONTROLLING MONUMENT
- M.R.R.C.T. MAP RECORDS, ROCKWALL COUNTY, TX
- P.R.R.C.T. PLAT RECORDS, ROCKWALL COUNTY, TX
- O.P.R.R.C.T. OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TX
- INST. NO. INSTRUMENT NUMBER
- VOL. VOLUME
- PG. PAGE
- CAB. CABINET
- SL. SLIDE



NOTES:

BASIS OF BEARINGS: BASIS OF BEARING: BEARINGS ARE BASED ON THE SOUTHWEST RIGHT-OF-WAY LINE OF HORIZON ROAD (SOUTH 45°46'04" EAST) AS SHOWN ON THE PLAT FOR PRESBYTERIAN HOSPITAL OF ROCKWALL ADDITION RECORDED IN CABINET G, SLIDE 43, OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TEXAS, AS MONUMENTED ON THE GROUND

CONTROLLING MONUMENTS: AS SHOWN

LOT-TO-LOT DRAINAGE WILL NOT BE ALLOWED WITHOUT ENGINEERING SECTION APPROVAL.

EXISTING BUILDINGS TO REMAIN

SEE SHEET 1 OF 4 FOR LINE AND CURVE TABLES

IT SHALL BE THE POLICY OF THE CITY OF ROCKWALL TO WITHHOLD ISSUING BUILDING PERMITS UNTIL ALL STREETS, WATER, SEWER AND STORM DRAINAGE SYSTEMS HAVE BEEN ACCEPTED BY THE CITY. THE APPROVAL OF A PLAT BY THE CITY DOES NOT CONSTITUTE ANY REPRESENTATION, ASSURANCE OR GUARANTEE THAT ANY BUILDING WITHIN SUCH PLAT SHALL BE APPROVED, AUTHORIZED OR PERMIT THEREFORE ISSUED, NOR SHALL SUCH APPROVAL CONSTITUTE ANY REPRESENTATION, ASSURANCE OR GUARANTEE BY THE CITY OF THE ADEQUACY AND AVAILABILITY FOR WATER FOR PERSONAL USE AND FIRE PROTECTION WITHIN SUCH PLAT, AS REQUIRED UNDER ORDINANCE 83-54

THE SUBJECT TRACT IS DEPICTED WITHIN ZONE X ON THE FLOOD INSURANCE RATE MAP, MAP NO. 48397C0040L, DATED SEPTEMBER 26, 2008. ZONE X IS DEFINED THEREON AS "AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN".

THE LOCATION OF THE FLOOD ZONE LINES SHOWN, IF ANY, WERE DETERMINED BY SCALING FROM SAID FEMA MAP. THE ACTUAL LOCATION AS DETERMINED BY ELEVATION CONTOURS MAY DIFFER. THIS FLOOD STATEMENT DOES NOT IMPLY THAT THE PROPERTY OR STRUCTURES THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE. ON RARE OCCASIONS FLOODS CAN AND WILL OCCUR AND FLOOD HEIGHTS MAY BE INCREASED BY MAN-MADE OR NATURAL CAUSES. THIS FLOOD STATEMENT SHALL NOT CREATE LIABILITY ON THE PART OF THE SURVEYOR OR RAYMOND L. GOODSON JR., INC. AS A RESULT OF FLOODING.

**FINAL PLAT
OF
PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION
LOT 25, BLOCK A
BEING A REPLAT
OF
PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION
LOT 24, BLOCK A
TOTAL 23.0927 ACRES**

EDWARD TEAL SURVEY, ABSTRACT NO. 207
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS

SCALE: 1" = 40'

DATE: 01-15-2021

OWNER:
TEXAS HEALTH RESOURCES
9330 AMBERTON PKWY., SUITE #1000
DALLAS, TX 75243
PHONE NUMBER
C/O CINDY PERRIN

SURVEYOR:
RAYMOND L. GOODSON JR., INC.
12001 N. CENTRAL EXPRESSWAY, STE 300
DALLAS, TX 75243
214-739-8100
rlg@rlginc.com
TX PE REG #P-493
TBPELS REG #100341-00




CASE NUMBER:

SHEET 3 OF 7

RECORDED	INST#	-	JOB NO.	1913.017	E-FILE	1913.017RP	DWG NO.	27,503Z
----------	-------	---	---------	----------	--------	------------	---------	---------

TRACT 2
PARKING EASEMENT TRACT
VOL. 5428, PG. 305
R.P.R.R.C.T.
(SOLID HATCHED AREA)

15' TXU ELECTRIC DELIVERY
COMPANY ESMF
CC#200700376826
O.P.R.R.C.T.



VICINITY MAP
NOT TO SCALE

LEGEND

- PROPERTY LINE
- EASEMENT LINE
- YCIWF 1/2" IRON ROD WITH YELLOW PLASTIC CAP STAMPED " " FOUND
- IRF IRON ROD FOUND
- CMF / CMF CHISELED "X" SET / FOUND
- (CM) CONTROLLING MONUMENT
- M.R.R.C.T. MAP RECORDS, ROCKWALL COUNTY, TX
- P.R.R.C.T. PLAT RECORDS, ROCKWALL COUNTY, TX
- O.P.R.R.C.T. OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TX
- INST. NO. INSTRUMENT NUMBER
- VOL. VOLUME
- PG. PAGE
- CAB. CABINET
- SL. SLIDE

FINAL PLAT
 OF
PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION
 LOT 25, BLOCK A
 BEING A REPLAT
 OF
PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION
 LOT 24, BLOCK A
TOTAL 23.0927 ACRES
 EDWARD TEAL SURVEY, ABSTRACT NO. 207
 CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS
 SCALE: 1" = 40'

DATE: 01-15-2021

OWNER:
TEXAS HEALTH RESOURCES
 9330 AMBERTON PKWY., SUITE #1000
 DALLAS, TX 75243
 PHONE NUMBER
 C/O CINDY PERRIN

SURVEYOR:
RAYMOND L. GOODSON JR., INC.
 12001 N. CENTRAL EXPRESSWAY, STE 300
 DALLAS, TX 75243
 214-739-8100
 rlj@riginc.com
 TX PE REG #F-483
 TBPELS REG #100341-00

CASE NUMBER:

SHEET 4 OF 7


RECORDED	INST#	-	JOB NO.	1913.017	E-FILE	1913.017RP	DWG NO.	27,503Z
----------	-------	---	---------	----------	--------	------------	---------	---------

MATCHLINE SHEET 3




MATCHLINE SHEET 5

LINE TABLE		
LINE	BEARING	LENGTH
L1	N62°45'02"W	230.44'
L2	S60°14'09"E	10.00'
L3	N60°38'29"W	10.00'
L4	S53°18'17"E	12.00'
L5	N56°20'58"W	12.00'

CURVE TABLE						
CURVE	DELTA	RADIUS	TANGENT	LENGTH	CH. BRG.	CHORD
C1	53°49'59"	40.50'	20.56'	38.05'	N00°48'33"E	36.67'
C2	1°38'09"	1423.52'	20.32'	40.64'	N28°32'37"E	40.64'
C3	0°24'09"	1423.52'	5.00'	10.00'	N29°33'46"E	10.00'
C4	0°24'19"	1413.52'	5.00'	10.00'	S29°33'41"W	10.00'
C5	3°53'00"	1423.52'	48.26'	96.48'	N31°42'20"E	96.46'
C6	3°02'53"	1423.52'	37.87'	75.73'	N35°10'17"E	75.72'
C7	3°02'41"	1411.52'	37.51'	75.01'	S35°10'24"W	75.00'



VICINITY MAP
NOT TO SCALE



FINAL PLAT
OF
**PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION**
LOT 25, BLOCK A
BEING A REPLAT
OF
**PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION**
LOT 24, BLOCK A
TOTAL 23.0927 ACRES
EDWARD TEAL SURVEY, ABSTRACT NO. 207
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS
SCALE: 1" = 40' DATE: 01-15-2021

- LEGEND**
- PROPERTY LINE
 - EASEMENT LINE
 - YORIF 1/2" IRON ROD WITH YELLOW PLASTIC CAP STAMPED "____" FOUND
 - IRF IRON ROD FOUND
 - CMS / CMF CHISELED "X" SET / FOUND
 - (CM) CONTROLLING MONUMENT
 - M.R.R.C.T. MAP RECORDS, ROCKWALL COUNTY, TX
 - P.R.R.C.T. PLAT RECORDS, ROCKWALL COUNTY, TX
 - O.P.R.R.C.T. OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TX
 - INST. NO. INSTRUMENT NUMBER
 - VOL. VOLUME
 - PG. PAGE
 - CAB. CABINET
 - SL. SLIDE

OWNER: TEXAS HEALTH RESOURCES 9330 AMBERTON PKWY., SUITE #1000 DALLAS, TX 75243 PHONE NUMBER C/O CINDY PERRIN		SURVEYOR: RAYMOND L. GOODSON JR., INC. 12001 N. CENTRAL EXPRESSWAY, STE 300 DALLAS, TX 75243 214-739-8100 rlg@rlginc.com TX PE REG #P-493 TBPELS REG #100341-00		CASE NUMBER: SHEET 5 OF 7	
RECORDED	INST#	JOB NO.	1913.017	E-FILE	1913.017RP
		DWG NO.	27,503Z		

STATE OF TEXAS
COUNTY OF ROCKWALL

Whereas **Rockwall Regional Hospital, LLC**, is the sole owner of a tract of land situated in the Edward Teal Survey, Abstract No. 207, City of Rockwall, Rockwall County, Texas, being the same tract of land described in Deed of Trust to Rockwall Regional Hospital, LLC, recorded in Instrument Number 20190000019597, Official Public Records, Rockwall County, Texas, and being all of Lot 24, Block A, Presbyterian Hospital of Rockwall Addition, an addition to the City of Rockwall, according to the plat recorded in 20200000011578, Official Public Records, Rockwall County, Texas and being more particularly described as follows:

COMMENCING at a 3/8" iron rod found at the intersection of the northerly right-of-way line of Summer Lee Drive (a 60' right-of-way) and the easterly right-of-way line of Rockwall Parkway (a 60' right-of-way) being the west corner of Lot 9, Block A, Horizon Ridge Center Addition, an addition to the City of Rockwall, according to the plat recorded in Cabinet E, Slide 149, Map Records, Rockwall County, Texas;

THENCE along the easterly right-of-way line of said Rockwall Parkway, the following courses and distances:

North 33° 25' 38" East, along the north line of said Lot 9, a distance of 166.37 feet to a point for the beginning of a tangent curve to the left;

In a northerly direction along said curve to the left whose chord bears North 32° 22' 28" East a distance of 33.63 feet, having a radius of 915.00 feet, having a central angle of 02° 06' 22" and an arc length of 33.63 feet to a 1/2" iron rod with yellow plastic cap stamped "Pacheco" found for the north corner of said Lot 9 and an exterior ell corner of said Lot 24 for the **POINT OF BEGINNING**, and continuing on said curve to the left;

In a northerly direction along said curve to the left whose chord bears North 27° 49' 52" East a distance of 111.41 feet, having a radius of 915.00 feet, a central angle of 06° 58' 51" and an arc length of 111.48 feet to a 5/8" iron rod with plastic cap stamped "Pate Sc" found for an exterior ell corner of said Lot 24 and the west corner of Lot 17, Block A, Presbyterian Hospital of Rockwall Addition, an addition to the City of Rockwall, according to the plat recorded in Cabinet G, Slide 315, Map Records, Rockwall County, Texas;

THENCE departing the easterly right-of-way line of said Rockwall Parkway and along the northerly line of said Lot 24, the following courses and distances:

South 46° 43' 37" East, along the southwesterly line of said Lot 17, a distance of 146.22 feet to a 5/8" iron rod with plastic cap stamped "Pate Sc" found for the south corner of said Lot 17 and an exterior ell corner of said Lot 24;

North 43° 16' 22" East, along the southeasterly line of said Lot 17, passing at a distance of 127.65 feet a 5/8" iron rod with plastic cap stamped "Pate Sc" found for the east corner of said Lot 17 and the south corner of Lot 16, Block A, of said Presbyterian Hospital of Rockwall Addition (Cabinet G, Slide 315), continuing along the southeasterly line of said Lot 16 passing at a distance of 154.96 a 1/2" iron rod with red plastic cap stamped "RPLS 48" found for the east corner of said Lot 16 and the south corner of Lot 19, Block A, of said Presbyterian Hospital of Rockwall Addition (Cabinet G, Slide 315), continuing along the southeasterly line of said Lot 19 for a total distance of 536.58 feet to a chiseled "X" in concrete found on the southwest line of Lot 18, Block A, Presbyterian Hospital of Rockwall Addition, an addition to the City of Rockwall, Rockwall County, Texas, according to the plat recorded in Cabinet G, Slide 297, Map Records, Rockwall County, Texas for the most easterly east corner of said Lot 19, the north corner of said Lot 24;

South 46° 43' 37" East, along the southwesterly line of said Lot 18, passing a chiseled "X" in concrete found at a distance of 220.15 feet for the south corner of said Lot 18 and the west corner of Lot 21, Block A, Presbyterian Hospital of Rockwall Addition, an addition to the City of Rockwall, according to the plat recorded in Cabinet I, Slide 87, Map Records, Rockwall County, Texas, continuing along the southwesterly line of said Lot 21 to a chiseled "X" in concrete found for a total distance of 566.96 feet for the south corner of said Lot 21 and an interior ell corner of said Lot 24;

North 43° 16' 22" East, along the southeasterly line of said Lot 21, a distance of 233.23 feet to a 1/2" iron rod found on the southwesterly right-of-way line of Horizon Road (a variable width right-of-way) for the east corner of said Lot 21 and the most northerly northeast corner of said Lot 24;

THENCE South 45° 47' 10" East, along the southwesterly right-of-way line of said Horizon Road, a distance of 112.02 feet to an Aluminum Disk Found stamped "TXDOT" found for the most easterly northeast corner of said Lot 24 and the north corner of Lot 20, Block A, Presbyterian Hospital of Rockwall Addition, an addition to the City of Rockwall, according to the plat recorded in Cabinet H, Slide 63, Map Records, Rockwall County, Texas;

THENCE along the common line between said Lot 24 and said Lot 20, the following courses and distances:

South 43° 16' 22" West, a distance of 231.39 feet to a 1/2" iron rod with yellow plastic cap stamped "RLG INC" found for an interior ell corner of said Lot 24 and the west corner of said Lot 20;

South 46° 43' 37" East, a distance of 441.68 feet to a 1/2" iron rod with yellow plastic cap stamped "Pacheco" found for the south corner of said Lot 20 and an interior ell corner of said Lot 24;

North 43° 16' 22" East, a distance of 215.03 feet to a 1/2" iron rod with yellow plastic cap stamped "Pacheco" found on the southwesterly line of said Horizon Road, for the east corner of said Lot 20 and exterior corner of said Lot 24;

THENCE South 45° 37' 11" East, along the southwesterly right-of-way line of said Horizon Road, a distance of 307.79 feet to a 1/2" iron rod with yellow plastic cap stamped "RLG INC" found at the intersection of the southwesterly right-of-way line of said Horizon Road and the northerly right-of-way of Tubbs Road (an 80-foot right-of-way), for the east corner of said Lot 24,

THENCE along the northerly right-of-way of said Tubbs Road, the following courses and distances:

South 54° 35' 45" West, a distance of 186.78 feet to a chiseled "X" in concrete found for the beginning of a tangent curve to the left;

In a southwesterly direction along said curve to the left whose chord bears South 49° 25' 46" West a distance of 187.74 feet, having a radius of 1042.50, a central angle of 10° 19' 56", passing a chiseled "X" in concrete found at an arc length of 119.90 feet, continuing along said curve to a chiseled "X" in concrete found for a total arc length of 187.99 feet to an exterior ell corner of Lot 24 and the east corner of Lot 7, Block A, of said Presbyterian Hospital of Rockwall Addition (Cabinet G, Slide 43);

THENCE departing the northerly right-of-way line of said Tubbs Road and along a southeasterly line of said Lot 24, the following courses and distances:

North 46° 43' 37" West, along the northeasterly line of said Lot 7, a distance of 210.30 feet to a 5/8" iron rod found for corner;

South 88° 16' 25" West, along the north line of said Lot 7, a distance of 28.48 feet to a 1/2" iron rod found for the beginning of a non-tangent curve to the left;

In a southwesterly direction along the northwesterly line of said Lot 7 and said curve to the left whose chord bears South 41° 05' 32" West a distance of 113.78 feet, having a radius of 1411.52 feet, a central angle of 04° 17' 11", and an arc length of 113.81 feet a 1/2" iron rod with yellow plastic cap stamped "RLG INC" found for a southeasterly corner of said Lot 24 and the west corner of said Lot 7;

THENCE South 47° 48' 26" East, along the common line between said Lot 7 and said Lot 24, a distance of 231.97 feet to a chiseled "X" in concrete found on the northerly right-of-way line of said Tubbs Road, for the east corner of said Lot 24 and the south corner of said Lot 7, and for the beginning of a non-tangent curve to the left;

THENCE along the northerly right-of-way line of said Tubbs Road, the following courses and distances:

In a southwesterly direction along said non-tangent curve to the left whose chord bears South 33° 01' 52" West a distance of 149.25 feet, having a radius of 1042.50 feet, a central angle of 08° 12' 36", passing at an arc length of 116.47 feet a chiseled "X" in concrete found for a south corner of said Lot 24, and continuing along said curve for a total arc length of 149.38 feet to a chiseled "X" in concrete found for a southeasterly corner of said Lot 24 and the end of said non-tangent curve to the left;

South 28° 55' 34" West, a distance of 94.93 feet to a chiseled "X" in concrete found at the intersection of the northerly right-of-way line of said Tubbs Road and the northeasterly right-of-way line of Summer Lee Drive (a 60-foot right-of-way), for the south corner of said Lot 24;

THENCE along the northeasterly right-of-way line of said Summer Lee Drive, the following courses and distances:

North 62° 45' 02" West, passing at a distance of 234.77 feet a chiseled "X" in concrete found for a south corner of said Lot 24, continuing for a total distance of 411.89 feet to a 1/2" iron rod with yellow plastic cap stamped "RLG INC" found for the beginning of a non-tangent curve to the right;

In a northwesterly direction along said curve to the right whose chord bears North 59° 39' 53" West a distance of 88.82 feet, having a radius of 825.00 feet, a central angle of 06° 10' 17" and an arc length of 88.86 feet to a 1/2" iron rod with yellow plastic cap stamped "RLG INC" found for the end of said curve to the right;

North 56° 34' 45" West, passing at a distance of 524.21 feet a 1/2" iron rod with yellow plastic cap stamped "RLG INC" found and continuing for a total distance of 772.12 feet to a 1/2" iron rod with yellow plastic cap stamped "RLG INC" found for the west corner of said Lot 24;

THENCE North 33° 25' 38" East, departing the northeasterly right-of-way line of said Summer Lee Drive and along the common line between said Lot 12 and said Lot 24, passing at a distance of 169.05 feet a 1/2" iron rod with yellow plastic cap stamped "RLG INC" found and continuing for a total distance of 200.00 feet to a chiseled "X" in concrete found for the east corner of said Lot 9, Block A, Horizon Ridge Center, and an interior ell corner of said Lot 24;

THENCE North 56° 34' 45" West, along the common line between said Lot 24 and said Lot 9, Block A, of said Horizon Ridge Center, a distance of 270.62 feet to the **POINT OF BEGINNING**, containing 1,005,917 square feet or 23.0927 acres, more or less.

FINAL PLAT
OF
**PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION
LOT 25, BLOCK A
BEING A REPLAT
OF
PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION
LOT 24, BLOCK A
TOTAL 23.0927 ACRES**

EDWARD TEAL SURVEY, ABSTRACT NO. 207
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS

SCALE: 1" = 40'

DATE: 01-15-2021

SURVEYOR:

RAYMOND L. GOODSON JR., INC.
12001 N. CENTRAL EXPRESSWAY, STE 300
DALLAS, TX 75243
214-739-8100
rlg@rlginc.com
TX PE REG #P-493
TBPELS REG #100341-00

CASE NUMBER:

SHEET 6 OF 7

OWNER:

TEXAS HEALTH RESOURCES
9330 AMBERTON PKWY., SUITE #1000
DALLAS, TX 75243
PHONE NUMBER
C/O CINDY PERRIN

RECORDED	INST#	-	JOB NO.	1913.017	E-FILE	1913.017RP	DWG NO.	27,503Z
----------	-------	---	---------	----------	--------	------------	---------	---------

STATE OF TEXAS
COUNTY OF ROCKWALL

I (we) the undersigned owner(s) of the land shown on this plat, and designated herein as the **PRESBYTERIAN HOSPITAL OF ROCKWALL ADDITION** subdivision to the City of Rockwall, Texas, and whose name is subscribed hereto, hereby dedicate to the use of the public forever all streets, alleys, parks, water courses, drains, easements and public places thereon shown on the purpose and consideration therein expressed. I (we) further certify that all other parties who have a mortgage or lien interest in the **PRESBYTERIAN HOSPITAL OF ROCKWALL ADDITION** subdivision have been notified and signed this plat. I (we) understand and do hereby reserve the easement strips shown on this plat for the purposes stated and for the mutual use and accommodation of all utilities desiring to use or using same. I (we) also understand the following:

1. No buildings shall be constructed or placed upon, over, or across the utility easements as described herein.
2. Any public utility shall have the right to remove and keep removed all or part of any buildings, fences, trees, shrubs, or other growths or improvements which in any way endanger or interfere with construction, maintenance or efficiency of their respective system on any of these easement strips; and any public utility shall at all times have the right of ingress or egress to, from and upon the said easement strips for purpose of construction, reconstruction, inspecting, patrolling, maintaining, and either adding to or removing all or part of their respective system without the necessity of, at any time, procuring the permission of anyone.
3. The City of Rockwall will not be responsible for any claims of any nature resulting from or occasioned by the establishment of grade of streets in the subdivision.
4. The developer and subdivision engineer shall bear total responsibility for storm drain improvements.
5. The developer shall be responsible for the necessary facilities to provide drainage patterns and drainage controls such that properties within the drainage area are not adversely affected by storm drainage from the development.
6. No house dwelling unit, or other structure shall be constructed on any lot in this addition by the owner or any other person until the developer and/or owner has complied with all requirements of the Subdivision Regulations of the City of Rockwall regarding improvements with respect to the entire block on the street or streets on which property abuts, including the actual installation of streets with the required base and paving, curb and gutter, water and sewer, drainage structures, storm structures, storm sewers, and alleys, all according to the specifications of the City of Rockwall; or
7. Property owner shall be responsible for maintaining, repairing, and replacing all systems within the drainage and detention easements.

Until an escrow deposit, sufficient to pay for the cost of such improvements, as determined by the city's engineer and/or city administrator, computed on a private commercial rate basis, has been made with the city secretary, accompanied by an agreement signed by the developer and/or owner, authorizing the city to make such improvements at prevailing private commercial rates, or have the same made by a contractor and pay for the same out of the escrow deposit, should the developer and/or owner fail or refuse to install the required improvements within the time stated in such written agreement, but in no case shall the City be obligated to make such improvements itself. Such deposit may be used by the owner and/or developer as progress payments as the work progresses in making such improvements by making certified requisitions to the city secretary, supported by evidence of work done; or

Until the developer and/or owner files a corporate surety bond with the city secretary in a sum equal to the cost of such improvements for the designated area, guaranteeing the installation thereof within the time stated in the bond, which time shall be fixed by the city council of the City of Rockwall.

I (we) further acknowledge that the dedications and/or exaction's made herein are proportional to the impact of the Subdivision upon the public services required in order that the development will comport with the present and future growth needs of the City; I (we), my (our) successors and assigns hereby waive any claim, damage, or cause of action that I (we) may have as a result of the dedication of exactions made herein.

Property Owner Signature

STATE OF TEXAS
COUNTY OF ROCKWALL

Before me, the undersigned authority, on this day personally appeared **ROCKWALL REGIONAL HOSPITAL, LLC**, known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that he executed the same for the purpose and consideration therein stated.

Given upon my hand and seal of office this _____ day of _____, _____.

Notary Public in and for the State of Texas

My Commission Expires

SURVEYOR'S CERTIFICATE

NOW, THEREFORE KNOW ALL MEN BY THESE PRESENTS:

THAT I, Brian R. Wade, do hereby certify that I prepared this plat from an actual and accurate survey of the land, and that the corner monuments shown thereon were properly placed under my personal supervision.

PRELIMINARY, THIS DOCUMENT SHALL NOT BE RECORDED FOR ANY PURPOSE AND SHALL NOT BE USED OR VIEWED OR RELIED UPON AS A FINAL SURVEY DOCUMENT.

BRIAN R. WADE, RPLS NO. 6098

STATE OF TEXAS
COUNTY OF ROCKWALL

Before me, the undersigned authority, on this day personally appeared **ROCKWALL REGIONAL HOSPITAL, LLC**, known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that he executed the same for the purpose and consideration therein stated.

Given upon my hand and seal of office this _____ day of _____, _____.

Notary Public in and for the State of Texas

My Commission Expires

APPROVED:

I hereby certify that the above and foregoing plat of an addition to the City of Rockwall, Texas, was approved by the City Council of the City of Rockwall on the _____ day of _____, _____.

This approval shall be invalid unless the approved plat for such addition is recorded in the office of the County Clerk of Rockwall, County, Texas, within one hundred eighty (180) days from said date of final approval.

WITNESS OUR HANDS:

Mayor, City of Rockwall

DATE

City Secretary

DATE

City Engineer

DATE

Planning & Zoning Commission, Chairman

Date

FINAL PLAT
OF
PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION
LOT 25, BLOCK A
BEING A REPLAT
OF
PRESBYTERIAN HOSPITAL
OF ROCKWALL ADDITION
LOT 24, BLOCK A
TOTAL 23.0927 ACRES

EDWARD TEAL SURVEY, ABSTRACT NO. 207
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS

SCALE: 1" = 40'

DATE: 01-15-2021

OWNER:
TEXAS HEALTH RESOURCES
9330 AMBERTON PKWY., SUITE #1000
DALLAS, TX 75243
PHONE NUMBER
C/O CINDY PERRIN

SURVEYOR:
RAYMOND L. GOODSON JR., INC.
12001 N. CENTRAL EXPRESSWAY, STE 300
DALLAS, TX 75243
214-739-8100
rlg@rlginc.com
TX PE REG #F-493
TBPELS REG #100341-00

CASE NUMBER:

SHEET 7 OF 7

RECORDED	INST#	-	JOB NO.	1913.017	E-FILE	1913.017RP	DWG NO.	27,503Z
----------	-------	---	---------	----------	--------	------------	---------	---------