



DEVELOPMENT APPLICATION

City of Rockwall
Planning and Zoning Department
385 S. Goliad Street
Rockwall, Texas 75087

STAFF USE ONLY

PLANNING & ZONING CASE NO. _____

NOTE: THE APPLICATION IS NOT CONSIDERED ACCEPTED BY THE CITY UNTIL THE PLANNING DIRECTOR AND CITY ENGINEER HAVE SIGNED BELOW.

DIRECTOR OF PLANNING: _____

CITY ENGINEER: _____

PLEASE CHECK THE APPROPRIATE BOX BELOW TO INDICATE THE TYPE OF DEVELOPMENT REQUEST [SELECT ONLY ONE BOX]:

PLATTING APPLICATION FEES:

- ☐ MASTER PLAT (\$100.00 + \$15.00 ACRE) ¹
- ☐ PRELIMINARY PLAT (\$200.00 + \$15.00 ACRE) ¹
- ☒ FINAL PLAT (\$300.00 + \$20.00 ACRE) ¹
- ☐ REPLAT (\$300.00 + \$20.00 ACRE) ¹
- ☐ AMENDING OR MINOR PLAT (\$150.00)
- ☐ PLAT REINSTATEMENT REQUEST (\$100.00)

SITE PLAN APPLICATION FEES:

- ☐ SITE PLAN (\$250.00 + \$20.00 ACRE) ¹
- ☐ AMENDED SITE PLAN/ELEVATIONS/LANDSCAPING PLAN (\$100.00)

ZONING APPLICATION FEES:

- ☐ ZONING CHANGE (\$200.00 + \$15.00 ACRE) ¹
- ☐ SPECIFIC USE PERMIT (\$200.00 + \$15.00 ACRE) ^{1 & 2}
- ☐ PD DEVELOPMENT PLANS (\$200.00 + \$15.00 ACRE) ¹

OTHER APPLICATION FEES:

- ☐ TREE REMOVAL (\$75.00)
- ☐ VARIANCE REQUEST/SPECIAL EXCEPTIONS (\$100.00) ²

NOTES:

¹: IN DETERMINING THE FEE, PLEASE USE THE EXACT ACREAGE WHEN MULTIPLYING BY THE PER ACRE AMOUNT. FOR REQUESTS ON LESS THAN ONE ACRE, ROUND UP TO ONE (1) ACRE.

²: A \$1,000.00 FEE WILL BE ADDED TO THE APPLICATION FEE FOR ANY REQUEST THAT INVOLVES CONSTRUCTION WITHOUT OR NOT IN COMPLIANCE TO AN APPROVED BUILDING PERMIT.

PROPERTY INFORMATION [PLEASE PRINT]

ADDRESS _____

SUBDIVISION

Quail Hollow Phase 2

LOT _____

BLOCK _____

GENERAL LOCATION

Northeast corner of said Hays Lane and Quail Run Road

ZONING, SITE PLAN AND PLATTING INFORMATION [PLEASE PRINT]

CURRENT ZONING _____

CURRENT USE _____

PROPOSED ZONING _____

PROPOSED USE _____

ACREAGE

42.742

LOTS [CURRENT] _____

LOTS [PROPOSED] _____

111

- ☐ **SITE PLANS AND PLATS:** BY CHECKING THIS BOX YOU ACKNOWLEDGE THAT DUE TO THE PASSAGE OF HB3167 THE CITY NO LONGER HAS FLEXIBILITY WITH REGARD TO ITS APPROVAL PROCESS, AND FAILURE TO ADDRESS ANY OF STAFF'S COMMENTS BY THE DATE PROVIDED ON THE DEVELOPMENT CALENDAR WILL RESULT IN THE DENIAL OF YOUR CASE.

OWNER/APPLICANT/AGENT INFORMATION [PLEASE PRINT/CHECK THE PRIMARY CONTACT/ORIGINAL SIGNATURES ARE REQUIRED]

☐ OWNER

Quail Hollow SF, LTD.

☐ APPLICANT

Corwin Engineering, Inc.

CONTACT PERSON

John Arnold

CONTACT PERSON

Chase Finch

ADDRESS

8214 Westchester Dr. Ste. 900

ADDRESS

200 W. Belmont, Ste. E

CITY, STATE & ZIP

Dallas, Tx 75202

CITY, STATE & ZIP

Allen, Texas 75013

PHONE

214-522-4945

PHONE

972-396-1200

E-MAIL

jarnold@skorburgcompany.com

E-MAIL

cfinch@corwinengineering.com

NOTARY VERIFICATION [REQUIRED]


BEFORE ME, THE UNDERSIGNED AUTHORITY, ON THIS DAY PERSONALLY APPEARED John Arnold [OWNER] THE UNDERSIGNED, WHO STATED THE INFORMATION ON THIS APPLICATION TO BE TRUE AND CERTIFIED THE FOLLOWING:

"I HEREBY CERTIFY THAT I AM THE OWNER FOR THE PURPOSE OF THIS APPLICATION; ALL INFORMATION SUBMITTED HEREIN IS TRUE AND CORRECT; AND THE APPLICATION FEE OF \$ 1,154.80 TO COVER THE COST OF THIS APPLICATION, HAS BEEN PAID TO THE CITY OF ROCKWALL ON THIS THE 11th DAY OF March, 2025. BY SIGNING THIS APPLICATION, I AGREE THAT THE CITY OF ROCKWALL (I.E. "CITY") IS AUTHORIZED AND PERMITTED TO PROVIDE INFORMATION CONTAINED WITHIN THIS APPLICATION TO THE PUBLIC. THE CITY IS ALSO AUTHORIZED AND PERMITTED TO REPRODUCE ANY COPYRIGHTED INFORMATION SUBMITTED IN CONJUNCTION WITH THIS APPLICATION, IF SUCH REPRODUCTION IS ASSOCIATED OR IN RESPONSE TO A REQUEST FOR PUBLIC INFORMATION."


GIVEN UNDER MY HAND AND SEAL OF OFFICE ON THIS THE 11th DAY OF March, 2025.

OWNER'S SIGNATURE

NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS



MY COMMISSION EXPIRES 2/1/2028




City of Rockwall

Planning & Zoning Department
385 S. Goliad Street
Rockwall, Texas 75087
(P): (972) 771-7745
(W): www.rockwall.com


The City of Rockwall GIS maps are continually under development and therefore subject to change without notice. While we endeavor to provide timely and accurate information, we make no guarantees. The City of Rockwall makes no warranty, express or implied, including warranties of merchantability and fitness for a particular purpose. Use of the information is the sole responsibility of the user.





NOTES

1. Bearings are referenced to a 85.7256 acre tract, as recorded in Deed No. 20220000023672 in the Deed Records of Rockwall County, Texas.
2. All lot lines are radial or perpendicular to the street unless otherwise noted by bearing.
3. 1/2" iron rods with "CORWIN ENGR. INC." caps set at all boundary corners, block corners, points of curvature, points of tangency, and angle points in public right-of-way unless otherwise noted.
4. Building Line.
C.C.M. - Controlling Monument.
D.E. - Drainage Easement.
S.E. - Sanitary Easement.
F.E. - Farmers Electric Easement.
5. The HOA will be responsible for maintaining repairing or replacing the open space/drainage easement lots, open space lots, and open space/sidewalk lots.
6. All non-standard decorative street signs, light poles/post, hardware, attachments, foundations, etc. shall be owned, maintained, repaired and replaced by the HOA.
7. All landscape, drainage and detention easements are to be owned, maintained, repaired and replaced by the Homeowners Association.




OWNER
QUAIL HOLLOW SF, LTD.
8214 WESTCHESTER DRIVE, SUITE 900
DALLAS, TEXAS 75225
214-522-4945
SHEET 1 OF 2
MASTER PLAT P2022-53
PRE PLAT P2022-37
CASE NO. P2024-xxx

FINAL PLAT
OF
QUAIL HOLLOW PHASE II
111 LOTS, BEING 42.742 ACRES
BEING A REPLAT OF
LOT 20 BLOCK G
QUAIL HOLLOW PHASE I
OUT OF THE
P. BRUCE HARRISON SURVEY, ABSTRACT NO. 97
IN THE
CITY OF ROCKWALL
ROCKWALL COUNTY, TEXAS
PREPARED BY
CORWIN ENGINEERING, INC.
TBPELS #10031700
200 W. BELMONT, SUITE E
ALLEN, TEXAS 75013
972-396-1200

MARCH 2025 SCALE 1" = 100'

THE PURPOSE OF THE REPLAT IS TO
SUBDIVIDE LOT 20 BLOCK G ALSO TO
RENUMBER THE OPEN SPACE OF LOT 1
BLOCK A TO LOT 31 BLOCK A.

| CITY OF ROCKWALL GRID SYSTEM COORDINATES | |
|---|-------------|
| X | Y |
| 2596531.062 | 7036252.063 |
| ELEV = 546.2 | |



| CITY OF ROCKWALL GRID SYSTEM COORDINATES | |
|---|-------------|
| X | Y |
| 2598383.557 | 7035113.399 |
| ELEV = 525.0 | |

OW, THEREFORE, KNOW ALL MEN BY THESE PRESENTS:
STATE OF TEXAS
COUNTY OF ROCKWALL
I(we) the undersigned owner(s) of the land shown on this plat, and designated herein as the QUAL HOLLOW PHASE II subdivision to the City of Rockwall, Texas, and whose name is subscribed hereto, hereby dedicate to the use of the public forever all streets, alleys, parks, water courses, drains, easements and public places thereon shown on the purpose and consideration therein expressed. I (we) further certify that all other parties who have a mortgage or lien interest in the QUAL HOLLOW PHASE II subdivision have been notified and signed this plat.

I(we) understand and do hereby reserve the easement strips shown on this plat for the purposes stated and for the mutual use and accommodation of all utilities desiring to use or using same. I (we) also understand the following:

1. No buildings shall be constructed or placed upon, over, or across the utility easements as described herein.
2. Any public utility shall have the right to remove and keep removed all or part of any buildings, fences, trees, shrubs, or other growths or improvements which in any way endanger or interfere with construction, maintenance or efficiency of their respective system on any of these easement strips; and any public utility shall at all times have the right of ingress or egress to, from and upon the said easement strips for purpose of construction, reconstruction, inspecting, patrolling, maintaining, and either adding to or removing all or part of their respective system without the necessity of, at any time, procuring the permission of anyone.
3. The City of Rockwall will not be responsible for any claims of any nature resulting from or occasioned by the establishment of grade of streets in the subdivision.
4. The developer/property owner and subdivision engineer shall bear total responsibility for storm drain improvements.
5. The developer/property owner shall be responsible for the necessary facilities to provide drainage patterns and drainage controls such that properties within the drainage area are not adversely affected by storm drainage from the development.
6. No house dwelling unit, or other structure shall be constructed on any lot in this addition by the owner or any other person until the developer and/or owner has complied with all requirements of the Subdivision Regulations of the City of Rockwall regarding improvements with respect to the entire block on the street or streets on which property abuts, including the actual installation of streets with the required base and paving, curb and gutter, water and sewer, drainage structures, storm structures, storm sewers, and alleys, all according to the specifications of the City of Rockwall; or Utilian escrow deposit, sufficient to pay for the cost of such improvements, as determined by the city's engineer and/or city administrator computed on a private commercial rate basis, has been made with the city secretary, accompanied by an agreement signed by the developer and/or owner, authorizing the city to make such improvements at prevailing private commercial rates, or have the same made by a contractor and pay for the same out of the escrow deposit, should the developer and/or owner fail or refuse to install the required improvements within the time stated in such written agreement, but in no case shall the City be obligated to make such improvements itself. Such deposit may be used by the owner and/or developer as progress payments as the work progresses in making such improvements by making certified requisitions to the city secretary, supported by evidence of work done; or until the developer and/or owner files a corporate surety bond with the city secretary in a sum equal to the cost of such improvements for the designated area, guaranteeing the installation thereof within the time stated in the bond, which time shall be fixed by the city council of the City of Rockwall.

I(we) further acknowledge that the dedications and/or exaction's made herein are proportional to the impact of the Subdivision upon the public services required in order that the development will comport with the present and future growth needs of the City: I(we), my (our) successors and assigns hereby waive any claim, damage, or cause of action that I(we) may have as a result of the dedication of exactions made herein.

QUAIL HOLLOW SF, LTD.
a Texas limited partnership
By: QUAIL HOLLOW SF GP Corporation,
a Texas corporation, its General Partner

John Arnold
Director

STATE OF TEXAS
COUNTY OF DALLAS
Before me, the undersigned authority, on this day personally appeared JOHN ARNOLD, known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that he executed the same for the purpose and consideration therein stated. Given upon my hand and seal of office this _____ day of _____, 2025.

Notary Public in and for the State of Texas My Commission Expires: _____

LINE TABLE

| LINE NO. | BEARING | DISTANCE |
|----------|---------------|----------|
| 1. | N 89°24'45" E | 30.00' |
| 2. | S 72°06'15" E | 62.50' |
| 3. | S 61°44'56" E | 66.60' |
| 4. | N 15°19'00" W | 13.78' |
| 5. | N 87°59'25" E | 14.35' |
| 6. | N 42°08'56" W | 13.14' |
| 7. | S 01°54'51" W | 13.92' |
| 8. | S 45°35'15" E | 14.14' |
| 9. | S 44°24'45" W | 14.14' |
| 10. | S 89°24'45" W | 40.50' |
| 11. | N 55°43'21" E | 18.03' |
| 12. | S 62°47'54" E | 38.18' |
| 13. | S 27°30'38" E | 14.24' |
| 14. | N 62°24'51" E | 14.02' |
| 15. | S 17°53'45" W | 25.00' |
| 16. | S 88°52'46" E | 14.59' |
| 17. | S 02°51'04" W | 14.14' |
| 18. | S 87°08'56" E | 35.36' |
| 19. | N 02°29'36" E | 35.58' |
| 20. | S 01°03'01" E | 33.18' |
| 21. | S 89°38'33" E | 37.00' |
| 22. | S 05°51'22" W | 33.15' |
| 23. | S 81°00'26" E | 38.85' |
| 24. | N 43°37'45" E | 14.11' |
| 25. | N 46°22'15" W | 21.26' |
| 26. | S 84°29'46" E | 33.83' |
| 27. | N 42°08'56" W | 44.02' |
| 28. | S 04°36'08" W | 36.49' |

CURVE TABLE

| CURVE NO. | DELTA | RADIUS | LENGTH | CHORD | BEARING |
|-----------|------------|----------|---------|---------|-------------|
| 1. | 18°29'00" | 820.00' | 264.53' | 263.38' | S81°20'45"E |
| 2. | 10°21'35" | 225.00' | 40.68' | 40.63' | S66°55'44"E |
| 3. | 02°21'04" | 650.00' | 26.67' | 26.67' | S31°37'51"W |
| 4. | 17°18'27" | 625.00' | 188.80' | 188.08' | S39°11'50"W |
| 5. | 29°57'19" | 545.00' | 284.93' | 281.70' | N57°07'36"W |
| 6. | 18°29'00" | 670.00' | 216.14' | 215.20' | N81°20'45"W |
| 7. | 18°29'00" | 520.00' | 167.75' | 167.02' | S81°20'45"E |
| 8. | 18°29'00" | 375.00' | 120.97' | 120.45' | S81°20'45"E |
| 9. | 172°26'34" | 50.00' | 150.48' | 99.78' | S49°56'21"E |
| 10. | 178°51'14" | 50.00' | 158.08' | 99.99' | N44°24'45"E |
| 11. | 18°29'00" | 325.00' | 104.84' | 104.39' | S08°39'15"W |
| 12. | 26°46'57" | 395.00' | 184.64' | 182.96' | S58°42'46"E |
| 13. | 29°57'19" | 250.00' | 130.70' | 129.22' | S57°07'36"E |
| 14. | 31°40'18" | 1000.00' | 552.78' | 545.77' | N72°55'05"E |
| 15. | 09°13'53" | 1000.00' | 161.12' | 160.94' | N52°28'00"E |
| 16. | 59°45'49" | 300.00' | 312.92' | 298.93' | S61°21'51"E |
| 17. | 37°13'38" | 255.00' | 165.68' | 162.78' | N72°37'56"W |
| 18. | 49°05'49" | 150.00' | 128.54' | 124.64' | S66°41'51"E |
| 19. | 163°59'22" | 50.00' | 143.10' | 99.03' | N43°37'45"E |
| 20. | 40°39'12" | 150.00' | 106.43' | 104.21' | S21°49'20"E |
| 21. | 36°09'50" | 300.00' | 189.35' | 186.23' | S19°34'39"E |
| 22. | 18°29'00" | 180.00' | 58.07' | 57.82' | N08°39'15"E |
| 23. | 01°27'19" | 932.50' | 23.68' | 23.68' | N88°01'35"E |

LEGAL DESCRIPTION

BEING, a tract of land situated in the P. Bruce Harrison Survey, Abstract No. 97 in the City of Rockwall, Rockwall County, Texas, being all of Lot 20 Block G out of Quail Hollow Phase I, an addition to the City of Rockwall, as described in Clerks File No. 20240000003859 in the Plat Records of Rockwall County, Texas being more particularly described as follows:

BEGINNING, at an "X" cut found at the southeast corner of Lot 20 Block G and being the southwest corner of Gideon Grove Phase 2, an addition to the City of Rockwall, as described in Doc. No. 20220000006324 in said Plat Records and being in Quail Run Road (Variable R.O.W.), same being in the north line of L.L. Leonard Addition, an addition to the City of Rockwall, as described in Cab. A, Pg. 336 in said Plat Records:

THENCE, South 88°45'15" West, along the south line of Lot 20 Block G and with said Quail Run Road and along the north line of said L.L. Leonard Addition, at 437.57, passing a 5/8 inch iron rod found with cap stamped "RPLS 3963", an continuing along said south line, for a total distance of 1835.99 feet, to an "X" cut found at the southwest corner of said Lot 20 Block G and being the southeast corner of Stone Creek Phase VIII, an addition to the City of Rockwall, an addition to the City of Rockwall, as described in Doc. No. 20190000004513 in said Plat Records:

THENCE, North 00°35'15" West, along the west line of said Lot 20 Block G and the east line of said Stone Creek Phase VIII, for a distance of 1172.61 feet, to an "X" cut found at the northwest corner of said Lot 20 Block G;

THENCE, North 89°24'45" West, departing said east and west lines and along the north line of said Lot 20 Block G, for a distance of 30.00 feet, to a 1/2 inch iron rod found in the east line Hays Lane (60' R.O.W.):

THENCE, North 00°35'15" West, along the east line of said Hays Lane, for a distance of 113.00 feet, to a 1/2 inch iron rod found:

THENCE, North 44°24'45" East, departing said Hays Lane, for a distance of 35.36 feet, to a 1/2 inch iron rod found in the south line of Montrose Drive (50' R.O.W.):

THENCE, South 00°35'15" East, departing said south line, for a distance of 138.00 feet, to a 1/2 inch iron rod found at the southwest corner of Lot 2 Block A out of said Quail Hollow Phase I and being in the north line of said Lot 20 Block G:

THENCE, North 89°24'45" East, along said north line, for a distance of 175.00 feet, to a 1/2 inch iron rod found:

THENCE, North 00°35'15" West, along said north line, for a distance of 18.00 feet, to a 1/2 inch iron rod found:

THENCE, North 89°24'45" East, continuing along said north line, for a distance of 55.45 feet, to a 1/2 inch iron rod found at the point of curvature of a curve to the right, having a radius of 820.00 feet, a central angle of 18°29'00";

THENCE, continuing along said north line and with said curve to the left for an arc distance of 264.53 feet (Chord Bearing South 81°20'45" East - 263.38 feet), to a 1/2 inch iron rod found at the point of tangency:

THENCE, South 72°06'15" East, continuing along said north line, for a distance of 906.83 feet, to a 1/2 inch iron rod found:

THENCE, North 17°53'45" East, continuing along said north line, for a distance of 120.00 feet, to a 1/2 inch iron rod found:

THENCE, South 72°06'15" East, continuing along said north line, for a distance of 62.50 feet, to a 1/2 inch iron rod found at the point of curvature of a curve to the right, having a radius of 225.00 feet, a central angle 10°21'35";

THENCE, continuing along said north line and with said curve to the right for an arc distance of 40.68 feet (Chord Bearing South 66°55'44" East - 40.63 feet), to a 1/2 inch iron rod found at the point of tangency:

THENCE, South 61°44'56" East, continuing along said north line, for a distance of 66.60 feet, to a 1/2 inch iron rod found on a non-tangent curve to the right, having a radius of 650.00 feet, a central angle of 02°21'04";

THENCE, continuing along said north line and with said curve to the right for an arc distance of 26.67 feet (Chord Bearing South 31°37'51" West - 26.67 feet), to a 1/2 inch iron rod found:

THENCE, South 57°11'37" East, continuing along said north line, for a distance of 178.39 feet, to a 1/2 inch iron rod found:

THENCE, North 47°51'04" East, continuing along said north line, for a distance of 119.53 feet, to a 1/2 inch iron rod found at the northeast corner of said Lot 20 Block G and being in the west line of said Gideon Grove Phase 2:

THENCE, South 01°29'44" East, along the east line of Lot 20 Block G and the west line of said Gideon Grove Phase 2, for a distance of 843.94 feet, to the POINT OF BEGINNING and containing 42.742 acres of land.

Recommended for Final Approval:

Planning & Zoning Commission

Date

APPROVED
I hereby certify that the above and foregoing plat of an addition to the City of Rockwall, Texas, was approved by the City Council of the City of Rockwall on the _____ day of _____, 2025.

This approval shall be invalid unless the approved plat for such addition is recorded in the office of the Court Clerk of Rockwall, County, Texas, within one hundred eighty (180) days from said date of final approval.

WITNESS OUR HANDS, this _____ day of _____, 2025.

Mayor, City of Rockwall

City Secretary

City Engineer

SURVEYOR CERTIFICATE

I, WARREN L. CORWIN, do hereby certify that the plat shown hereon accurately represents the results of an on-the-ground survey made under my direction and supervision and all corners are as shown thereon and there are no encroachments, conflicts, protrusions or visible utilities on the ground except as shown and said plat has been prepared in accordance with the platting rules and regulations of the City Plan Commission of the City of Rockwall, Texas.

DATED the this _____ day of _____, 2025.

WARREN L. CORWIN
R.P.L.S. No. 4621

THE STATE OF TEXAS
COUNTY OF COLLIN

BEFORE ME, the undersigned, a Notary Public in and for the State of Texas, on this day personally appeared WARREN L. CORWIN, known to me to be the person whose name is subscribed to the foregoing instrument and acknowledged to me that he executed the same in the capacity therein stated and for the purposes and considerations therein expressed.

WITNESS MY HAND AND SEAL OF OFFICE, this the _____ day of _____, 2025.

Notary Public in and for the State of Texas

FINAL PLAT
OF

QUAIL HOLLOW PHASE II

111 LOTS, BEING 42.472 ACRES

BEING A REPLAT OF

LOT 20 BLOCK G
QUAIL HOLLOW PHASE I

OUT OF THE

P. BRUCE HARRISON SURVEY, ABSTRACT NO. 97

IN THE

CITY OF ROCKWALL
ROCKWALL COUNTY, TEXAS

OWNER

QUAIL HOLLOW SF, LTD.

8214 WESTCHESTER DRIVE, SUITE 900
DALLAS, TEXAS 75225
214-522-4945

PREPARED BY

CORWIN ENGINEERING, INC.

TBPELS #10031700

200 W. BELMONT, SUITE E
ALLEN, TEXAS 75013
972-396-1200

MARCH 2025

MASTER PLAT P2022-53
PRE PLAT P2022-37

CASE NO. P2024-XXX

SHEET 2 OF 2