

EXTERIOR FINISH SCHEDULE 1. EQUAL PRODUCTS ARE ACCPETABLE AFTER IT HAS BEEN SUBMITTED & APPROVED BY ARCHITECT. 2. ALL PRODUCTS TO BE INSTALLED PER MANUFACTURER REQUIREMENTS MATERIAL TAG SPECIFICATION / DESCRIPTION LOCATION REMARKS PROFILE: IMPERIAL MARQUEE AWNING W/8" FLAT PANELS, 3" DEEP W/ BLACK EXT. AW-1 AWNING GENERAL AWNING PER ELEVATIONS FINISH AND BLACK GUTTER DOWNSPOUT KIT PROFILE:MODULAR; COLOR: SILVER CITY WIRECUT; MORTAR COLOR: Portland EQUAL PRODUCT IS ACCEPTABLE WITH GLEN-GERY EXT. BR-1. PER ELEVATIONS BRICK ARCHITECT APPROVAL Cement & Lime Blend PROFILE: MODULAR; COLOR: VINTAGE BLACK VELOUR; MORTAR COLOR: EQUAL PRODUCT IS ACCEPTABLE WITH EXT. BR-2 BRICK GLEN-GERY PER ELEVATIONS G-602 ARCHITECT APPROVAL EQUAL PRODUCT IS ACCEPTABLE WITH EXT. C-1 COPING PAC-CLAD PROFILE: PAC TITE GOLD COPING; COLOR: BLACK ALUMINUM PER ELEVATIONS ARCHITECT APPROVAL PROFILE: ALUMINUM SLAT WALL STYLE COVRIT TOUGHGATE, 96" W X 72" H., EXT. MG-1 METAL GATE CITYSCAPE PER ELEVATIONS PROVIDE SELF-LATCHING HARDWARE MFG STD COLOR PLANKS, MFG COLOR FRAME; COLOR: BLACK EXT. R-1 TPO ROOFING FIRESTONE PROFILE: FIRESTONE TPO SELF-ADHERED MEMBRANE: FINISH COLOR: WHITE AT ROOF PROFILE: HOLLOW METAL 2"X5" RECTANGULAR; FINISH: BLACK ALUMIMUN: EXT. SFD-1 STORE FRONT DOOR AMC PER ELEVATIONS GLASS FINISH: SOLAR CONTROL GREY PROFILE: URBAN LEDGESTONE STEEL GREY; SHA/UL22: 2-5/16" H x 23-5/8" L x EQUAL PRODUCT IS ACCEPTABLE WITH 3-5/8" (±1/4") D; COLOR MORTAR: GLEN-GERY - PORLAND CEMENT & LIME EXT. ST-1 STONE ARRISCRAFT PER ELEVATIONS ARCHITECT APPROVAL BLEND PROFILE: HOLLOW METAL 2"X5" RECTANGULAR; FINISH: BLACK ALUMIMUN: AMC EXT. STF-1 STORE FRONT PER ELEVATIONS GLASS FINISH: SOLAR CONTROL GREY

EXTERIOR LIGHT FIXTURE SCHEDULE										
TAG	DESCRIPTION	MANUFACTURER	MODEL	LAMP	WATTAGE	COLOR TEMPERATURE	QTY	IMAGE	REMARKS	LOCATION
EXT. LT-1	EXTERIOR SCONCE	AVENUE LIGHTING	AVENUE SQUARE; AV9900-BLK; 12" HEIGHT; FINISH: BLACK SIZE: 7"W x 12"H x 3.75"D. 12 WATTS; 357 LUMENS LABEL: DAMP LOCATION	2 x LED/6W/120V LED	12 W	3000K	8			EXTERIOR
EXT. LT-2	EXTERIOR STREET LIGHT	CREE LIGHTING	QSQ SERIES; OSQM-B-11L-40K7-4M-U-OSQ-BLSMF; FINISH: BLACK	LED	144 W	4000K	2	F		EXTERIOR PARKING LOT
EXT. LT-3	EXTERIOR STREET LIGHT	CREE LIGHTING	QSQ SERIES; OSQM-B-16L-40K7-4M-UxOSQ-BLSMF; FINISH: BLACK	LED	520 W	4000K	5	F		EXTERIOR PARKING LOT
EXT. LT-4	EXTERIOR WALL PACK	CREE LIGHTING	XSP SERIES; XSPW-B-WM-3ME-4L-40K-UL; FINISH: BLACK	LED	63 W	4000K	2			EXTERIOR

SUBCONTRACTOR NOTES

A. PROVIDE WEATHER BARRIER OVER ALL EXTERIOR SHEATHING PRIOR TO THE INSTALLATION OF ANY EXTERIOR FINISH MATERIAL.

B. INSTALL PER MANUFACTURER'S SPECIFICATIONS AND PROVIDE ALL MANUFACTURER'S ACCESSORIES TO FULLY FLASH AND COUNTER-FLASH AT ALL WINDOWS, DOORS, AND EXTERIOR PENETRATIONS.

C. PROVIDE A WEATHER TIGHT BARRIER AT ALL SURFACES.

D. COORDINATE FLASHING WITH WINDOW, DOOR, VENT, ETC. MANUFACTURER'S FOR A WEATHER TIGHT SEAL AT ALL OPENINGS. E. TAPE FLASH AROUND ALL OPENINGS AND ON

REQUIREMENTS.

WALL JOINTS PER MANUFACTURER

9550 W.Higgins Rd. 170 Rosemont, IL 60018

DR. CAPPS, DR. HODGES & DR. MORGAN CHM REAL ESTATE, LLC 1200 SUMMER LEE DR. ROCKWALL, TX 75032

LOT 5, BLOCK B HORIZON RIDGE ADDITION

SITE DA	TA TABLE	
SITE AREA	1.253 AC (54,583 SF)	
LEGAL DESCRIPTION	LOT 5, BLOCK B HORIZON RIDGE ADDITION	
EXISTING ZONING	PLANNED DEVELOPMENT (PD-9)	
PROPOSED USE	MEDICAL OFFICE BUILDING	
PROPOSED BUILDING AREA	11,250 SF	
PROPOSED BUILDING HEIGHT	18' - 00"	
LOT COVERAGE	20.61%	SEAL:
FLOOR AREA RATIO	0.20 : 1	
PERVIOUS AREA	12,233 SF	
IMPERVIOUS AREA	42,350 SF	
PERCENT IMPERVIOUS	77.60%	DISCLAIMER: All drawings are proprietary and the exclusive property our company. This/These print(s) shall not be shared, copied or reproduced without expressed permission of our company. This print loaned in confidence and subject to return upon request by our company.

No.	Description	Date
	ISSUED FOR PERMIT	XX/XX/2022
1110		

EXTERIOR SCHEDULES

10422

Project number

A1-3

As indicated

APPLICATION INFORMATION

JEFF KILBURG APEX DESIGN BUILD 9550 W HIGGINS RD, SUITE 170, ROSEMONT, IL 60018 PHONE: 847-288-0100 RAQUELLEK@APEXDESIGNBUILD.NET

OWNER INFORMATION

DR. CAPPS, DR. HODGES & DR. MORGAN CHM REAL ESTATE, LLC 740 WILFORD WAY, HEATH, TX 75032 PHONE: 972-771-9500 EMAIL: CHADJCAPPS@GMAIL.COM

SURVEYOR

WINDROSE LAND SURVEYING 220 ELM STREET, SUITE #200 LEWISVILLE, TX 75057 PH: 214.217.2544


PROJECT NAME:


CAPPS, HODGES & MORGAN


CASE NUMBER: SP2022-009.


PLAN SIGNATURE BLOCK


I HEREBY CERTIFY THAT THE ABOVE AND FOREGGING PLAN FOR A DEVELOPMENT IN THE CITY OF ROCKWALL, TEXAS, WAS APPROVED BY THE PLANNING & ZONING COMMISSION OF THE CITY OF ROCKWALL













1 GARBAGE ENCLOSURE ELEVATION - (EAST)

1/4" = 1'-0" NOTE: IF DRAWING IS PRINTED @ 11X17 SCALE TO BE REDUCED BY 50%




GARBAGE ENCLOSURE ELEVATION - (NORTH)

1/4" = 1'-0" NOTE: IF DRAWING IS PRINTED @ 11X17 SCALE TO BE REDUCED BY 50%



2 GARBAGE ENCLOSURE ELEVATION - (SOUTH)

1/4" = 1'-0" NOTE: IF DRAWING IS PRINTED @ 11X17 SCALE TO BE REDUCED BY 50%



GARBAGE ENCLOSURE ELEVATION - (WEST)

1/4" = 1'-0" NOTE: IF DRAWING IS PRINTED @ 11X17 SCALE TO BE REDUCED BY 50%

SITE DATA TABLE				
1.253 AC (54,583 SF				

LEGAL DESCRIPTION

EXISTING ZONING

SITE AREA

LOT 5, BLOCK B HORIZON RIDGE ADDITION PLANNED DEVELOPMENT (PD-9)

MEDICAL OFFICE BUILDING

PROPOSED BUILDING AREA

PROPOSED BUILDING AREA 11,250 SF
PROPOSED BUILDING HEIGHT 18' - 00"

LOT COVERAGE 20.61%

FLOOR AREA RATIO 0.20 : 1

PERVIOUS AREA 12,233 SF

IMPERVIOUS AREA 42,350 SF
PERCENT IMPERVIOUS 77.60%

DESIGN > BUILD

9550 W.Higgins Rd. 170 Rosemont, IL 60018

DR. CAPPS, DR. HODGES & DR. MORGAN CHM REAL ESTATE, LLC 1200 SUMMER LEE DR. ROCKWALL, TX 75032

LOT 5, BLOCK B HORIZON RIDGE ADDITION

SEAL:

DISCLAIMER: All drawings are proprietary and the exclusive property of our company. This/These print(s) shall not be shared, copied or reproduced without expressed permission of our company. This print is loaned in confidence and subject to return upon request by our

No.	Description	Date
-		
	Kall-Miles	

EXTERIOR ELEVATIONS

Project number 10422

A1-4.4

Scale As indicated

APPLICATION INFORMATION

JEFF KILBURG
APEX DESIGN BUILD
9550 W HIGGINS RD, SUITE 170,
ROSEMONT, IL 60018
PHONE: 847-288-0100
EMAIL:
RAQUELLEK@APEXDESIGNBUILD.NET

OWNER INFORMATION

DR. CAPPS, DR. HODGES & DR. MORGAN
CHM REAL ESTATE, LLC
740 WILFORD WAY, HEATH, TX 75032
PHONE: 972-771-9500
EMAIL: CHADJCAPPS@GMAIL.COM

SURVEYOR

WINDROSE LAND SURVEYING 220 ELM STREET, SUITE #200 LEWISVILLE, TX 75057 PH: 214.217.2544

PROJECT NAME:

CAPPS, HODGES & MORGAN

CASE NUMBER: SP2022-009.

COPYRIGHT APEX DESIGN BUILD 2022

PLAN SIGNATURE BLOCK

APPROVED:

I HEREBY CERTIFY THAT THE ABOVE AND FOREGOING PLAN FOR A DEVELOPMENT IN THE CITY OF ROCKWALL, TEXAS, WAS APPROVED BY THE PLANNING & ZONING COMMISSION OF THE CITY OF ROCKWALL ON THE 12 DAY OF April. 2022

WITNESS OUR HANDS, THIS 11 DAY OF May . 2022

PLANNING & ZONING COMMISSION, CHAIRMAN DIRECTOR OF PLANNING AND ZONING

No.	Description	Date

EXTERIOR ELEVATIONS RENDERINGS

10422

JEFF KILBURG APEX DESIGN BUILD 9550 W HIGGINS RD, SUITE 170, ROSEMONT, IL 60018

EMAIL: RAQUELLEK@APEXDESIGNBUILD.NET

DR. CAPPS, DR. HODGES & DR. MORGAN CHM REAL ESTATE, LLC 740 WILFORD WAY, HEATH, TX 75032 PHONE: 972-771-9500 EMAIL: CHADJCAPPS@GMAIL.COM

SURVEYOR

WINDROSE LAND SURVEYING 220 ELM STREET, SUITE #200 LEWISVILLE, TX 75057 PH: 214.217.2544

CAPPS, HODGES & MORGAN

CASE NUMBER: SP2022-009.



Project number

A1-4.5

6" = 1'-0" Scale APPLICATION INFORMATION

PHONE: 847-288-0100

OWNER INFORMATION

PROJECT NAME:



BUILDING ELEVATION - SUMMER LEE DR (SOUTH)



BUILDING ELEVATION - ROCKWALL PKWY (EAST)

I HEREBY CERTIFY THAT THE ABOVE AND FOREGOING PLAN FOR A DEVELOPMENT IN THE CITY OF ROCKWALL, TEXAS, WAS APPROVED BY THE PLANNING & ZONING COMMISSION OF THE CITY OF ROCKWALL

SITE AREA

LEGAL DESCRIPTION

EXISTING ZONING

PROPOSED USE

LOT COVERAGE

FLOOR AREA RATIO

IMPERVIOUS AREA

PLAN SIGNATURE BLOCK

PERCENT IMPERVIOUS

PERVIOUS AREA

PROPOSED BUILDING AREA

PROPOSED BUILDING HEIGHT 18' - 00"

ON THE 12th DAY OF April . 2002

PLANNING & ZONING COMMISSION, CHAIRMAN

SITE DATA TABLE

1.253 AC (54,583 SF)

HORIZON RIDGE ADDITION

MEDICAL OFFICE BUILDING

PLANNED DEVELOPMENT (PD-9)

LOT 5, BLOCK B

11,250 SF

20.61%

0.20:1

12,233 SF

42,350 SF

77.60%

LOT 5, BLOCK B HORIZON RIDGE ADDITION

SEAL

DISCLAIMER: All drawings are proprietary and the exclusive property of our company. This/These print(s) shall not be shared, copied or reproduced without expressed permission of our company. This print is loaned in confidence and subject to return upon request by our

No.	Description	Date
-		-
		-

EXTERIOR ELEVATIONS RENDERINGS

Project number

10422

A1-4.6

Scale 6" = 1'-0"

JEFF KILBURG

APEX DESIGN BUILD

9550 W HIGGINS RD, SUITE 170,
ROSEMONT, IL 60018
PHONE: 847-288-0100
EMAIL:
RAQUELLEK@APEXDESIGNBUILD.NET

OWNER INFORMATION

DR. CAPPS, DR. HODGES & DR. MORGAN
CHM REAL ESTATE, LLC
740 WILFORD WAY, HEATH, TX 75032
PHONE: 972-771-9500
EMAIL: CHADJCAPPS@GMAIL.COM


SURVEYOR

WINDROSE LAND SURVEYING 220 ELM STREET, SUITE #200 LEWISVILLE, TX 75057 PH: 214.217.2544

PROJECT NAME:

CAPPS, HODGES & MORGAN

CASE NUMBER: SP2022-009.



BUILDING ELEVATION - (NORTH)



BUILDING ELEVATION - (WEST)

PLAN SIGNATURE BLOCK

PERCENT IMPERVIOUS

SITE AREA

LEGAL DESCRIPTION

EXISTING ZONING

PROPOSED USE

LOT COVERAGE

PERVIOUS AREA

IMPERVIOUS AREA

FLOOR AREA RATIO

PROPOSED BUILDING AREA

PROPOSED BUILDING HEIGHT 18' - 00"

APPROVED:

HEREBY CERTIFY THAT THE ABOVE AND FOREGOING PLAN FOR A DEVELOPMENT IN THE CITY OF ROCKWALL, TEXAS, WAS APPROVED BY THE PLANNING & ZONING COMMISSION OF THE CITY OF ROCKWALL

WITNESS OUR HANDS, THIS 11th DAY OF May , 202

MING & ZONING COMMISSION, CHAIRMAN DIRECTOR

SITE DATA TABLE

1.253 AC (54,583 SF)

HORIZON RIDGE ADDITION

MEDICAL OFFICE BUILDING

PLANNED DEVELOPMENT (PD-9)

LOT 5, BLOCK B

11,250 SF

20.61%

0.20:1

12,233 SF

42,350 SF

77.60%



3D VIEW - SUMMER LEE DR & ROCKWALL PKWY



3D VIEW - ROCKWELL PWKY & NORTHEAST



3D VIEW - SUMMER LEE DR & NORTHWEST

3D VIEW - TRASH ENCLOSURE



PLAN SIGNATURE BLOCK

APPROVED:

I HEREBY CERTIFY THAT THE ABOVE AND FOREGOING PLAN FOR A DEVELOPMENT IN THE CITY OF ROCKWALL, TEXAS, WAS APPROVED BY THE PLANNING & ZONING COMMISSION OF THE CITY OF ROCKWALL

ON THE MAY OF April, 2022

PLANNING & ZONING COMMISSION, CHAIRMAN

9550 W.Higgins Rd. 170 Rosemont, IL 60018

DR. CAPPS, DR. HODGES & DR. MORGAN CHM REAL ESTATE, LLC 1200 SUMMER LEE DR. ROCKWALL, TX 75032

LOT 5, BLOCK B HORIZON RIDGE ADDITION

DISCLAIMER: All drawings are proprietary and the exclusive property of our company. This/These print(s) shall not be shared, copied or reproduced without expressed permission of our company. This print is loaned in confidence and subject to return upon request by our

No.	Description	Date	

EXTERIOR RENDERINGS

10422

Project number

GA0-1

Scale

APPLICATION INFORMATION

JEFF KILBURG APEX DESIGN BUILD 9550 W HIGGINS RD, SUITE 170, ROSEMONT, IL 60018 PHONE: 847-288-0100 EMAIL: RAQUELLEK@APEXDESIGNBUILD.NET

OWNER INFORMATION

DR. CAPPS, DR. HODGES & DR. MORGAN CHM REAL ESTATE, LLC 740 WILFORD WAY, HEATH, TX 75032 PHONE: 972-771-9500 EMAIL: CHADJCAPPS@GMAIL.COM

SURVEYOR


WINDROSE LAND SURVEYING 220 ELM STREET, SUITE #200 LEWISVILLE, TX 75057 PH: 214.217.2544


PROJECT NAME:

CAPPS, HODGES & MORGAN


CASE NUMBER: SP2022-009.











HORIZON RIDGE ADDITION				
200000000000000000000000000000000000000	TY: (WALL	STATE: TEXAS		
COUNTY	SURVEY:	ABSTRACT NO.	1	
ROCKWALL	E. TEAL SURVEY	207	-	

PLANTING SPECIFICATIONS

- A. QUALIFICATIONS OF LANDSCAPE CONTRACTOR
- ALL LANDSCAPE WORK SHOWN ON THESE PLANS SHALL BE PERFORMED BY A SINGLE FIRM SPECIALIZING IN LANDSCAPE PLANTING.
- 2. A LIST OF SUCCESSFULLY COMPLETED PROJECTS OF THIS TYPE SIZE AND NATURE MAY BE REQUESTED BY THE OWNER FOR FURTHER QUALIFICATION MEASURES.
- THE LANDSCAPE CONTRACTOR SHALL HOLD A VALID NURSERY AND FLORAL CERTIFICATE ISSUED BY THE TEXAS DEPARTMENT OF AGRICULTURE. AS WELL AS OPERATE UNDER A COMMERCIAL PESTICIDE. APPLICATOR LICENSE ISSUED BY EITHER THE TEXAS DEPARTMENT OF AGRICULTURE OR THE TEXAS STRUCTURAL PEST CONTROL BOARD.
- B. SCOPE OF WORK
 - WORK COVERED BY THESE SECTIONS INCLUDES THE FURNISHING AND PAYMENT OF ALL MATERIALS, LABOR, SERVICES, EQUIPMENT, LICENSES, TAXES AND ANY OTHER ITEMS THAT ARE NECESSARY FOR THE EXECUTION, INSTALLATION AND COMPLETION OF ALL WORK, SPECIFIED HEREIN AND / OR SHOWN ON THE LANDSCAPE PLANS, NOTES, AND DETAILS.
- 2. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES AND REGULATIONS REQUIRED BY AUTHORITIES HAVING JURISDICTION OVER SUCH WORK, INCLUDING ALL INSPECTIONS AND PERMITS REQUIRED BY FEDERAL, STATE AND LOCAL AUTHORITIES IN SUPPLY, TRANSPORTATION AND INSTALLATION OF MATERIALS.
- 3. THE LANDSCAPE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL UNDERGROUND UTILITY LINES (WATER, SEWER, ELECTRICAL, TELEPHONE, GAS, CABLE, TELEVISION, ETC.) PRIOR TO THE START OF
- A. ALL MANUFACTURED PRODUCTS SHALL BE NEW B. CONTAINER AND BALLED-AND-BURLAPPED PLANTS:
- FURNISH NURSERY-GROWN PLANTS COMPLYING WITH ANSI Z60.1-2014. PROVIDE WELL-SHAPED, FULLY BRANCHED, HEALTHY, VIGOROUS STOCK FREE OF DISEASE, INSECTS, EGGS, LARVAE, AND DEFECTS SUCH AS KNOTS, SUN SCALD, INJURIES, ABRASIONS, AND DISFIGUREMENT, ALL PLANTS WITHIN A SPECIES SHALL HAVE SIMILAR SIZE. AND SHALL BE OF A FORM TYPICAL FOR THE SPECIES. ALL TREES SHALL BE OBTAINED FROM SOURCES WITHIN 200 MILES OF THE PROJECT SITE, AND WITH SIMILAR CLIMACTIC CONDITIONS.
- 2. ROOT SYSTEMS SHALL BE HEALTHY, DENSELY BRANCHED ROOT SYSTEMS, NON-POT-BOUND, FREE FROM ENCIRCLING AND/OR GIRDLING ROOTS, AND FREE FROM ANY OTHER ROOT DEFECTS (SUCH AS J-SHAPED ROOTS
- TREES MAY BE PLANTED FROM CONTAINERS OR BALLED-AND-BURLAPPED (B&B), UNLESS SPECIFIED ON THE PLANTING LEGEND. BARE-ROOT TREES ARE NOT ACCEPTABLE.
- ANY PLANT DEEMED UNACCEPTABLE BY THE LANDSCAPE ARCHITECT OR OWNER SHALL BE IMMEDIATELY REMOVED FROM THE SITE AND SHALL BE REPLACED WITH AN ACCEPTBLE PLANT OF LIKE TYPE AND SIZE AT THE CONTRACTOR'S OWN EXPENSE. ANY PLANTS APPEARING TO BE UNHEALTHY, EVEN IF DETERMINED TO STILL BE ALIVE, SHALL NOT BE ACCEPTED. THE LANDSCAPE ARCHITECT AND OWNER SHALL BE THE SOLE JUDGES AS TO THE ACCEPTABILITY OF PLANT MATERIAL.
- ALL TREES SHALL BE STANDARD IN FORM, UNLESS OTHERWISE SPECIFIED. TREES WITH CENTRAL LEADERS WILL NOT BE ACCEPTED IF LEADER IS DAMAGED OR REMOVED. PRUNE ALL DAMAGED TWIGS
- 6. CALIPER MEASUREMENTS FOR STANDARD (SINGLE TRUNK) TREES SHALL BE AS FOLLOWS: SIX INCHES ABOVE THE ROOT FLARE FOR TREES UP TO AND INCLUDING FOUR INCHES IN CALIPER, AND TWELVE INCHES ABOVE THE ROOT FLARE FOR TREES EXCEEDING FOUR INCHES IN CALIPER. MULTI-TRUNK TREES SHALL BE MEASURED BY THEIR OVERALL HEIGHT, MEASURED FROM THE TOP OF THE ROOT BALL. WHERE CALIPER MEASUREMENTS ARE USED, THE CALIPER SHALL BE CALCULATED
- AS ONE-HALF OF THE SUM OF THE CALIPER OF THE THREE LARGEST TRUNKS. 8. ANY TREE OR SHRUB SHOWN TO HAVE EXCESS SOIL PLACED ON TOP OF THE ROOT BALL, SO THAT THE ROOT FLARE HAS BEEN COMPLETELY COVERED, SHALL BE REJECTED.
- C. SOD: PROVIDE WELL-ROOTED SOD OF THE VARIETY NOTED ON THE PLANS. SOD SHALL BE GUT FROM HEALTHY MATURE TURE WITH SOIL THICKNESS OF 3/4" TO 1". EACH PALLET OF SOD SHALL BE ACCOMPANIED BY A CERTIFICATE FROM SUPPLIER STATING THE COMPOSITION OF THE SOD.
- PLANTS ROOTS AND SEEDS COMPOST: WELL-COMPOSTED, STABLE, AND WEED-FREE ORGANIC MATTER, 6H RANGE OF 5.5 TO 8: MOISTURE CONTENT 35 TO 55 PERCENT BY WEIGHT: 100 PERCENT PASSING THROUGH 3/4-INCH SIEVE: SOLUBLE SALT CONTENT OF 5 TO 10 DECISIEMENS/M: NOT EXCEEDING 0.5 PERCENT INERT CONTAMINANTS AND FREE OF SUBSTANCES TOXIC TO PLANTINGS. NO MANURE OR ANIMAL-BASED PRODUCTS SHALL BE
- F. FERTILIZER: GRANULAR FERTILIZER CONSISTING OF NITROGEN, PHOSPHORUS, POTASSIUM, AND OTHER NUTRIENTS IN PROPORTIONS, AMOUNTS, AND RELEASE RATES RECOMMENDED IN A SOIL REPORT FROM A
- QUALIFIED SOIL-TESTING AGENCY (SEE BELOW). MULCH: SIZE AND TYPE AS INDICATED ON PLANS, FREE FROM DELETERIOUS MATERIALS AND SUITABLE AS A TOP DRESSING OF TREES AND SHRUBS. H. TREE STAKING AND GUYING
- STAKES: 6' LONG GREEN METAL T-POSTS.
- GUY AND TIE WIRE: ASTM A 641, CLASS 1, GALVANIZED-STEEL WIRE, 2-STRAND, TWISTED, 0.106 INCH STRAP CHAFING GUARD: REINFORCED NYLON OR CANVAS AT LEAST 1-1/2 INCH WIDE, WITH
- GROMMETS TO PROTECT TREE TRUNKS FROM DAMAGE. STEEL EDGING: PROFESSIONAL STEEL EDGING, 14 GAUGE THICK X 4 INCHES WIDE, FACTORY PAINTED DARK
- GREEN. ACCEPTABLE MANUFACTURERS INCLUDE COL-MET OR APPROVED EQUAL. PRE-EMERGENT HERBICIDES: ANY GRANULAR, NON-STAINING PRE-EMERGENT HERBICIDE THAT IS LABELED FOR THE SPECIFIC ORNAMENTALS OR TURF ON WHICH IT WILL BE UTILIZED. PRE-EMERGENT HERBICIDES SHALL BE APPLIED PER THE MANUFACTURER'S LABELED RATES.
- A. SOIL PREPARATION
- BEFORE STARTING WORK, THE LANDSCAPE CONTRACTOR SHALL VERIFY THAT THE GRADE OF ALL LANDSCAPE AREAS ARE WITHIN +/-0.1' OF FINISH GRADE. THE CONTRACTOR SHALL NOTIFY THE OWNER IMMEDIATELY SHOULD ANY DISCREPANCIES EXIST. SOIL TESTING:
- a. AFTER FINISH GRADES HAVE BEEN ESTABLISHED, CONTRACTOR SHALL HAVE SOIL SAMPLES FROM THE PROJECT'S LANDSCAPE AREAS TESTED BY AN ESTABLISHED SOIL TESTING LABORATORY. EACH SAMPLE SUBMITTED TO THE LAB SHALL CONTAIN NO LESS THAN ONE QUART OF SOIL. TAKEN FROM BETWEEN THE SOIL SURFACE AND 6" DEPTH. IF NO SAMPLE LOCATIONS ARE INDICATED ON THE PLANS, THE CONTRACTOR SHALL TAKE A MINIMUM OF THREE SAMPLES FROM VARIOUS REPRESENTATIVE LOCATIONS FOR TESTING.
- THE CONTRACTOR SHALL HAVE THE SOIL TESTING LABORATORY PROVIDE RESULTS FOR THE FOLLOWING: SOIL TEXTURAL CLASS, GENERAL SOIL FERTILITY, pH, ORGANIC MATTER CONTENT, SALT (CEC), LIME, SODIUM ADSORPTION RATIO (SAR) AND BORON CONTENT.
- THE CONTRACTOR SHALL ALSO SUBMIT THE PROJECT'S PLANT LIST TO THE LABORATORY ALONG THE SOIL REPORT PRODUCED BY THE LABORATORY SHALL CONTAIN RECOMMENDATIONS FOR THE FOLLOWING (AS APPROPRIATE): SEPARATE SOIL PREPARATION AND BACKFILL MIX
- RECOMMENDATIONS FOR GENERAL ORNAMENTAL PLANTS, XERIC PLANTS, TURF, AND NATIVE SEED, AS WELL AS PRE-PLANT FERTILIZER APPLICATIONS AND RECOMMENDATIONS FOR ANY OTHER SOIL RELATED ISSUES. THE REPORT SHALL ALSO PROVIDE A FERTILIZER PROGRAM FOR THE ESTABLISHMENT PERIOD AND FOR LONG-TERM MAINTENANCE 3. THE CONTRACTOR SHALL INSTALL SOIL AMENDMENTS AND FERTILIZERS PER THE SOILS REPORT
- RECOMMENDATIONS. ANY CHANGE IN COST DUE TO THE SOIL REPORT RECOMMENDATIONS. EITHER INCREASE OR DECREASE, SHALL BE SUBMITTED TO THE OWNER WITH THE REPORT. 4. FOR BIDDING PURPOSES ONLY. THE SOIL PREPARATION SHALL CONSIST OF THE FOLLOWIN. TURF: INCORPORATE THE FOLLOWING AMENDMENTS INTO THE TOP 8" OF SOIL BY MEANS OF
- ROTOTILLING AFTER CROSS-RIPPING: NITROGEN STABILIZED ORGANIC AMENDMENT - 4 CU. YDS. PER 1,000 S.F. PREPLANT TURF FERTILIZER (10-20-10 OR SIMILAR, SLOW RELEASE, ORGANIC) - 15 LBS PER 1,000
- "CLAY BUSTER" OR EQUAL USE MANUFACTURER'S RECOMMENDED RATE TREES, SHRUBS, AND PERENNIALS: INCORPORATE THE FOLLOWING AMENDMENTS INTO THE TOP 8" OF SOIL BY MEANS OF ROTOTILLING AFTER CROSS-RIPPING:
- NITROGEN STABILIZED ORGANIC AMENDMENT 4 CU. YDS. PER 1,000 S.F. 12-12-12 FERTILIZER (OR SIMILAR, ORGANIC, SLOW RELEASE) - 10 LBS. PER CU. YD. "CLAY BUSTER" OR EQUAL - USE MANUFACTURER'S RECOMMENDED RATE
- IRON SULPHATE 2 LBS. PER CU. YD. 5. IN THE CONTEXT OF THESE PLANS, NOTES, AND SPECIFICATIONS, "FINISH GRADE" REFERS TO THE FINAL ELEVATION OF THE SOIL SURFACE (NOT TOP OF MULCH) AS INDICATED ON THE GRADING PLANS. a. BEFORE STARTING WORK, THE LANDSCAPE CONTRACTOR SHALL VERIFY THAT THE ROUGH GRADES OF ALL LANDSCAPE AREAS ARE WITHIN +/-0.1' OF FINISH GRADE. SEE SPECIFICATIONS
- FOR MORE DETAILED INSTRUCTION ON TURF AREA AND PLANTING BED PREPARATION. b. CONSTRUCT AND MAINTAIN FINISH GRADES AS SHOWN ON GRADING PLANS, AND CONSTRUCT AND MAINTAIN SLOPES AS RECOMMENDED BY THE GEOTECHNICAL REPORT. ALL LANDSCAPE AREAS SHALL HAVE POSITIVE DRAINAGE AWAY FROM STRUCTURES AT THE MINIMUM SLOPE SPECIFIED IN THE REPORT AND ON THE GRADING PLANS, AND AREAS OF POTENTIAL PONDING SHALL BE REGRADED TO BLEND IN WITH THE SURROUNDING GRADES AND ELIMINATE PONDING c. THE LANDSCAPE CONTRACTOR SHALL DETERMINE WHETHER OR NOT THE EXPORT OF ANY SOIL
- WILL BE NEEDED, TAKING INTO ACCOUNT THE ROUGH GRADE PROVIDED, THE AMOUNT OF SOIL AMENDMENTS TO BE ADDED (BASED ON A SOIL TEST, PER SPECIFICATIONS), AND THE FINISH GRADES TO BE ESTABLISHED ENSURE THAT THE FINISH GRADE IN SHRUB AREAS IMMEDIATELY ADJACENT TO WALKS AND OTHER WALKING SURFACES, AFTER INSTALLING SOIL AMENDMENTS, IS 3" BELOW THE ADJACENT
- FINISH SURFACE, IN ORDER TO ALLOW FOR PROPER MULCH DEPTH. TAPER THE SOIL SURFACE TO MEET FINISH GRADE, AS SPECIFIED ON THE GRADING PLANS, AT APPROXIMATELY 18" AWAY e. ENSURE THAT THE FINISH GRADE IN TURF AREAS IMMEDIATELY ADJACENT TO WALKS AND
- OTHER WALKING SURFACES, AFTER INSTALLING SOIL AMENDMENTS, IS 1" BELOW THE FINISH SURFACE OF THE WALKS. TAPER THE SOIL SURFACE TO MEET FINISH GRADE, AS SPECIFIED ON THE GRADING PLANS, AT APPROXIMATELY 18" AWAY FROM THE WALKS.
- SHOULD ANY CONFLICTS AND/OR DISCREPANCIES ARISE BETWEEN THE GRADING PLANS, GEOTECHNICAL REPORT, THESE NOTES AND PLANS, AND ACTUAL CONDITIONS, THE CONTRACTOR SHALL IMMEDIATELY BRING SUCH ITEMS TO THE ATTENTION OF THE LANDSCAPE ARCHITECT, GENERAL CONTRACTOR, AND OWNER.
- 6. ONCE SOIL PREPARATION IS COMPLETE, THE LANDSCAPE CONTRACTOR SHALL ENSURE THAT THERE ARE NO DEBRIS, TRASH, OR STONES LARGER THAN 1" REMAINING IN THE TOP 6" OF SOIL.

- THE CONTRACTOR SHALL PROVIDE SUBMITTALS AND SAMPLES, IF REQUIRED, TO THE LANDSCAPE ARCHITECT, AND RECEIVE APPROVAL IN WRITING FOR SUCH SUBMITTALS BEFORE WORK COMMENCES.
- SUBMITTALS SHALL INCLUDE PHOTOS OF PLANTS WITH A RULER OR MEASURING STICK FOR SCALE. PHOTOS OR SAMPLES OF ANY REQUIRED MULCHES, AND SOIL TEST RESULTS AND PREPARATION RECOMMENDATIONS FROM THE TESTING LAB (INCLUDING COMPOST AND FERTILIZER RATES AND TYPES, AND OTHER AMENDMENTS FOR TREE/SHRUB, TURF, AND SEED AREAS AS MAY BE APPROPRIATE)
- 3. SUBMITTALS SHALL ALSO INCLUDE MANUFACTURER CUT SHEETS FOR PLANTING ACCESSORIES SUCH AS TREE STAKES AND TIES, EDGING, AND LANDSCAPE FABRICS (IF ANY). 4. WHERE MULTIPLE ITEMS ARE SHOWN ON A PAGE, THE CONTRACTOR SHALL CLEARLY INDICATE THE
- ITEM BEING CONSIDERED. GENERAL PLANTING
- REMOVE ALL NURSERY TAGS AND STAKES FROM PLANTS. EXCEPT IN AREAS TO BE PLANTED WITH ORNAMENTAL GRASSES, APPLY PRE-EMERGENT HERBICIDES
- AT THE MANUFACTURER'S RECOMMENDED RATE. TRENCHING NEAR EXISTING TREES: a. CONTRACTOR SHALL NOT DISTURB ROOTS 1-1/2" AND LARGER IN DIAMETER WITHIN THE CRITICAL ROOT ZONE (CRZ) OF EXISTING TREES, AND SHALL EXERCISE ALL POSSIBLE CARE AND PRECAUTIONS TO AVOID INJURY TO TREE ROOTS, TRUNKS, AND BRANCHES. THE CRZ IS DEFINED AS A CIRCULAR AREA EXTENDING OUTWARD FROM THE TREE TRUNK, WITH A RADIUS
- EQUAL TO 1' FOR EVERY 1" OF TRUNK DIAMETER-AT-BREAST-HEIGHT (4.5' ABOVE THE AVERAGE GRADE AT THE TRUNK b. ALL EXCAVATION WITHIN THE CRZ SHALL BE PERFORMED USING HAND TOOLS. NO MACHINE EXCAVATION OR TRENCHING OF ANY KIND SHALL BE ALLOWED WITHIN THE CRZ.
- ALTER ALIGNMENT OF PIPE TO AVOID TREE ROOTS 1-1/2" AND LARGER IN DIAMETER. WHERE TREE ROOTS 1-1/2" AND LARGER IN DIAMETER ARE ENCOUNTERED IN THE FIELD. TUNNEL UNDER SUCH ROOTS. WRAP EXPOSED ROOTS WITH SEVERAL LAYERS OF BURLAP AND KEEP MOIST. CLOSE ALL TRENCHES WITHIN THE CANOPY DRIP LINES WITHIN 24 HOURS.
- d. ALL SEVERED ROOTS SHALL BE HAND PRUNED WITH SHARP TOOLS AND ALLOWED TO AIR-DRY. DO NOT USE ANY SORT OF SEALERS OR WOUND PAINTS.
- TREE PLANTING HOLES SHALL BE EXCAVATED TO MINIMUM WIDTH OF TWO TIMES THE WIDTH OF THE ROOTBALL, AND TO A DEPTH EQUAL TO THE DEPTH OF THE ROOTBALL LESS TWO TO FOUR INCHES. 2 SCARIEY THE SIDES AND BOTTOM OF THE PLANTING HOLE PRIOR TO THE PLACEMENT OF THE TREE
- REMOVE ANY GLAZING THAT MAY HAVE BEEN CAUSED DURING THE EXCAVATION OF THE HOLE. 3. FOR CONTAINER AND BOX TREES, TO REMOVE ANY POTENTIALLY GIRDLING ROOTS AND OTHER ROOT DEFECTS, THE CONTRACTOR SHALL SHAVE A 1" LAYER OFF OF THE SIDES AND BOTTOM OF THE ROOTBALL OF ALL TREES JUST BEFORE PLACING INTO THE PLANTING PIT. DO NOT "TEASE" ROOTS
- 4. INSTALL THE TREE ON UNDISTURBED SUBGRADE SO THAT THE TOP OF THE ROOTBALL IS TWO TO FOUR INCHES ABOVE THE SURROUNDING GRADE.
- BACKFILL THE TREE HOLE UTILIZING THE EXISTING TOPSOIL FROM ON-SITE. ROCKS LARGER THAN 1* DIA. AND ALL OTHER DEBRIS SHALL BE REMOVED FROM THE SOIL PRIOR TO THE BACKFILL. SHOULD ADDITIONAL SOIL BE REQUIRED TO ACCOMPLISH THIS TASK, USE STORED TOPSOIL FROM ON-SITE OR IMPORT ADDITIONAL TOPSOIL FROM OFF-SITE AT NO ADDITIONAL COST TO THE OWNER. IMPORTED TOPSOIL SHALL BE OF SIMILAR TEXTURAL CLASS AND COMPOSITION IN THE ON-SITE SOIL.
- TREES SHALL NOT BE STAKED UNLESS LOCAL CONDITIONS (SUCH AS HEAVY WINDS OR SLOPES) REQUIRE STAKES TO KEEP TREES UPRIGHT. SHOULD STAKING BE REQUIRED, THE TOTAL NUMBER OF TREE STAKES (BEYOND THE MINIMUMS LISTED BELOW) WILL BE LEFT TO THE LANDSCAPE CONTRACTOR'S DISCRETION. SHOULD ANY TREES FALL OR LEAN, THE LANDSCAPE CONTRACTOR SHALL STRAIGHTEN THE TREE, OR REPLACE IT SHOULD IT BECOME DAMAGED. TREE STAKING SHALL ADHERE TO THE FOLLOWING GUIDELINES: TWO STAKES PER TREE a. 1"-2" TREES THREE STAKES PER TREE
- TREES OVER 4" CALIPER GUY AS NEEDED THREE STAKES PER TREE MINIMUM, QUANTITY AND POSITIONS AS MULTI-TRUNK TREES NEEDED TO STABILIZE THE TREE MULTI-TRUNK TREES THREE STAKES PER TREE MINIMUM, QUANTITY AND POSITIONS AS
- NEEDED TO STABILIZE THE TREE 7. UPON COMPLETION OF PLANTING, CONSTRUCT AN EARTH WATERING BASIN AROUND THE TREE. COVER THE INTERIOR OF THE TREE RING WITH THE WEED BARRIER CLOTH AND TOPDRESS WITH
- MULCH (TYPE AND DEPTH PER PLANS). E. SHRUB, PERENNIAL, AND GROUNDCOVER PLANTING DIG THE PLANTING HOLES TWICE AS WIDE AND 2" LESS DEEP THAN EACH PLANT'S ROOTBALL. INSTALL
- THE PLANT IN THE HOLE. BACKFILL AROUND THE PLANT WITH SOIL AMENDED PER SOIL TEST INSTALL THE WEED BARRIER CLOTH, OVERLAPPING IT AT THE ENDS. UTILIZE STEEL STAPLES TO KEEP THE WEED BARRIER CLOTH IN PLACE.
- WHEN PLANTING IS COMPLETE. INSTALL MULCH (TYPE AND DEPTH PER PLANS) OVER ALL PLANTING BEDS, COVERING THE ENTIRE PLANTING AREA.
- SOD VARIETY TO BE AS SPECIFIED ON THE LANDSCAPE PLAN.


b 2-1/2"-4" TREES


- LAY SOD WITHIN 24 HOURS FROM THE TIME OF STRIPPING. DO NOT LAY IF THE GROUND IS FROZEN. LAY THE SOD TO FORM A SOLID MASS WITH TIGHTLY FITTED JOINTS. BUTT ENDS AND SIDES OF SOD STRIPS - DO NOT OVERLAP. STAGGER STRIPS TO OFFSET JOINTS IN ADJACENT COURSES.
- 4. ROLL THE SOD TO ENSURE GOOD CONTACT OF THE SOD'S ROOT SYSTEM WITH THE SOIL 5. WATER THE SOD THOROUGHLY WITH A FINE SPRAY IMMEDIATELY AFTER PLANTING TO OBTAIN AT
- LEAST SIX INCHES OF PENETRATION INTO THE SOIL BELOW THE SOD.
- INSTALL MULCH TOPDRESSING, TYPE AND DEPTH PER MULCH NOTE, IN ALL PLANTING AREAS AND TREE RINGS.
- 2. DO NOT INSTALL MULCH WITHIN 6" OF TREE ROOT FLARE AND WITHIN 24" OF HABITABLE STRUCTURES. EXCEPT AS MAY BE NOTED ON THESE PLANS. MULCH COVER WITHIN 6" OF CONCRETE WALKS AND CURBS SHALL NOT PROTRUDE ABOVE THE FINISH SURFACE OF THE WALKS AND CURBS. MULCH COVER WITHIN 12" OF WALLS SHALL BE AT LEAST 3" LOWER THAN THE TOP OF WALL.
- H. CLEAN UP 1. DURING LANDSCAPE PREPARATION AND PLANTING, KEEP ALL PAVEMENT CLEAN AND ALL WORK AREAS IN A NEAT, ORDERLY CONDITION.
- DISPOSED LEGALLY OF ALL EXCAVATED MATERIALS OFF THE PROJECT SITE. INSPECTION AND ACCEPTANCE 1. UPON COMPLETION OF THE WORK, THE LANDSCAPE CONTRACTOR SHALL PROVIDE THE SITE CLEAN, FREE OF DEBRIS AND TRASH, AND SUITABLE FOR USE AS INTENDED. THE LANDSCAPE CONTRACTOR
- SHALL THEN REQUEST AN INSPECTION BY THE OWNER TO DETERMINE FINAL ACCEPTABILITY. 2. WHEN THE INSPECTED PLANTING WORK DOES NOT COMPLY WITH THE CONTRACT DOCUMENTS, THE LANDSCAPE CONTRACTOR SHALL REPLACE AND/OR REPAIR THE REJECTED WORK TO THE OWNER'S SATISFACTION WITHIN 24 HOURS.
- 3. THE LANDSCAPE MAINTENANCE PERIOD WILL NOT COMMENCE UNTIL THE LANDSCAPE WORK HAS BEEN RE-INSPECTED BY THE OWNER AND FOUND TO BE ACCEPTABLE. AT THAT TIME, A WRITTEN NOTICE OF FINAL ACCEPTANCE WILL BE ISSUED BY THE OWNER, AND THE MAINTENANCE AND GUARANTEE PERIODS WILL COMMENCE.
- J. LANDSCAPE MAINTENANCE 1. THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL WORK SHOWN ON THESE PLANS FOR 90 DAYS BEYOND FINAL ACCEPTANCE OF ALL LANDSCAPE WORK BY THE OWNER. LANDSCAPE MAINTENANCE SHALL INCLUDE WEEKLY SITE VISITS FOR THE FOLLOWING ACTIONS (AS APPROPRIATE): PROPER PRUNING, RESTAKING OF TREES, RESETTING OF PLANTS THAT HAVE SETTLED, MOWING AND AERATION OF LAWNS, WEEDING, TREATING FOR INSECTS AND DISEASES REPLACEMENT OF MULCH, REMOVAL OF LITTER, REPAIRS TO THE IRRIGATION SYSTEM DUE TO FAULTY PARTS AND/OR WORKMANSHIP, AND THE APPROPRIATE WATERING OF ALL PLANTINGS. THE LANDSCAPE CONTRACTOR SHALL MAINTAIN THE IRRIGATION SYSTEM IN PROPER WORKING
- ORDER, WITH SCHEDULING ADJUSTMENTS BY SEASON TO MAXIMIZE WATER CONSERVATION. SHOULD SEEDED AND/OR SODDED AREAS NOT BE COVERED BY AN AUTOMATIC IRRIGATION SYSTEM, THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR WATERING THESE AREAS AND OBTAINING A FULL, HEALTHY STAND OF PLANTS AT NO ADDITIONAL COST TO THE OWNER. 3. TO ACHIEVE FINAL ACCEPTANCE AT THE END OF THE MAINTENANCE PERIOD, ALL OF THE FOLLOWING
- CONDITIONS MUST OCCUR: THE LANDSCAPE SHALL SHOW ACTIVE. HEALTHY GROWTH (WITH EXCEPTIONS MADE FOR SEASONAL DORMANCY). ALL PLANTS NOT MEETING THIS CONDITION SHALL BE REJECTED AND REPLACED BY HEALTHY PLANT MATERIAL PRIOR TO FINAL ACCEPTANCE.
- ALL HARDSCAPE SHALL BE CLEANED PRIOR TO FINAL ACCEPTANCE. SODDED AREAS MUST BE ACTIVELY GROWING AND MUST REACH A MINIMUM HEIGHT OF 1 1/2 INCHES BEFORE FIRST MOWING. BARE AREAS LARGER THAN TWELVE SQUARE INCHES MUST BE RESODDED (AS APPROPRIATE) PRIOR TO FINAL ACCEPTANCE. ALL SODDED TURF SHALL BE
- NEATLY MOWED. K. WARRANTY PERIOD, PLANT GUARANTEE AND REPLACEMENTS 1. THE LANDSCAPE CONTRACTOR SHALL GUARANTEE ALL TREES, SHRUBS, PERENNIALS, SOD, AND IRRIGATION SYSTEMS FOR A PERIOD OF ONE YEAR FROM THE DATE OF THE OWNER'S FINAL ACCEPTANCE (90 DAYS FOR ANNUAL PLANTS). THE CONTRACTOR SHALL REPLACE, AT HIS OWN EXPENSE AND TO THE SATISFACTION OF THE OWNER, ANY PLANTS WHICH DIE IN THAT TIME, OR
- CONTRACTOR SHALL ONLY BE RESPONSIBLE FOR REPLACEMENT OF PLANTS WHEN PLANT DEATH CANNOT BE ATTRIBUTED DIRECTLY TO OVERWATERING OR OTHER DAMAGE BY HUMAN ACTIONS. PROVIDE A MINIMUM OF (2) COPIES OF RECORD DRAWINGS TO THE OWNER UPON COMPLETION OF WORK. A RECORD DRAWING IS A RECORD OF ALL CHANGES THAT OCCURRED IN THE FIELD AND THAT ARE DOCUMENTED THROUGH CHANGE ORDERS, ADDENDA, OR CONTRACTOR/CONSULTANT DRAWING MARKUPS.

2. AFTER THE INITIAL MAINTENANCE PERIOD AND DURING THE GUARANTEE PERIOD. THE LANDSCAPE

REPAIR ANY PORTIONS OF THE IRRIGATION SYSTEM WHICH OPERATE IMPROPERLY.


APPROVED: HEREBY CERTIFY THAT THE ABOVE AND FOREGOING SITE PLAN FOR A DEVELOPMENT IN THE CITY OF ROCKWALL, TEXAS, WAS APPROVED BY THE PLANNING & ZONING COMMISSION OF THE CITY OF ROCKWALL ON THE 12th DAY OF April 2022





(800) 680-6630 15455 Dallas Pkwy., Ste 600 Addison, TX 75001 www.EvergreenDesignGroup.com





200 SU ROC

0,0 Zσ

CONTACT NAME: MARK N. PEEPLE SHEET

HORIZON RIDGE ADDITION **TEXAS** ABSTRACT NO.

207

CASE #: SP2022-009

CAPPS, HODGES, & MORGAN

APPLICANT:

LEGAL DESCRIPTION:

LOT 5, BLOCK B.

SURVEY:

E. TEAL SURVEY

9550 W. HIGGINS RD., SUITE 170, ROSEMONT, IL 60018

EMAIL: RAQUELLE@APEXDESIGNBUILD.NET

DR. CAPPS, DR. HODGES & DR. MORGAN

740 WILFORD WAY, HEATH, TX 75032

EMAIL: CHADJCAPPS@GMAIL.COM

WINDROSE LAND SURVEYING

ROCKWALL

220 ELM STREET, SUITE #200

CHM REAL ESTATE, LLC

PHONE: 972-771-9500

APEX DESIGN BUILD

LEWISVILLE, TX 75057

PH: 214.217.2544

COUNTY

ROCKWAL

JEFF KILBURG

PH: 847-288-0100

119.5

TOTAL MITIGATION FOR SITE

207

ROCKWALL

E. TEAL SURVEY

- 1. FABRIC: 4 FOOT HIGH ORANGE PLASTIC FENCING AS SHOWN ON THE PLANS AND SHALL BE WOVEN WITH 2 INCH MESH OPENINGS SUCH THAT IN A VERTICAL DIMENSION OF 23 INCHES ALONG THE DIAGONALS OF THE OPENINGS THERE SHALL BE AT LEAST 7 MESHES.
- 2. POSTS: POSTS SHALL BE A MINIMUM OF 72 INCHES LONG AND STEEL 'T' SHAPED WITH A MINIMUM WEIGHT OF 1.3 POUNDS PER LINEAR FOOT.
- 3. TIE WIRE: WIRE FOR ATTACHING THE FABRIC TO THE T-POSTS SHALL BE NOT LESS THAN NO. 12 GAUGE GALVANIZED WIRE,
- 4. USED MATERIALS: PREVIOUSLY-USED MATERIALS, MEETING THE ABOVE REQUIREMENTS AND WHEN APPROVED BY THE OWNER, MAY BE USED.

CONSTRUCTION METHODS


- ALL TREES AND SHRUBS SHOWN TO REMAIN WITHIN THE PROXIMITY OF THE CONSTRUCTION SITE SHALL BE PROTECTED PRIOR TO BEGINNING ANY DEVELOPMENT ACTIVITY.
- 2. EMPLOY THE SERVICES OF AN ISA (INTERNATIONAL SOCIETY OF ARBORICULTURE) CERTIFIED ARBORIST AND OBTAIN ALL REQUIRED PERMITS TO PRUNE THE EXISTING TREES FOR CLEANING, RAISING AND THINNING, AS MAY BE REQUIRED.
- 3. PROTECTIVE FENCING SHALL BE ERECTED OUTSIDE THE CRITICAL ROOT ZONE (CRZ, EQUAL TO 1' FROM THE TRUNK FOR EVERY 1" OF DBH) AT LOCATIONS SHOWN IN THE PLANS OR AS DIRECTED BY THE LANDSCAPE CONSULTANT AND/OR CITY ARBORIST, AND IN ACCORDANCE WITH THE DETAILS SHOWN ON THE PLANS. FENCING SHALL BE MAINTAINED AND REPAIRED BY THE CONTRACTOR DURING SITE CONSTRUCTION. TREES IN CLOSE PROXIMITY SHALL BE FENCED TOGETHER, RATHER THAN INDIVIDUALLY.
- 4. PROTECTIVE FENCE LOCATIONS IN CLOSE PROXIMITY TO STREET INTERSECTIONS OR DRIVES SHALL ADHERE TO THE APPLICABLE JURISDICTION'S SIGHT DISTANCE CRITERIA.
- 5. THE PROTECTIVE FENCING SHALL BE ERECTED BEFORE SITE WORK COMMENCES AND SHALL REMAIN IN PLACE DURING THE ENTIRE CONSTRUCTION PHASE.
- 6. THE INSTALLATION POSTS SHALL BE PLACED EVERY 6 FEET ON CENTER AND EMBEDDED TO 18 INCHES DEEP. MESH FABRIC SHALL BE ATTACHED TO THE INSTALLATION POSTS BY THE USE OF SUFFICIENT WIRE TIES TO SECURELY FASTEN THE FABRIC TO THE T-POSTS TO HOLD THE FABRIC IN A STABLE AND UPRIGHT POSITION.

- a. DO NOT CLEAR, FILL OR GRADE IN THE CRZ OF ANY TREE. b. DO NOT STORE, STOCKPILE OR DUMP ANY JOB MATERIAL, SOIL OR
- RUBBISH UNDER THE SPREAD OF THE TREE BRANCHES. c. DO NOT PARK OR STORE ANY EQUIPMENT OR SUPPLIES UNDER THE
- d. DO NOT SET UP ANY CONSTRUCTION OPERATIONS UNDER THE TREE CANOPY (SUCH AS PIPE CUTTING AND THREADING, MORTAR MIXING, PAINTING OR LUMBER CUTTING)
- e. DO NOT NAIL OR ATTACH TEMPORARY SIGNS METERS, SWITCHES, WIRES, BRACING OR ANY OTHER ITEM TO THE TREES.
- f. DO NOT PERMIT RUNOFF FROM WASTE MATERIALS INCLUDING SOLVENTS, CONCRETE WASHOUTS, ASPHALT TACK COATS (MC-30 OIL), ETC. TO ENTER THE CRZ. BARRIERS ARE TO BE PROVIDED TO PREVENT SUCH RUNOFF SUBSTANCES FROM ENTERING THE CRZ WHENEVER POSSIBLE, INCLUDING IN AN AREA WHERE RAIN OR SURFACE WATER COULD CARRY SUCH MATERIALS TO THE ROOT
- 8. ROUTE UNDERGROUND UTILITIES TO AVOID THE CRZ. IF DIGGING IS UNAVOIDABLE, BORE UNDER THE ROOTS, OR HAND DIG TO AVOID SEVERING THEM.


- 9. WHERE EXCAVATION IN THE VICINITY OF TREES MUST OCCUR, SUCH AS FOR IRRIGATION INSTALLATION, PROCEED WITH CAUTION, AND USING HAND TOOLS ONLY.
- 10. THE CONTRACTOR SHALL NOT CUT ROOTS LARGER THAN ONE INCH IN DIAMETER WHEN EXCAVATION OCCURS NEAR EXISTING TREES. ALL ROOTS LARGER THAN ONE INCH IN DIAMETER ARE TO BE CUT CLEANLY. FOR OAKS ONLY, ALL WOUNDS SHALL BE PAINTED WITH WOUND SEALER WITHIN 30 MINUTES
- 11. REMOVE ALL TREES, SHRUBS OR BUSHES TO BE CLEARED FROM PROTECTED ROOT ZONE AREAS BY HAND.
- 12. TREES DAMAGED OR KILLED DUE TO CONTRACTOR'S NEGLIGENCE DURING CONSTRUCTION SHALL BE MITIGATED AT THE CONTRACTOR'S EXPENSE AND TO THE PROJECT OWNER'S AND LOCAL JURISDICTION'S
- 13. ANY TREE REMOVAL SHALL BE APPROVED BY THE OWNER AND LOCAL JURISDICTION PRIOR TO ITS REMOVAL, AND THE CONTRACTOR SHALL HAVE ALL REQUIRED PERMITS FOR SUCH ACTIVITIES.
- 14. COVER EXPOSED ROOTS AT THE END OF EACH DAY WITH SOIL, MULCH OR
- 15. IN CRITICAL ROOT ZONE AREAS THAT CANNOT BE PROTECTED DUING CONSTRUCTION AND WHERE HEAVY TRAFFIC IS ANTICIPATED, COVER THE SOIL WITH EIGHT INCHES OF ORGANIC MULCH TO MINIMIZE SOIL COMPACTION. THIS EIGHT INCH DEPTH OF MULCH SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.
- 16. WATER ALL TREES IMPACTED BY CONSTRUCTION ACTIVITIES, DEEPLY ONCE A WEEK DURING PERIODS OF HOT DRY WEATHER. SPRAY TREE CROWNS WITH WATER PERIODICALLY TO REDUCE DUST ACCUMULATION ON THE LEAVES.
- 17. WHEN INSTALLING CONCRETE ADJACENT TO THE ROOT ZONE OF A TREE, USE A PLASTIC VAPOR BARRIER BEHIND THE CONCRETE TO PROHIBIT LEACHING OF LIME INTO THE SOIL.
- 18. CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL TREE PROTECTION FENCING WHEN ALL THREATS TO THE EXISTING TREES FROM CONSTRUCTION-RELATED ACTIVITIES HAVE BEEN REMOVED.

TREES THAT ARE MARKED TO BE PRESERVED ON A SITE PLAN AND FOR WHICH UTILITIES MUST PASS TROUGH THEIR ROOT PROTECTION ZONES MAY REQUIRE TUNNELING AS OPPOSED TO OPEN TRENCHES. THE DECISION TO TUNNEL WILL BE DETERMINED ON A CASE BY CASE BASIS BY THE ENGINEER.

TUNNELS SHALL BE DUG THROUGH THE ROOT PROTECTION ZONE IN ORDER TO MINIMIZE ROOT DAMAGE.




TUNNEL TO MINIMIZE ROOT DAMAGE (TOP) AS OPPOSED TO SURFACE-DUG TRENCHES IN ROOT PROTECTION ZONE WHEN THE 5' MINIMUM DISTANCE



OPEN TRENCHING MAY BE USED IF EXPOSED TREE ROOTS DO NOT EXCEED 3" OR ROOTS CAN BE BENT BACK.

BORING THROUGH ROOT PROTECTION ZONE

- RETENTION AREAS WILL BE SET AS PART OF THE REVIEW PROCESS AND PRE-CONSTRUCTION MEETING.
- BOUNDARIES OF RETENTION AREAS MUST BE STAKED AT THE PRE-CONSTRUCTION MEETING AND FLAGGED PRIOR TO ROOT PRUNING.
- EXACT LOCATION OF ROOT PRUNING SHALL BE DETERMINED IN THE FIELD IN COORDINATION WITH THE FORESTRY INSPECTOR.
- TRENCH SHOULD BE IMMEDIATELY BACKFILLED WITH EXCAVATED SOIL OR OTHER
- ORGANIC SOIL AS SPECIFIED PER PLAN OR BY THE FORESTRY INSPECTOR. ROOTS SHALL BE CLEANLY CUT USING VIBRATORY KNIFE OR OTHER ACCEPTABLE EQUIPMENT. ROT PRUNING METHODS AND MEANS MUST BE IN ACCORDANCE WITH
- ANSI STANDARD A3000. ALL PRUNING MUST BE EXECUTED AT LOD SHOWN ON PLANS OR AS AUTHORIZED
- IN WRITING BY THE FORESTRY INSPECTOR. 7. SUPPLEMENTAL WATERING MAY BE REQUIRED FOR ROOT PRUNED TREES THROUGHOUT THE GROWING SEASON DURING CONSTRUCTION AND SUBSEQUENT WARRANTY AND MAINTENANCE PERIOD.




PRE-CONSTRUCTION MEETING.

ON THE 18 DAY OF April . 2022

MANNING & ZONING COMMISSION, CHAIRMAN

ROOT PRUNING DETAIL



MULCH INSIDE RPZ PROTECTION FENCE (SEE SPECS)

EVERGREEN


15455 Dallas Pkwy., Ste 600


Addison, TX 75001

www.EvergreenDesignGroup.con

 THE FENCING LOCATION SHOWN ABOVE IS DIAGRAMATIC ONLY AND WILL CONFORM TO THE DRIP LINE AND BE LIMITED TO PROJECT BOUNDARY. WHERE MULTIPLE ADJACENT TREES

WILL BE ENCLOSED BY FENCING, THE FENCING SHALL BE CONTINUOUS AROUND ALL TREES. FOR ACCEPTABLE FENCING MATERIALS SEE SPECIFICATIONS.





CASE #: SP2022-009

CAPPS, HODGES, & MORGAN

DR. CAPPS, DR. HODGES & DR. MORGAN CHM REAL ESTATE, LLC 740 WILFORD WAY, HEATH, TX 75032 PHONE: 972-771-9500 EMAIL: CHADJCAPPS@GMAIL.COM

APPLICANT: JEFF KILBURG APEX DESIGN BUILD 9550 W. HIGGINS RD., SUITE 170, ROSEMONT, IL 60018 PH: 847-288-0100 EMAIL: RAQUELLE@APEXDESIGNBUILD.NET

WINDROSE LAND SURVEYING LEWISVILLE, TX 75057

CONTACT NAME: MARK N. PEEPLE

207

LOT 5, BLOCK B, HORIZON RIDGE ADDITION ROCKWALL TEXAS ABSTRACT NO. SHEET

I HEREBY CERTIFY THAT THE ABOVE AND FOREGOING SITE PLAN FOR A DEVELOPMENT IN THE CITY OF ROCKWALL, TEXAS, WAS APPROVED BY THE PLANNING & ZONING COMMISSION OF THE CITY OF ROCKWALL 220 ELM STREET, SUITE #200 PH: 214.217.2544 LEGAL DESCRIPTION: DIRECTOR OF PLANNING AND ZONING SURVEY: ROCKWALL E. TEAL SURVEY


100 March 100 Ma

 \forall

PLAN TAILS 0 S & SS ШO

04/05/20

TRE



 From:
 Ross, Bethany

 To:
 "Jeff Kilburg | APEX"

 Cc:
 Raquelle Kemnitz | APEX

Subject: RE: Building Elevations - Capps, Morgan, Hodges Date: Wednesday, March 23, 2022 4:45:00 PM

Jeff,

Thanks for the clarification. I got them all sorted out.

Bethany Ross
Planner
City of Rockwall
972.772.6488 Office
bross@rockwall.com
http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Cc: Raquelle Kemnitz | APEX <RaquelleK@apexdesignbuild.net>

Subject: Building Elevations - Capps, Morgan, Hodges

Bethany,

I left you a voicemail, but wanted to follow up on your question regarding the elevations. They elevations correlate to the renderings (taken from the same angle). Because this site does not give a perfect perpendicular approach, it does make it a bit more difficult to look at the elevations. For example:

- Rendering #1 from Summer Lee Drive is summarized by Building Elevation #2 on A1-4.0
- Rendering #2 from Rockwall Pkwy is summarized by Building Elevation #1 on A1-4.0

Hope that helps delineate the elevations a bit better, but please feel free to call or email me!

Thanks,

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | **Main:** 847.288.0100 | **Website:** <u>www.apexdesignbuild.net</u>

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

Facebook | Linkedin | Twitter | Vimeo | Pinterest | Instagram

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Ross, Bethany

From: Ross, Bethany

Sent: Friday, March 25, 2022 12:14 PM

To: Jeff Kilburg (jeffk@apexdesignbuild.net)

Subject: Project Comments: SP2022-009

Attachments: Project Comments (03.25.2022).pdf; Marked Building Elevations (03.24.2022).pdf;

Engineering Markups.pdf

Good Afternoon Jeff,

Attached are the project comments, building elevation markups, and engineering markups for SP2022-009. Please address these comments and have revisions returned to staff by <u>April 5, 2022</u>. The schedule for you case is as follows:

Planning and Zoning Commission Work Session Meeting: March 29, 2022 Planning and Zoning Commission Meeting: April 12, 2022

All meetings will be held at 6:00 PM in the City Council Chambers of City Hall at 385 S. Goliad Street. Please note that a representative will need to be present. If you have any additional questions please let us know. Thanks.

Bethany Ross
Planner
City of Rockwall
972.772.6488 Office
bross@rockwall.com
http://www.rockwall.com/planning/

From: Ross, Bethany
To: "Jeff Kilburg | APEX"

 Subject:
 RE: Project Comments: SP2022-009

 Date:
 Tuesday, March 29, 2022 9:27:00 AM

Great! See you then.

Bethany Ross

Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Tuesday, March 29, 2022 8:55 AM **To:** Ross, Bethany

Subject: Re: Project Comments: SP2022-009

Thank you, Bethany! I'll plan on being there.

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | Main: 847.288.0100 | Website:www.apexdesignbuild.net

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018 Facebook | Linkedin | Twitter | Vimeo | Pinterest | Instagram

From: Ross, Bethany < bross@rockwall.com > Sent: Tuesday, March 29, 2022 8:13:14 AM

To: Jeff Kilburg | APEX < <u>jeffk@apexdesignbuild.net</u>>

Subject: RE: Project Comments: SP2022-009

Yes, please attend ARB as well tonight if you can make it at 5 PM.

Thank you!

Bethany Ross

Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Monday, March 28, 2022 5:05 PM

To: Ross, Bethany < bross@rockwall.com > **Subject:** RE: Project Comments: SP2022-009

Bethany,

That is our intent. Both Claymoore and ourselves have begun to adjust drawings, renderings, and elevations. Additionally, can you clarify whether I should be at the ARB tomorrow? I thought that was a requirement, but only noted that P&Z Meeting.

Thanks,

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | **Main:** 847.288.0100 | **Website:** <u>www.apexdesignbuild.net</u>

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

<u>Facebook</u> | <u>Linkedin</u> | <u>Twitter</u> | <u>Vimeo</u> | <u>Pinterest</u> | <u>Instagram</u>

From: Ross, Bethany < bross@rockwall.com > Sent: Monday, March 28, 2022 8:38 AM

To: Jeff Kilburg | APEX < jeffk@apexdesignbuild.net >

Subject: RE: Project Comments: SP2022-009

Good Morning Jeff,

As long as you address all the comments by April 5^{th} , I have no problem with fielding any questions prior.

As for the fire hydrant accessibility – just make sure you have all the existing fire hydrants labeled in your site plan [per my comment M.5 (7)] so that measurements can be confirmed with Ariana.

Please let me know if you have any further questions.

Thanks,
Bethany Ross
Planner
City of Rockwall
972.772.6488 Office
bross@rockwall.com

http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Friday, March 25, 2022 12:30 PM

To: Ross, Bethany
 Subject: RE: Project Comments: SP2022-009

Thank you, Bethany. If there are questions regarding these, should they be addressed on the 29th or prior? **Example: We spoke with Ariana regarding the Fire Lane, and will not need one with the Fire Hydrant accessibility on the site.**

Thanks.

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | **Main:** 847.288.0100 | **Website:** <u>www.apexdesignbuild.net</u>

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

<u>Facebook</u> | <u>Linkedin</u> | <u>Twitter</u> | <u>Vimeo</u> | <u>Pinterest</u> | <u>Instagram</u>

From: Ross, Bethany < bross@rockwall.com > Sent: Friday, March 25, 2022 12:14 PM

To: Jeff Kilburg | APEX < <u>jeffk@apexdesignbuild.net</u>>

Subject: Project Comments: SP2022-009

Good Afternoon Jeff,

Attached are the project comments, building elevation markups, and engineering markups for SP2022-009. Please address these comments and have revisions returned to staff by <u>April 5, 2022</u>. The schedule for you case is as follows:

Planning and Zoning Commission Work Session Meeting: March 29, 2022 Planning and Zoning Commission Meeting: April 12, 2022

All meetings will be held at 6:00 PM in the City Council Chambers of City Hall at 385 S. Goliad Street. Please note that a representative will need to be present. If you have any additional questions please let us know. Thanks.

Bethany Ross
Planner
City of Rockwall
972.772.6488 Office
bross@rockwall.com
http://www.rockwall.com/planning/

This email was scanned by Bitdefender

This email was scanned by Bitdefender	
CAUTION: This email originated from ou or open attachments unless you recognize the	<u> </u>
This email was scanned by Bitdefender	

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

From: Ross, Bethany

To: "Raquelle Kemnitz | APEX"
Cc: Jeff Kilburg | APEX

Subject: RE: Project Comments: SP2022-009 (Rockwall, TX)

Date: Monday, April 4, 2022 1:48:00 PM

Hi Raquelle,

This is just a friendly reminder that digital project comments are due tomorrow by 3:00 PM.

Thank you!

Bethany Ross

Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Raquelle Kemnitz | APEX [mailto:RaquelleK@apexdesignbuild.net]

Cc: Jeff Kilburg | APEX < jeffk@apexdesignbuild.net>; Raquelle Kemnitz | APEX

<RaquelleK@apexdesignbuild.net>

Subject: RE: Project Comments: SP2022-009 (Rockwall, TX)

Hello Bethany –

Thanks so much, we will definitely be sure to have all the physical documents mailed in time for the April 12th meeting.

Have a great rest of your day!

Thank you.

Regards,

Raquelle Kemnitz

Project Coordinator | Apex Design Build

Direct: 708.610.5000 | **Main:** 847.288.0100 | **Website:** <u>www.apexdesignbuild.net</u>

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

<u>Facebook</u> | <u>Linkedin</u> | <u>Twitter</u> | <u>Vimeo</u> | <u>Pinterest</u> | <u>Instagram</u>

From: Ross, Bethany

Sent: Tuesday, March 29, 2022 3:27 PM

To: Raquelle Kemnitz | APEX < <u>Raquelle K@apexdesignbuild.net</u>>

Cc: Jeff Kilburg | APEX < <u>ieffk@apexdesignbuild.net</u>>

Subject: RE: Project Comments: SP2022-009 (Rockwall, TX)

Hi Raquelle,

As long as you have 100% corrected digital copies for your project by April 5th, that is good. It shouldn't take me more than a couple days to review. Just make sure you have your physical copies by the April 12th Planning and Zoning meeting so that we can get those signed and you can move on to the Engineering process.

Thank you,
Bethany Ross
Planner
City of Rockwall
972.772.6488 Office
bross@rockwall.com
http://www.rockwall.com/planning/

From: Raquelle Kemnitz | APEX [mailto:RaquelleK@apexdesignbuild.net]

Sent: Tuesday, March 29, 2022 2:14 PM **To:** Ross, Bethany < bross@rockwall.com >

Cc: Jeff Kilburg | APEX < <u>jeffk@apexdesignbuild.net</u>>

Subject: RE: Project Comments: SP2022-009 (Rockwall, TX)

Hello Bethany -

Thank you very much for your reply! I understand that we will need to first email you digital copies of all the updated plans first before we mail in 2 hard copies.

Only because we will need to plan to mail in the plans from Illinois to be received by 3PM on 04/05, can you please tell me how long you anticipate the digital reviews to take once you have received the digital copies?

Thank you again for your help!

Regards,

Raquelle Kemnitz

Project Coordinator | Apex Design Build

Direct: 708.610.5000 | **Main:** 847.288.0100 | **Website:** <u>www.apexdesignbuild.net</u>

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

From: Ross, Bethany < bross@rockwall.com > Sent: Tuesday, March 29, 2022 1:10 PM

To: Raquelle Kemnitz | APEX < <u>Raquelle K@apexdesignbuild.net</u>>

Cc: Jeff Kilburg | APEX < <u>jeffk@apexdesignbuild.net</u>>

Subject: RE: Project Comments: SP2022-009 (Rockwall, TX)

Good Afternoon Raquelle,

- 1. Send the digital copies to me first and then you can bring the hard copies by whenever we are sure all the comments are addressed.
- 2. No, you do not need to send another copy of the development application.
- 3. You do not need to submit another application fee it is a one-time payment for site plan.

Please let me know if you have any other questions!

Thank you,

Bethany Ross

Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Raquelle Kemnitz | APEX [mailto:RaquelleK@apexdesignbuild.net]

Sent: Tuesday, March 29, 2022 11:52 AM **To:** Ross, Bethany bross@rockwall.com>

Cc: Raquelle Kemnitz | APEX < <u>RaquelleK@apexdesignbuild.net</u>>; Jeff Kilburg | APEX

<jeffk@apexdesignbuild.net>

Subject: RE: Project Comments: SP2022-009 (Rockwall, TX)

Good Morning Bethany -

Thank you again for all of your help during this process. I was hoping to follow up with you regarding some questions I had about the resubmittal process.

- 1. Will you require 2 hard copies and 1 digital copy of all updated plans/documents? And should the digital copies still be sent to Angelica Gomez?
- 2. Will you require another copy of the Development Application?

3. I understand that we will need to submit another application fee when we submit our comment response to your department, however, I was wondering if I could confirm the amount with you. Will we only need to submit \$100 in total when we mail in our updated plans/comment responses? Or is this \$100 per document needing re-reviewing?

Thank you for your time and assistance.

Regards,

Raquelle Kemnitz

Project Coordinator | Apex Design Build

Direct: 708.610.5000 | **Main:** 847.288.0100 | **Website:** <u>www.apexdesignbuild.net</u>

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

<u>Facebook</u> | <u>Linkedin</u> | <u>Twitter</u> | <u>Vimeo</u> | <u>Pinterest</u> | <u>Instagram</u>

From: Ross, Bethany < bross@rockwall.com>
Sent: Monday, March 28, 2022 8:38:11 AM

To: Jeff Kilburg | APEX < <u>jeffk@apexdesignbuild.net</u>>

Subject: RE: Project Comments: SP2022-009

Good Morning Jeff,

As long as you address all the comments by April 5th , I have no problem with fielding any questions prior.

As for the fire hydrant accessibility – just make sure you have all the existing fire hydrants labeled in your site plan [per my comment M.5 (7)] so that measurements can be confirmed with Ariana.

Please let me know if you have any further questions.

Thanks,
Bethany Ross
Planner
City of Rockwall
972.772.6488 Office
bross@rockwall.com

http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Friday, March 25, 2022 12:30 PM **To:** Ross, Bethany < bross@rockwall.com > **Subject:** RE: Project Comments: SP2022-009

Thank you, Bethany. If there are questions regarding these, should they be addressed on the 29th or prior? **Example: We spoke with Ariana regarding the Fire Lane, and will not need one with the Fire Hydrant accessibility on the site.**

Thanks,

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | **Main:** 847.288.0100 | **Website:** <u>www.apexdesignbuild.net</u>

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

<u>Facebook</u> | <u>Linkedin</u> | <u>Twitter</u> | <u>Vimeo</u> | <u>Pinterest</u> | <u>Instagram</u>

From: Ross, Bethany < bross@rockwall.com>
Sent: Friday, March 25, 2022 12:14 PM

To: Jeff Kilburg | APEX < jeffk@apexdesignbuild.net >

Subject: Project Comments: SP2022-009

Good Afternoon Jeff,

Attached are the project comments, building elevation markups, and engineering markups for SP2022-009. Please address these comments and have revisions returned to staff by <u>April 5, 2022</u>. The schedule for you case is as follows:

Planning and Zoning Commission Work Session Meeting: March 29, 2022 Planning and Zoning Commission Meeting: April 12, 2022

All meetings will be held at 6:00 PM in the City Council Chambers of City Hall at 385 S. Goliad Street. Please note that a representative will need to be present. If you have any additional questions please let us know. Thanks.

Bethany Ross
Planner
City of RockwallA
972.772.6488 Office
bross@rockwall.com
http://www.rockwall.com/planning/

This email was scanned by Bitdefender

CAUTION:	This email origina	ated from	outside of	the organi	zation. Do	not click	links
or open attach	ments unless you	recognize	the sender	and know	the conter	nt is safe.	
This email was sca	nned by Bitdefender						
CAUTION.	This amail arigin	atad fram	outside of	the engani	zation Do	not aliak	links
	This email original ments unless you						IIIIKS
or open attach	ments unless you	recognize	the senuer	anu Know	the conte	it is saic.	
This email was sca	nned by Bitdefender						

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

From: Ross, Bethany

To: "Raquelle Kemnitz | APEX"

Subject: RE: Site Plan Review - Comment Responses: SP2022-009

Date: Tuesday, April 5, 2022 3:53:00 PM

Perfect! Sounds great.

Bethany Ross

Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Raquelle Kemnitz | APEX [mailto:RaquelleK@apexdesignbuild.net]

Sent: Tuesday, April 5, 2022 3:54 PM **To:** Ross, Bethany
bross@rockwall.com>

Cc: Raquelle Kemnitz | APEX <RaquelleK@apexdesignbuild.net> **Subject:** RE: Site Plan Review - Comment Responses: SP2022-009

Wonderful, thanks so much Bethany!

Also, Jeff will be working on the required letter and will send as soon as possible.

Have a great rest of your day!

Thank you.

Regards,

Raquelle Kemnitz

Project Coordinator | Apex Design Build

Direct: 708.610.5000 | Main: 847.288.0100 | Website: www.apexdesignbuild.net

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

<u>Facebook</u> | <u>Linkedin</u> | <u>Twitter</u> | <u>Vimeo</u> | <u>Pinterest</u> | <u>Instagram</u>

From: Ross, Bethany < bross@rockwall.com >

Sent: Tuesday, April 5, 2022 3:52 PM

To: Raquelle Kemnitz | APEX <<u>RaquelleK@apexdesignbuild.net</u>> **Subject:** RE: Site Plan Review - Comment Responses: SP2022-009

Raquelle,

You are fine. I will accept it. Thanks for checking in.

Bethany Ross
Planner
City of Rockwall
972.772.6488 Office
bross@rockwall.com
http://www.rockwall.com/planning/

From: Raquelle Kemnitz | APEX [mailto:RaquelleK@apexdesignbuild.net]

Sent: Tuesday, April 5, 2022 3:11 PM **To:** Ross, Bethany < <u>bross@rockwall.com</u>>

Cc: Raquelle Kemnitz | APEX < <u>Raquelle K@apexdesignbuild.net</u>> **Subject:** RE: Site Plan Review - Comment Responses: SP2022-009

Hello Bethany -

Our landscape architect sent us a last minute update saying to replace one of the pages in my previously submitted landscape plans.

Will you let us change that our for the landscape plan included in this email or is it too late?

Also, per our conversation, I will not print out hard copies of these documents until I have heard back from you.

Thank you again for your time and consideration.

Regards,

Raquelle Kemnitz

Project Coordinator | Apex Design Build

Direct: 708.610.5000 | **Main:** 847.288.0100 | **Website:** <u>www.apexdesignbuild.net</u>

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

<u>Facebook</u> | <u>Linkedin</u> | <u>Twitter</u> | <u>Vimeo</u> | <u>Pinterest</u> | <u>Instagram</u>

From: Raquelle Kemnitz | APEX < <u>Raquelle K@apexdesignbuild.net</u>>

Sent: Tuesday, April 5, 2022 2:54 PM **To:** Ross, Bethany <<u>bross@rockwall.com</u>>

Cc: Raquelle Kemnitz | APEX < <u>Raquelle K@apexdesignbuild.net</u>> **Subject:** Site Plan Review - Comment Responses: SP2022-009

Good Afternoon Bethany -

Please find the required comment response documents attached.

- 1. Landscape Plan
- 2. Photometric Calculation
- 3. Site Plan
- 4. Exterior Plan

And just to reconfirm, I do not need to wait to hear back from you to mail in the hard copies of all the attachments correct? And do you only need one copy of each?

Thank you for your time and assistance.

Regards,

Raquelle Kemnitz

Project Coordinator | Apex Design Build

Direct: 708.610.5000 | **Main:** 847.288.0100 | **Website:** <u>www.apexdesignbuild.net</u>

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

<u>Facebook</u> | <u>Linkedin</u> | <u>Twitter</u> | <u>Vimeo</u> | <u>Pinterest</u> | <u>Instagram</u>

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

 From:
 Ross, Bethany

 To:
 "Juan Villagomez | APEX"

 Cc:
 Jeff Kilburg | APEX; Raquelle Kemnitz | APEX

 Cc:
 Jeff Kilburg | APEX; Raquelle Kemnitz

 Subject:
 RE: Revised Drawings

 Date:
 Tuesday, April 5, 2022 1:42:00 PM

Attachments: image004.png

Juan,

Yes on ALL pages of the submittal

Thanks,

Bethany Ross Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Juan Villagomez | APEX [mailto:juanv@apexdesignbuild.net]

Cc: Jeff Kilburg | APEX <jeffk@apexdesignbuild.net>; Raquelle Kemnitz | APEX <RaquelleK@apexdesignbuild.net>

Subject: RE: Revised Drawings

Rethany

Does this signature block need to be on all sheets or just site plan? If all sheets do we need to edit as to say "Elevation" in lieu of "Site" on the elevations sheet and same for other sheets or exactly the same?

SITE PLAN SIGNATURE BLOCK

APPROVED:

I hereby certify that the above and foregoing site plan for a development in the City of Rockwall, Texas, was approved by the Planning & Zoning Commission of the City of Rockwall on the [DAY] day of [MONTH], [YEAR].

WITNESS OUR HANDS, this [DAY] day of [MONTH], [YEAR].

Planning & Zoning Commission, Chairman

Director of Planning and Zoning

Best,

Juan Villagomez

Senior Architectural Designer | Apex Design Build

Direct: 224.717.1470 | Main: 847.288.0100 | Website: www.apexdesignbuild.net Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

Facebook | Linkedin | Twitter | Vimeo | Pinterest | Instagram

From: Ross, Bethany < bross@rockwall.com >

Sent: Tuesday, April 5, 2022 1:01 PM

To: Juan Villagomez | APEX < juanv@apexdesignbuild.net >

 $\textbf{Cc:} \ \mathsf{Jeff Kilburg} \ | \ \mathsf{APEX} < \underline{\mathsf{jeffk@apexdesignbuild.net}} > ; \ \mathsf{Raquelle Kemnitz} \ | \ \mathsf{APEX} < \underline{\mathsf{RaquelleK@apexdesignbuild.net}} > ; \\ \mathsf{APEX} < \underline{\mathsf{Raquelle K@apexdesignbuild.net}} > ; \\ \mathsf{APEX} < \underline{\mathsf{Raquelle K@apexdes$

Subject: RE: Revised Drawings

Juan

See my response below. I can jump on a call to go over any of these.

1. Make sure you are providing all site data information to ALL pages of the submittal in the lower right-hand corner (title block, owner/applicant/surveyor information, Case Number: SP2022-009, Signature block, etc.) Would the title block shown on the pdf attached suffice?. Yes. Not sure what the signature block would be? See Below:

SITE PLAN SIGNATURE BLOCK

APPROVED:

I hereby certify that the above and foregoing site plan for a development in the City of Rockwall, Texas, was approved by the Planning & Zoning Commission of the City of Rockwall on the [DAY] day of [MONTH], [YEAR].

WITNESS OUR HANDS, this [DAY] day of [MONTH], [YEAR].

Planning & Zoning Commission, Chairman

Director of Planning and Zoning

Photometric Plan:


2. On Summer Lee, the maximum light intensity at the property line must be 0.2. Please revise to not exceed maximum light intensity standards. Working on updating the photometrics Sounds good.

Building Elevations:
3. RTU's need to be screened **OR** provide a roof plan and site line study to verify the RTU is not visible from ground level. On sheet A1-4.0 we have these views from both street




3 SOUTHEAST BUILDING EYE LEVEL PERSPECTIVE - SIGHT LINE STUDY

THERE ARE ROOF-MOUNTED HVAC SYSTEMS, WHICH ARE LOCATED CENTRIC TO THE BUILDING'S ROOF DESIGN. THIS EFFECTIVELY ALLOWS FOR THE BUILDING'S PARAPET TO BE OUR MECHANICAL SCREENING SUSTEN WHICH RESULTS IN THE APPROPRIATE CONCEALMENT OF SUCH. THIS CAN BE NOTED WITH BUILDING PERSPECTIVES, AS THESE HAVE BEEN CREATED FROM THE RESPECTIVE STEET-VIEWS AND NEIGHBORING PROPERTIES AROUND THIS PROPOSED BUILDING.




Updated Landscape Plan Working on updating plans Great.

5. Provide updated headlight screening with berm.



Variances:



Please provide a letter with variances and 2 compensatory measures for each variance with your submittal. Noted

Please note that all other departments have not reviewed these updates. Noted

Thanks,

Bethany Ross

Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Juan Villagomez | APEX [mailto:juanv@apexdesignbuild.net]

Sent: Tuesday, April 5, 2022 12:25 PM
To: Ross, Bethany pross@rockwall.com>
Subject: RE: Revised Drawings

Bethany,

See my response below. I can jump on a call to go over any of these.

1. Make sure you are providing all site data information to **ALL** pages of the submittal in the lower right-hand corner (title block, owner/applicant/surveyor information, Case Number: SP2022-009, Signature block, etc.) Would the title block shown on the pdf attached suffice?. Not sure what the signature block would be?

Photometric Plan:

- 2. On Summer Lee, the maximum light intensity at the property line must be 0.2. Please revise to not exceed maximum light intensity standards. Working on updating the photometrics Building Elevations:
 - 3. RTU's need to be screened **OR** provide a roof plan and site line study to verify the RTU is not visible from ground level. On sheet A1-4.0 we have these views from both street sides showing that the RTUS are not visible at eye level.




(3)

SOUTHEAST BUILDING EYE LEVEL PERSPECTIVE - SIGHT LINE STUDY

THERE ARE ROOF-MOUNTED HVAC SYSTEMS, WHICH ARE LOCATED CENTRIC TO THE BUILDING'S ROOF DESIGN. THIS EFFECTIVELY ALLOWS FOR THE BUILDING'S PARAPET TO BE OUR MECHANICAL SCREENING SUSTEN WHICH RESULTS IN THE APPROPRIATE CONCEALMENT OF SUCH. THIS CAN BE NOTED WITH BUILDING PERSPECTIVES, AS THESE HAVE BEEN CREATED FROM THE RESPECTIVE STEET-VIEWS AND NEIGHBORING PROPERTIES AROUND THIS PROPOSED BUILDING.


4. Dumpster enclosure must be self-latching. If it is, just add a short comment about that. Note added.



SELF- LATCHING GATE


Updated Landscape Plan Working on updating plans

5. Provide updated headlight screening with berm.



Variances:

Building Articulation on Secondary Building Facades. Are these variances due to the building elevation not meeting #2



Entrance on Summer lee. Noted

Please provide a letter with variances and 2 compensatory measures for each variance with your submittal. Noted

Please note that all other departments have not reviewed these updates. Noted

Best,

Juan Villagomez

Senior Architectural Designer | Apex Design Build

Direct: 224.717.1470 | Main: 847.288.0100 | Website: www.apexdesignbuild.net Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018 Facebook | Linkedin | Twitter | Vimeo | Pinterest | Instagram

From: Ross, Bethany < bross@rockwall.com > Sent: Tuesday, April 5, 2022 12:05 PM

To: Juan Villagomez | APEX < iuanv@apexdesignbuild.net >

Subject: RE: Revised Drawings

I just got your voicemail about the building articulations. Apologies, I was away from my desk.

Our standards are listed in Subsection 04.01.C2 of Article 05 in our Unified Development Code (Page 70 of the PDF [Figure 7]).

The raised parapets meet what the Architecture Review Board suggested but you still need to ask for a variance on the articulation for the two secondary facades: (North and West).

I'm headed to lunch but I'll be back at 1 and can discuss any other questions you have.

Thanks,

Bethany Ross

Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Tuesday, April 5, 2022 10:57 AM To: Ross, Bethany

bross@rockwall.com>

Cc: Juan Villagomez | APEX < juanv@apexdesignbuild.net>; Raquelle Kemnitz | APEX < RaquelleK@apexdesignbuild.net>; Drew Donosky < drew@claymooreeng.com>

Subject: Re: Revised Drawings

Thank you, Bethany. We'll try to get these revisions made.

Jeff Kilburg

Preconstruction Manager | Apex Design Build Direct: 630.596.3764 | Main: 847.288.0100 | Website:www.apexdesignbuild.net

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018 Facebook | Linkedin | Twitter | Vimeo | Pinterest | Instagram

From: Ross, Bethany < bross@rockwall.com >

Sent: Tuesday, April 5, 2022 10:32:25 AM

To: Jeff Kilburg | APEX < jeffk@apexdesignbuild.net >

Cc: Juan Villagomez | APEX < juanv@apexdesignbuild.net >; Raquelle Kemnitz | APEX < RaquelleK@apexdesignbuild.net >

Subject: RE: Revised Drawings

Hi Jeff.

Thank you. Sure.


1. Make sure you are providing all site data information to **ALL** pages of the submittal in the lower right-hand corner (title block, owner/applicant/surveyor information, Case Number: SP2022-009, Signature block, etc.)

Photometric Plan:

- 2. On Summer Lee, the maximum light intensity at the property line must be 0.2. Please revise to not exceed maximum light intensity standards. Building Elevations:
 - 3. RTU's need to be screened **OR** provide a roof plan and site line study to verify the RTU is not visible from ground level.
 - 4. Dumpster enclosure must be self-latching. If it is, just add a short comment about that.

Updated Landscape Plan

5. Provide updated headlight screening with berm.



Variances:

- Building Articulation on Secondary Building Facades.
- Entrance on Summer lee.

Please provide a letter with variances and 2 compensatory measures for each variance with your submittal.

Please note that all other departments have not reviewed these updates.

Thanks, Bethany Ross

Planner

City of Rockwall 972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Tuesday, April 5, 2022 9:44 AM **To:** Ross, Bethany < <u>bross@rockwall.com</u>>

Cc: Juan Villagomez | APEX < juanv@apexdesignbuild.net >; Raquelle Kemnitz | APEX < RaquelleK@apexdesignbuild.net >

Subject: RE: Revised Drawings

 $\label{thm:condition} \mbox{And just to be clear, we're merely looking for feedback prior to resubmission this afternoon!}$

Thank you again,

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | Main: 847.288.0100 | Website: www.apexdesignbuild.net
Address: 9550 W. Higgins Road, Ste 170, Rosemont, II. 60018
Facebook | Linkedin | Twitter | Vimeo | Pinterest | Instagram

From: Jeff Kilburg | APEX

Sent: Tuesday, April 5, 2022 9:41 AM
To: 'Ross, Bethany' < bross@rockwall.com>

Cc: Juan Villagomez | APEX < <u>juanv@apexdesignbuild.net</u>>; Raquelle Kemnitz | APEX < <u>RaquelleK@apexdesignbuild.net</u>>

Subject: RE: Revised Drawings

Bethany,

Please see the attached revisions from Landscaping.

Thanks,

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Sent: Monday, April 4, 2022 5:44 PM
To: 'Ross, Bethany' <<u>bross@rockwall.com</u>>

Cc: Juan Villagomez | APEX <<u>juany@apexdesignbuild.net</u>>; Raquelle Kemnitz | APEX <<u>RaquelleK@apexdesignbuild.net</u>>; 'Drew Donosky' <<u>drew@claymooreeng.com</u>>

Subject: Revised Drawings

Bethany,

I hope you're doing well and had an enjoyable weekend! I wanted to follow up with pertinent revisions to get a cursory review prior to submitting these tomorrow. Attached you will find the Architectural Elevations, Renderings, Photometrics, and Site Plan (Landscaping Plans are forthcoming). We have reviewed all pertinent comments, and have thus reduced our variances as a result. Our intention is to only submit for a single variance, which is associated with the entrance off of Summer Lee Dr.

Thanks.

Jeff Kilburg Preconstruction Manager Apex Design Build			
Direct: 630.596.3764 Main: 847.288.0100 Website: www.apexdesignbuild.net Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018 Facebook Linkedin Twitter Vimeo Pinterest Instagram			

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

This email was scanned by Bitdefender

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe,

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe,

From: Ross, Bethany
To: Jeff Kilburg | APEX

Cc: Juan Villagomez | APEX; Raquelle Kemnitz | APEX

Subject: Re: Response Letter and Cut Sheets

Date: Wednesday, April 6, 2022 6:09:39 PM

Perfect. Thanks, Jeff.

Bethany Ross

Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX < jeffk@apexdesignbuild.net>

Cc: Juan Villagomez | APEX < juanv@apexdesignbuild.net>; Raquelle Kemnitz | APEX

<RaquelleK@apexdesignbuild.net>

Subject: RE: Response Letter and Cut Sheets

Bethany,

Please see the revisions you requested earlier. Thank you again for the productive feedback!

Thanks,

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | **Main:** 847.288.0100 | **Website:** <u>www.apexdesignbuild.net</u>

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

<u>Facebook</u> | <u>Linkedin</u> | <u>Twitter</u> | <u>Vimeo</u> | <u>Pinterest</u> | <u>Instagram</u>

To: Jeff Kilburg | APEX < jeffk@apexdesignbuild.net>

Cc: Juan Villagomez | APEX < juanv@apexdesignbuild.net>; Raquelle Kemnitz | APEX

<RaquelleK@apexdesignbuild.net>

Subject: RE: Response Letter and Cut Sheets

Great! Thank you.

Bethany Ross
Planner
City of Rockwall
972.772.6488 Office
bross@rockwall.com
http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Wednesday, April 6, 2022 11:59 AM **To:** Ross, Bethany <<u>bross@rockwall.com</u>>

Cc: Juan Villagomez | APEX < <u>juanv@apexdesignbuild.net</u>>; Raquelle Kemnitz | APEX

< Raquelle K@apexdesign build.net >

Subject: Re: Response Letter and Cut Sheets

Sounds good, Bethany. I'll update and resend this evening! Appreciate your feedback.

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | Main: 847.288.0100 | Website:www.apexdesignbuild.net

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018 Facebook | Linkedin | Twitter | Vimeo | Pinterest | Instagram

From: Ross, Bethany < bross@rockwall.com > Sent: Wednesday, April 6, 2022 11:57 AM

To: Jeff Kilburg | APEX < <u>ieffk@apexdesignbuild.net</u>>

Cc: Juan Villagomez | APEX < <u>juanv@apexdesignbuild.net</u>>; Raquelle Kemnitz | APEX

<RaquelleK@apexdesignbuild.net>

Subject: RE: Response Letter and Cut Sheets

Hi Jeff,

I understand your concern about the Summer Lee Drive exception but it is still an exception that still needs 2 compensatory measures per our code and engineering.

You can easily compensate since you **already have** [1] three (3) extra canopy trees along Rockwall Parkway and [2] three (3) extra canopy trees along Summer Lee Drive shown on your landscape plan - just add that to your letter, please.

Thanks,
Bethany Ross
Planner
City of Rockwall
972.772.6488 Office
bross@rockwall.com

http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Tuesday, April 5, 2022 5:16 PM **To:** Ross, Bethany < bross@rockwall.com >

Cc: Juan Villagomez | APEX < <u>juanv@apexdesignbuild.net</u>>; Raquelle Kemnitz | APEX

< <u>RaquelleK@apexdesignbuild.net</u>> **Subject:** Response Letter and Cut Sheets

Bethany,

In our haste to make revisions, one item which was not sent through were the Cut Sheets for the respective fixtures at the poles/building on the Exterior. I have included those for reference, and I apologize for the delay on those as I was not at the office during the afternoon correspondence. Additionally, you will find the aforementioned prepared Response Letter addressing not only the Exceptions, but also the prior comments as well. We appreciate your help and feedback on this project and thank you for your flexibility and time as well!

Thank you,

Jeff Kilburg Preconstruction Manager Apex Design Build
Direct: 630.596.3764 Main: 847.288.0100 Website: www.apexdesignbuild.net Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018 Facebook Linkedin Twitter Vimeo Pinterest Instagram
This email was scanned by Bitdefender
CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.
This email was scanned by Bitdefender

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

CAUTION: This email originated from outside of the organization. Do not click links

or open attachments unless you recognize the sender and know the content is safe.

From: Ross, Bethany

To: "Raquelle Kemnitz | APEX"

Subject: RE: Response Letter and Cut Sheets: SP2022-009

Date: Friday, April 8, 2022 9:32:00 AM

Thanks! You too!

Bethany Ross Planner City of Rockwall 972.772.6488 Office bross@rockwall.com

http://www.rockwall.com/planning/

----Original Message-----

From: Raquelle Kemnitz | APEX [mailto:RaquelleK@apexdesignbuild.net]

Sent: Friday, April 8, 2022 9:32 AM To: Ross, Bethany bross@rockwall.com

Cc: Raquelle Kemnitz | APEX < Raquelle K@apexdesignbuild.net>

Subject: RE: Response Letter and Cut Sheets: SP2022-009

Wonderful, thanks so much!!

I hope you have a great weekend!

Thank you.

Regards,

Raquelle Kemnitz

Project Coordinator | Apex Design Build

Direct: 708.610.5000 | Main: 847.288.0100 | Website: www.apexdesignbuild.net

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

Facebook | Linkedin | Twitter | Vimeo | Pinterest | Instagram

----Original Message-----

Sent: Friday, April 8, 2022 9:30 AM

To: Raquelle Kemnitz | APEX < Raquelle K@apexdesignbuild.net>

Subject: RE: Response Letter and Cut Sheets: SP2022-009

Good Morning Raquelle,

Yes, one copy of each is great.

- 1. Site Plan
- 2. Building Elevations
- 3. Landscape Plan
- 4. Treescape Plan
- 5. Photometric Plan

Thank you!

Bethany Ross

Planner City of Rockwall 972.772.6488 Office bross@rockwall.com http://www.rockwall.com/planning/

----Original Message-----

From: Raquelle Kemnitz | APEX [mailto:RaquelleK@apexdesignbuild.net]

Sent: Friday, April 8, 2022 9:23 AM To: Ross, Bethany bross@rockwall.com

Cc: Raquelle Kemnitz | APEX < Raquelle K@apexdesignbuild.net>

Subject: RE: Response Letter and Cut Sheets: SP2022-009

Good Morning Bethany -

Thank you again with your help this week with our comment responses, we really appreciate your time.

I was hoping to follow up this morning to ask if it would be alright for me to print out all the submitted comment responses for the meeting on April 12th.

Also, can you confirm that we will only need to provide 1 copy of each document/plans when we arrive for the meeting?

Thank you for all of your assistance!

Regards, Raquelle Kemnitz Project Coordinator | Apex Design Build

Direct: 708.610.5000 | Main: 847.288.0100 | Website: www.apexdesignbuild.net

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

Facebook | Linkedin | Twitter | Vimeo | Pinterest | Instagram

----Original Message----

From: Ross, Bethany
 sons@rockwall.com> Sent: Wednesday, April 6, 2022 6:10 PM

To: Jeff Kilburg | APEX < jeffk@apexdesignbuild.net>

Cc: Juan Villagomez | APEX < juanv@apexdesignbuild.net>; Raquelle Kemnitz | APEX

< Raquelle K@apexdesign build.net>

Subject: Re: Response Letter and Cut Sheets

Perfect. Thanks, Jeff.

Bethany Ross

Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com<mailto:bross@rockwall.com>

http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX < jeffk@apexdesignbuild.net>

Sent: Wednesday, April 6, 2022 5:10 PM To: Ross, Bethany bross@rockwall.com

Cc: Juan Villagomez | APEX < juanv@apexdesignbuild.net>; Raquelle Kemnitz | APEX

<RaquelleK@apexdesignbuild.net>

Subject: RE: Response Letter and Cut Sheets

Bethany,

Please see the revisions you requested earlier. Thank you again for the productive feedback!

Thanks,

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | Main: 847.288.0100 | Website: www.apexdesignbuild.net

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018 Facebookhttps://www.facebook.com/APEXDesignBuild.Net/

Linkedinhttps://www.linkedin.com/company/apex-design-build/ | Twitterhttps://twitter.com/APEXDB |

Vimeo<https://vimeo.com/user88423282 | Pinteresthttps://www.pinterest.com/apexdesignus/pins/> |

Instagram<https://www.instagram.com/apex_design_build/

From: Ross, Bethany
 Sent: Wednesday, April 6, 2022 1:20 PM

To: Jeff Kilburg | APEX <jeffk@apexdesignbuild.net>

Cc: Juan Villagomez | APEX < juanv@apexdesignbuild.net>; Raquelle Kemnitz | APEX

<RaquelleK@apexdesignbuild.net>

Subject: RE: Response Letter and Cut Sheets

Great! Thank you.

Bethany Ross
Planner
City of Rockwall
972.772.6488 Office
bross@rockwall.com<mailto:bross@rockwall.com>
http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Wednesday, April 6, 2022 11:59 AM

To: Ross, Bethany bross@rockwall.com>>

Cc: Juan Villagomez | APEX < juanv@apexdesignbuild.net < mailto: juanv@apexdesignbuild.net >>; Raquelle

Kemnitz | APEX <RaquelleK@apexdesignbuild.net<<u>mailto:RaquelleK@apexdesignbuild.net</u>>>

Subject: Re: Response Letter and Cut Sheets

Sounds good, Bethany. I'll update and resend this evening! Appreciate your feedback.

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | Main: 847.288.0100 | Website:www.apexdesignbuild.net

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018 Facebook | Linkedin | Twitter | Vimeo | Pinterest |

Instagram

From: Ross, Bethany bross@rockwall.com>>

Sent: Wednesday, April 6, 2022 11:57 AM

To: Jeff Kilburg | APEX < jeffk@apexdesignbuild.net < mailto:jeffk@apexdesignbuild.net >>

Ce: Juan Villagomez | APEX < juanv@apexdesignbuild.net < <u>mailto:juanv@apexdesignbuild.net</u> >>; Raquelle

Kemnitz | APEX <RaquelleK@apexdesignbuild.net<mailto:RaquelleK@apexdesignbuild.net>>

Subject: RE: Response Letter and Cut Sheets

Hi Jeff,

I understand your concern about the Summer Lee Drive exception but it is still an exception that still needs 2 compensatory measures per our code and engineering.

You can easily compensate since you already have [1] three (3) extra canopy trees along Rockwall Parkway and [2] three (3) extra canopy trees along Summer Lee Drive shown on your landscape plan - just add that to your letter, please.

Thanks,
Bethany Ross
Planner
City of Rockwall
972.772.6488 Office
bross@rockwall.com<mailto:bross@rockwall.com>
http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Tuesday, April 5, 2022 5:16 PM

To: Ross, Bethany bross@rockwall.com>>

Cc: Juan Villagomez | APEX < juanv@apexdesignbuild.net < mailto: juanv@apexdesignbuild.net >>; Raquelle

Kemnitz | APEX <RaquelleK@apexdesignbuild.net<mailto:RaquelleK@apexdesignbuild.net>>

Subject: Response Letter and Cut Sheets

Bethany,

In our haste to make revisions, one item which was not sent through were the Cut Sheets for the respective fixtures at the poles/building on the Exterior. I have included those for reference, and I apologize for the delay on those as I was not at the office during the afternoon correspondence. Additionally, you will find the aforementioned prepared Response Letter addressing not only the Exceptions, but also the prior comments as well. We appreciate your help and feedback on this project and thank you for your flexibility and time as well!

Thank you,

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | Main: 847.288.0100 | Website: www.apexdesignbuild.net

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018 Facebookhttps://www.facebook.com/APEXDesignBuild.Net/

Linkedinhttps://www.linkedin.com/company/apex-design-build/ | Twitterhttps://twitter.com/APEXDB |

Vimeohttps://vimeo.com/user88423282 | Pinteresthttps://www.pinterest.com/apexdesignus/pins/ |

Instagram<https://www.instagram.com/apex_design_build/

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

From: Ross, Bethany
To: "Jeff Kilburg | APEX"
Subject: RE: Engineering Submittal

Date: Monday, April 11, 2022 2:41:00 PM

Jeff,

As long as you feel you answered ARBs concerns, P&Z should follow suit and approve.

Thanks,

Bethany Ross

Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Monday, April 11, 2022 2:26 PM **To:** Ross, Bethany
bross@rockwall.com>

Subject: RE: Engineering Submittal

Thank you, Bethany. Appreciate the feedback!

In your eyes, is there anything we're missing which will prevent approval for our Site Plan, Building Elevations/Renderings tomorrow?

Thanks,

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | **Main:** 847.288.0100 | **Website:** <u>www.apexdesignbuild.net</u>

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

<u>Facebook</u> | <u>Linkedin</u> | <u>Twitter</u> | <u>Vimeo</u> | <u>Pinterest</u> | <u>Instagram</u>

From: Ross, Bethany <<u>bross@rockwall.com</u>>

Sent: Monday, April 11, 2022 2:22 PM

To: Jeff Kilburg | APEX < <u>jeffk@apexdesignbuild.net</u>>

Subject: RE: Engineering Submittal

Hi Jeff,

You are correct, it will just set your timeline back a couple weeks. It will not affect our processes.

Thanks,
Bethany Ross
Planner
City of Rockwall
972.772.6488 Office
bross@rockwall.com
http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Monday, April 11, 2022 1:52 PM **To:** Ross, Bethany <<u>bross@rockwall.com</u>>

Cc: Raquelle Kemnitz | APEX < <u>Raquelle K@apexdesignbuild.net</u>>

Subject: Engineering Submittal

Bethany,

I just spoke with Drew Donosky from Claymoore Engineering, and he informed me that the timing for their completed Engineering Submittal will likely fall around 5/11, best case scenario. This is due to current projected workload and their Team availability. Does this impact our process with Rockwall at all beyond the fact that it pushes our timeline back by roughly (2) weeks?

Thanks.

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | **Main:** 847.288.0100 | **Website:** <u>www.apexdesignbuild.net</u>

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

<u>Facebook</u> | <u>Linkedin</u> | <u>Twitter</u> | <u>Vimeo</u> | <u>Pinterest</u> | <u>Instagram</u>

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

This email was scanned by Bitdefender

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

From: Ross, Bethany
To: "Jeff Kilburg | APEX"

Subject: RE: ARB

Date: Tuesday, April 12, 2022 8:23:00 AM

Great! See you then.

Bethany Ross

Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Subject: Re: ARB

Sounds good. I'll be in the audience! If you or anyone else has questions, please feel free to come and grab me.

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | Main: 847.288.0100 | Website:www.apexdesignbuild.net

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018 Facebook | Linkedin | Twitter | Vimeo | Pinterest | Instagram

From: Ross, Bethany < bross@rockwall.com > Sent: Tuesday, April 12, 2022 8:16:01 AM

To: Jeff Kilburg | APEX < <u>ieffk@apexdesignbuild.net</u>>

Subject: RE: ARB

Yes.

Bethany Ross

Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Tuesday, April 12, 2022 8:02 AM

To: Ross, Bethany < bross@rockwall.com > Subject: ARB
Bethany,
The ARB Meets today at 5pm, correct?
Thanks,
Jeff Kilburg Preconstruction Manager Apex Design Build Direct: 630.596.3764 Main: 847.288.0100 Website:www.apexdesignbuild.net Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018 Facebook Linkedin Twitter Vimeo Pinterest Instagram
This email was scanned by Bitdefender
CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

This email was scanned by Bitdefender

From: Ross, Bethany
To: "Jeff Kilburg | APEX"

Cc: Raquelle Kemnitz | APEX; Juan Villagomez | APEX

Subject: RE: Next City Meetings

Date: Wednesday, April 13, 2022 8:19:00 AM

Good Morning Jeff,

Site Plans do not need to go to City Council. You just need to get the revisions to the elevations with the screened parapets before you submit for the engineering process.

Thanks,

Bethany Ross

Planner

City of Rockwall

972.772.6488 Office

bross@rockwall.com

http://www.rockwall.com/planning/

From: Jeff Kilburg | APEX [mailto:jeffk@apexdesignbuild.net]

Sent: Wednesday, April 13, 2022 7:39 AM **To:** Ross, Bethany

cbross@rockwall.com>

Cc: Raquelle Kemnitz | APEX <RaquelleK@apexdesignbuild.net>; Juan Villagomez | APEX

<juanv@apexdesignbuild.net>
Subject: Next City Meetings

Bethany,

Thank you again for your help through the Rockwall process last night, and proactive feedback. I wanted to see if we are required to be present at the City Council Meeting now that this has been approved by P&Z based on the conditional approval from the ARB. As well, when would you like to see revisions of the elevations for the parapet height?

Thank you in advance,

Jeff Kilburg

Preconstruction Manager | Apex Design Build

Direct: 630.596.3764 | Main: 847.288.0100 | Website: www.apexdesignbuild.net

Address: 9550 W. Higgins Road, Ste 170, Rosemont, IL 60018

<u>Facebook</u> | <u>Linkedin</u> | <u>Twitter</u> | <u>Vimeo</u> | <u>Pinterest</u> | <u>Instagram</u>

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.